

FINAL REPORT  
FINDING OF SUITABILITY FOR TRANSFER (FOST)

For the

VETERANS AFFAIRS MEDICAL CENTER  
GULFPORT, MISSISSIPPI  
SOUTH PARCEL



February 26, 2009

*Prepared for:*

The United States Department of Veterans Affairs

## TABLE OF CONTENTS

### EXECUTIVE SUMMARY

<b>1.0 INTRODUCTION .....</b>	<b>1</b>
<b>2.0 LOCATION AND LEGAL DESCRIPTION .....</b>	<b>2</b>
<b>3.0 BACKGROUND .....</b>	<b>3</b>
<b>4.0 CITY OF GULFPORT REUSE PLAN.....</b>	<b>6</b>
<b>5.0 ENVIRONMENTAL CONDITIONS.....</b>	<b>7</b>
5.1 Solid Waste .....	7
5.2 Underground and Aboveground Fuel Storage Tanks .....	7
5.3 Polychlorinated Biphenyls .....	9
5.3.1 Fluorescent Light Ballasts.....	9
5.3.2 Transformers .....	9
5.4 Asbestos .....	10
5.4.1 Building 1 ACM .....	10
5.4.2 Building 2 ACM .....	10
5.4.3 Building 3 ACM .....	11
5.4.4 Building 4 ACM .....	11
5.4.5 Building 5 ACM .....	12
5.4.6 Building 41 ACM .....	13
5.4.7 Building 57.....	13
5.4.8 Building 62.....	14
5.4.9 Building 63.....	14
5.4.10 Building 64.....	15
5.5 Lead Based Paint and Lead in Building Materials.....	16
5.5.1 Building #1, LBP and Lead in Building Materials .....	16
5.5.2 Building #2, LBP and Lead in Building Materials .....	17
5.5.3 Building #3, LBP and Lead in Building Materials .....	17
5.5.4 Building #4, LBP and Lead in Building Materials .....	18
5.5.5 Building #5, LBP and Lead in Building Materials .....	19
5.5.6 Building #41, LBP and Lead in Building Materials .....	19
5.5.7 Building #57, LBP and Lead in Building Materials .....	20
5.5.8 Building #62, LBP and Lead in Building Materials .....	20
5.5.9 Building #63, LBP and Lead in Building Materials .....	21
5.5.10 Building #64, LBP and Lead in Building Materials .....	22
5.5.11 Lead in Soil .....	22
<b>6.0 SOIL AND GROUNDWATER CONDITIONS .....</b>	<b>24</b>
6.1 Soil Conditions.....	24
6.2 Groundwater Conditions.....	25
<b>7.0 CONCLUSIONS .....</b>	<b>26</b>

## TABLES

TABLE ONE  
TABLE TWO

ASBESTOS REMAINING, UPDATE SURVEY  
LEAD BASED PAINT and LEAD IN BUILDING  
MATERIALS REMAINING, UPDATE SURVEY

## FIGURES

BUILDING 1  
BUILDING 2  
BUILDING 3  
BUILDING 4  
BUILDING 5  
BUILDING 41  
BUILDING 57  
BUILDING 62  
BUILDING 64

SOIL SAMPLE LOCATIONS  
SOIL SAMPLE LOCATIONS

## ATTACHMENTS

ATTACHMENT 1  
ATTACHMENT 2  
ATTACHMENT 3  
ATTACHMENT 4  
ATTACHMENT 5  
  
ATTACHMENT 6  
ATTACHMENT 7  
  
ATTACHMENT 8  
  
ATTACHMENT 9  
ATTACHMENT 10

VA Gulfport Mississippi, Building Schedule Drawing  
Legal Description  
VA Electrical Utility Plan  
AMI Certificate of Final Inspection  
AMI Environmental, Lead Survey on Disc, Lead Survey  
Sheets  
Demolition Permits  
MDEQ Underground Storage Tank Closure Letter and  
Laboratory Analysis Summary Sheets  
OHC Environmental Engineering Soil and Groundwater  
Laboratory Analysis Summary Tables  
MDEQ Brownfield Target Remediation Goals  
OHC Soil and Groundwater Remediation Specifications

## EXECUTIVE SUMMARY

The Veterans Affairs Medical Center (VA) property located at 200 East Beach Boulevard, Gulfport, Harrison County, Mississippi is in the process of a transfer of the property from the United States Department of Veteran Affairs to the City of Gulfport, Mississippi. The property has approximately 86 acres in two (2) parcels separated by Railroad Avenue. This Finding of Suitability for Transfer (FOST) Final Report is for the south parcel, located south of Railroad Avenue and borders gulf coast U.S. Highway 90. This south parcel consists of approximately 43 acres. This Final FOST Report has been prepared based on the review of the references noted and an on-site review on October 31-November 3, 2008 by a PEMC Co., LLC environmental professional.

The future use of the property by the City of Gulfport has not been provided to the VA or its contractors. Therefore remediation levels were based on the Mississippi Department of Environmental Quality (MDEQ) Brownfields Target Remediation Goals for residential unrestricted use. The VA has commitments to conduct remediation activities prior to transfer. Upon completion of the VA commitments specified in this Final FOST Report, the facility south parcel will be suitable for transfer. The Final FOST Report can be prepared after all VA commitments are complete and documentation provided.

The FOST has been prepared for environmental considerations only. The FOST is not intended to address structural integrity of the buildings, the grading of the grounds, the underground utilities or aesthetic considerations of the buildings or grounds.

## 1.0 INTRODUCTION

The United States (U.S.) Department of Veteran Affairs has entered into an agreement to transfer the Veterans Affairs Facility in Gulfport, Mississippi (VA) to the City of Gulfport, Mississippi. The facility to be transferred comprises of two (2) parcels of property separated by East Railroad Street. This Finding of Suitability for Transfer (FOST) is for the south parcel. A drawing of the VA Gulfport, Mississippi, Pre-Hurricane Katrina Building Schedule is presented in Attachment 1. A limited number of these buildings will be transferred to the City of Gulfport.

The FOST is intended to identify environmental issues at the facility and address the remedial activities that have been conducted or are necessary to bring them to the established compliance levels. The environmental issues have been identified and summarized below for the buildings scheduled to be transferred. The demolished buildings have not been presented since the associated environmental issues have been removed with the building materials. The VA commits to the remediation or the mitigation of the environmental conditions identified. Mitigation will include complete remediation of the environmental condition to the most stringent action levels. The regulatory standards to be used include:

- Mississippi Department of Environmental Quality, Brownfields Target Remediation Goals (TRGs) for Unrestricted Residential Use for soil and groundwater contamination. The Brownfields TRGs have been included in Attachment 8.
- Mississippi Department of Environmental Quality Underground Storage Tank Regulations for petroleum product storage.
- U.S. Housing and Urban Development (HUD) standards for lead based paint and lead in soils around housing/buildings.
- NESHAP 40 CFR 61 Subpart M, Emissions standards for asbestos containing materials in buildings.

Deviations from mitigation of the environmental conditions identified to the above-referenced standards will be clearly expressed with this report. The environmental concerns for the buildings have been limited to the buildings to remain and be transferred to the City of Gulfport, Mississippi.

The FOST has been prepared for environmental concerns only. The FOST does not address structural integrity or condition, utility service condition, maintenance or aesthetic condition.

## 2.0 LOCATION AND LEGAL DESCRIPTION

The VA, Gulfport is located at 200 East Beach Boulevard (U.S. Highway 90), Gulfport, Harrison County, Mississippi, approximately three (3) miles east of U.S. Highway 49. The southern end of the main facility borders U.S. Highway 90 which is an east-west highway along the Gulf of Mexico coast line. The VA facility is split into two (2) parcels, a south parcel consisting of approximately 48.06 acres (the subject of this FOST Report), and a north parcel consisting of 37.9 acres (the FOST North Parcel Report has been previously submitted). This FOST is specifically for the environmental considerations of the south parcel.

The VA is located approximately 2.9 miles east of the center of the intersection of U.S. Highway 90 and Mississippi Highway 49. The facility south parcel is located north of East Beach Boulevard, and south of the Louisiana and Nashville (CSX) Railroad line which borders the south parcel northern property line. The entrances onto the south parcel include vehicle entrances off East Beach Boulevard, and from the north end off Railroad Street in the northeast section of the facility. One pedestrian tunnel entrance is located next to the north vehicle entrance. The tunnel runs under the railroad and Railroad Street and emerges at the VA north parcel.

The legal description of the south parcel is shown in Attachment 2.

### 3.0 BACKGROUND

The VA was originally occupied by the Mississippi Gulf Coast Exhibition and converted to a Naval Training Base in 1917. In 1919 the property was developed into a Veterans Hospital. The date of construction of each individual building is not known from the information reviewed.

The south parcel had 30 buildings/structures, an elevated water tank and pump station, the flag pole, an aboveground storage tank (AST), and underground storage tanks (USTs) at seven (7) locations prior to Hurricane Katrina. In the northeast corner of the property is a telecommunications building which is not owned by the VA and is not included in the facility buildings scheduled to be transferred. The VA buildings and corresponding building numbers are listed below:

BUILDING No.	BUILDING DESIGNATION
1	Medical Administration, Clinics & Psychiatric Wards
2	Kitchen, Dining, and Administration Offices, northern ½ of building has been removed.
3	Psychiatry Service Wards
4	Psychiatry Service Wards
5	Psychiatry Service Wards
6	Boiler Plant, Previously Abandoned and Building Destroyed
32	Engineering Shops, Building Destroyed
33	Engineering Shops and Office, Building Destroyed
37	Flag Pole
40	Buildings Management, Employee Locker Room, Building Destroyed
41	Psychiatry Service Wards
42	Security Police Office, Building Destroyed
43	3-Car Garage, Building Destroyed
44	4-Car Garage, Building Destroyed
45	Engineering Material Storage, Building Destroyed
49	Aboveground Fuel Storage Tank, Previously Removed
50	Engineering Equipment Storage, Building Destroyed
51-56	Staff Quarters, Buildings Destroyed
57	Psychiatry Service Wards
58	Pavilion, Structure Destroyed
59	Engineering Storage, Building Destroyed
60	Warehouse, Building Destroyed
61	Building Management Storage, Building Destroyed
62	Psychiatry Service Wards
63	Chapel
64	Mental Health O.P.C. & Administration Offices
76	Therapeutic Exercise Clinic, Building Destroyed
113	Building Management Storage, Building Destroyed

117	Vocational Rehabilitation Clinics, Building Destroyed
118	Elevated Water Tank
119	Special Activities Building, Building Destroyed
602	Greenhouse, Building Destroyed
664	Fuel Storage Tanks, previously abandoned, Removed

On August 29, 2005 Hurricane Katrina hit the Mississippi gulf coast. The coastal flooding reached storm surge heights of 25-28 feet above normal tide level based on the NOAA Coastal Services Center. As a result, most of the VA buildings and structures in place at the time were severely damaged and/or destroyed and subsequently removed.

As of the date of this report 10 buildings, the elevated water tower and the flag pole remain on the property. These remaining buildings scheduled for the facility transfer include; Buildings #1, #2-southern ½ only, #3, #4, #5, #41, #57, #62, #63, and #64.

The environmental conditions and concerns of the VA facility-south parcel have been identified by AMI Environmental (AMI) and OHC Environmental Engineering (OHC). AMI conducted the environmental assessment of the buildings for asbestos and lead based paint, and lead in soil around the buildings.

AMI conducted an initial survey of the buildings for asbestos containing material was conducted in October 2006, and summarized it in a report. The 2006 initial sampling results can be found on the disc in Attachment 4. Reinspection of the remaining buildings, which are scheduled for transfer, was conducted by AMI in April 2008.

AMI conducted an initial lead based paint and lead containing building materials in October 2006. The lead survey was summarized with the asbestos report and can be found on the disc in Attachment 4. Soil samples were collected around each of the remaining buildings and analyzed for lead in April 2008. The results were summarized in the AMI report dated August 1, 2008 and can be found in Attachment 5. Figures of the lead sampling points for each building have been provided.

OHC conducted a review of the site for hazardous materials, underground storage tanks, and other areas with potential contaminants of concern on the facility. A summary of the OHC findings was presented in the OHC Environmental Engineering "Interim Assessment Report" V.A. Medical Center, October 24, 2007. This report has been submitted and is on file with the VA. Subsequent soil and groundwater sampling events have been conducted by OHC. The OHC "Soil and Groundwater Sampling Report Parts I-IV" have been submitted and are on file with the VA. OHC has prepared remediation specifications to conduct the remediation of existing soil and groundwater contamination above the most stringent levels referenced above. The OHC laboratory analysis summary tables can be found in Attachment 8 and remediation specifications in Attachment 10.

OHC has contacted the MDEQ regarding the arsenic in soil and is preparing a statistical analysis assessment that the existing levels do not exceed background levels. This statistical analysis assessment will be submitted to the MDEQ for approval.

The underground storage tanks in place immediately before and after the Hurricane Katrina devastation have been removed by Mitigation Services, Inc. in August 2008. In August 2008, a UST Closure report was submitted to the MDEQ summarizing the required UST soil sampling results. The MDEQ has reviewed the sampling results and has provided a letter dated October 20, 2008 that the concentrations do not pose a current or potential threat to human health or the environment and no further action is required. The MDEQ UST response letter and the associated UST closure sheets and laboratory data sheets can be found in Attachment 7.

## 4.0 CITY OF GULFPORT REUSE PLAN

The City of Gulfport has not informed the VA about the plans for redevelopment of the facility.

The City of Gulfport is unable to define the redevelopment of the site, therefore the VA has assumed an Unrestricted Residential Reuse for the site unless specifically selecting another standard that are more stringent and as expressed in this report.

## 5.0 ENVIRONMENTAL CONDITIONS

### 5.1 Solid Waste

Solid waste issues were identified during the on-site observations for review of the facility readiness for transfer. No solid waste facility, dump sites, landfill areas or transfer areas were identified. Solid waste in the form of construction debris was being generated as the buildings are cleaned-out and stripped to the bare walls. This material is placed in roll-off bins and removed from the site as the bins are filled. No demolition waste material is scheduled to remain on site.

VA Commitments:

The VA has agreed to remove the demolition debris.

Restrictions:

There will be no restrictions from this environmental condition.

Future Commitments:

There are no future requirements as a result of this environmental condition.

### 5.2 Underground and Aboveground Fuel Storage Tanks

The VA had underground storage tanks (USTs) located at the northern end of the south parcel near Buildings #1, #6, south of #33, #41, #60, #62 and #63. One (1) aboveground storage tank (AST) was located at Structure #49. The USTs at Buildings #1, #6, #41, #60, #62, and #63 were associated with power and chiller systems and contained diesel fuels. The UST at building #60 and the UST south of building #33 contained gasoline. The AST structure #49 was used for bulk fuel storage. The AST at Structure #49 was removed prior to these transfer operations and Hurricane Katrina in 2005. The USTs have been removed in accordance with the Mississippi Department of Environmental Quality (MDEQ) regulations. The USTs and AST were taken out of service and removed as follows:

<u>BUILDING/STRUCTURE</u>	<u>OUT OF SERVICE</u>	<u>REMOVED</u>
#1	2005	8/6/08
#6 (4-tanks)	Unknown	1993
#41	2005	8/6/08
#60	Unknown	1993
#62	Unknown	1996
#63	2005	8/6/08
#49 AST	Unknown	Unknown

The USTs noted as out-of-service in 2005 were the only tanks in service immediately prior to the Hurricane Katrina devastation. As noted these USTs were removed on August 6, 2008.

**Soil:**

The soil samples from the underground storage tanks closure conducted in July 2008 were below the MDEQ action levels for diesel range organics (DROs) and polynuclear aromatic hydrocarbons (PAHs). The MDEQ Office of Pollution Control classified the sites as no further action required in a letter dated October 20, 2008. The MDEQ closure letter and laboratory analytical summary reports can be found in Attachment 7.

Soil samples collected at building #6 indicated impact by the petroleum hydrocarbons, and semi-volatile organic compounds (PAHs). These tanks had been removed in 1993, prior to Hurricane Katrina.

**Groundwater:**

OHC Environmental Engineers collected groundwater samples from monitoring wells at Building #1 and Building #41, and from a probe boring drilled at Building #6. Groundwater sample results indicated non-detect and below the MDEQ action levels from the monitoring well samples at Buildings #1 and #41 and the probe boring at Building #6.

**VA Commitments:**

The VA has removed the USTs that existed post-Hurricane Katrina. The area around building #6 requires remedial action of the soil due to the PAHs. The remediation of the soil will be over-excavation, removal and proper disposal into a licensed Subtitle D landfill of the contaminated soil, and replacement with clean fill. The over-excavation volume will be defined in the remediation specifications based the existing sampling information and the recent December 2008 sampling event.

The remediation will be completed to the unrestricted residential use standards of the MDEQ Brownfields TRGs for the polynuclear aromatic hydrocarbons (PAHs) chemicals of concern. The PAHs of concern include:

Benzo (a) pyrene,  
Benzo (b) fluoranthene,  
Benzo (a) fluoranthene,  
Chrysene, and  
Dibenzo (a,h) anthracene.

The TRGs are found in Attachment 9.

**Restrictions:**

Restrictions as a result of this environmental condition will depend on the level of remedial action conducted. The City of Gulfport will be required to allow the VA to conduct the required investigation, sampling and remediation activities.

Future Commitments:

Once the initial VA commitments have been met, no additional commitment exists.

### **5.3 Polychlorinated Biphenyls**

#### **5.3.1 Fluorescent Light Ballasts**

All buildings remaining will have fluorescent lights removed as a part of the demolition/cleanup operations.

A PEMC Co. representative conducted a site reconnaissance of the remaining 10 buildings. Fluorescent lighting remained Building #41, eastern ½ of Building #2, and southern ½ of the second floor of Building #4.

VA Commitments:

Fluorescent lighting will be removed as a part of the demolition and cleanup. The condition will be abated prior to transfer.

Restrictions:

There are no restrictions as a result of this environmental condition.

Future Commitments:

No additional commitment exists.

#### **5.3.2 Transformers**

Pad mounted transformers were at several locations of the VA south parcel. The main transformers were located at the southwest side of the property at the west property line along Coffee Creek, and near Building #6 and #61 at the northwest corner of the property. There were smaller pad mounted transformers at each building on the facility. All transformers have been removed. The pad mounted transformers locations are illustrated on the VA Electrical Utility Plan drawing presented in Attachment 3.

OHC Environmental Engineering conducted sampling of the soil and ground water in the area of the transformers near Buildings #6 and #61. The soil and ground water sample results indicated no detection of PCBs. The sampling procedures and analysis were reported in the OHC Environmental Engineering Report, *Soil and Groundwater Sampling Report – Part IV, June 2, 2008*.

VA Commitments:

There are no commitments prior to transfer from this environmental condition.

Restrictions:

There are no restrictions as a result of this environmental condition.

Future Commitments:

No additional commitment exists.

## 5.4 Asbestos

Asbestos containing materials (ACM) have been identified in most of the buildings that survived the destruction of Hurricane Katrina, 2005. The asbestos was abated as a prerequisite of the demolition permits for the buildings demolished and removed from the facility. The Demolition Permits can be found in Attachment 6. The following are the reviews of the asbestos containing materials for the buildings remaining and scheduled to be transferred to the City of Gulfport.

The initial ACM survey was conducted in October 2006, and additional samples collected through April 2008. The updated survey data has been summarized in the attached Table One "Asbestos Remaining Updated Survey". The table shows the ACM remaining in each building, and the ACM over 1% which would be abated. The ACM in the exterior skim coat of the buildings will not be removed if it is not an exposed friable ACM material. Attachment 4 contains the initial survey laboratory data on the disc, and the April 2008 survey data report.

The remediation of the ACM is conducted on any materials over 1% asbestos per the NESHAP concentration level. As each containment area has been abated, a visual survey is conducted by AMI and a certificate of final inspection for that containment area is prepared. The AMI Certificates of Final Inspections can be found in Attachment 4.

The following sections present the asbestos environmental condition by building.

### 5.4.1 Building #1 ACM

An initial asbestos survey was conducted in Building #1 by AMI in October 2006, prior to any interior demolition, and asbestos was found in limited building materials. The building has been abated and cleared, in accordance with the NESHAP regulations, for the asbestos environmental condition.

#### VA Commitments:

There are no VA commitments from this environmental condition in Building #1.

#### Restrictions:

There are no restrictions due to asbestos condition in Building #1.

#### Future Commitments:

No additional commitment exists.

### 5.4.2 Building #2 ACM

AMI Environmental conducted an initial asbestos survey was conducted in October 2006 and an updated survey April 2008 on selected materials in Building #2 which identified ACM in several materials. The majority of the ACM identified has been abated. The ACM remaining was identified in the window glazing. The abatement of the windows will be completed with the scheduled windows/roofing replacement.

The northern section of Building #2 was demolished and the debris removed from the site.

VA Commitments:

The VA commits to conduct asbestos abatement of the windows from Building #2. The certificates of final inspection for the ACM removed to date are included in Attachment 4. The certificate of final inspection will be provided when the identified windows have been abated.

Restrictions:

After completion of asbestos abatement, there are no restrictions as a result of an asbestos environmental condition in Building #2.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

#### **5.4.3 Building #3 ACM**

AMI conducted an initial asbestos survey in October 2006, and an updated survey was conducted in April 2008 on selected materials in Building #3, which identified ACM in several materials. The ACM identified with asbestos content above 1% has been abated, except for a tan and black textured paint and the roofing felt paper. The AMI Environmental Certificate of Final Inspection sheets are presented in Attachment 4.

A PEMC Co. representative conducted a visual review of the building on October 31, 2008, for the identified ACM, which appeared to have been abated. The roof was not accessed for review.

VA Commitments:

The VA commits to complete the abatement of the interior tan textured paint and the estimated 25,000 linear feet of roofing felt paper on Building #3. A final certificate of final inspection will be provided once the abatement has been completed.

Restrictions:

After completion of the VA commitments, there are no restrictions as a result of an asbestos environmental condition for Building #3.

Future Commitments:

After completion of the initial VA commitments, no additional commitment exists.

#### **5.4.4 Building #4 ACM**

AMI conducted an initial asbestos survey in October 2006 and an updated survey in April 2008 on selected materials in Building #4, and identified ACM in several building materials. The majority of the ACM identified has been abated. The remaining ACM above the 1% asbestos content includes the roofing flashing and exterior skim coat

stucco. The exterior skim coat has been covered by newer non-ACM layers of stucco and therefore will remain in place for the transfer of Building #4.

A PEMC Co. representative conducted a visual review of the building on floor 1 and the north half of floor 2 on November 2, 2008. The identified ACM materials were not observed in these areas. The south half of the 2<sup>nd</sup> floor was in containment and was not reviewed at the time of the walk-through. The roofing was not accessible at the time of the walk-through.

VA Commitments:

The VA commits to conduct asbestos abatement of the 1200 linear feet of roof flashing from Building #4. The VA will provide a certificate of final inspection once this abatement has been completed.

Restrictions:

The City of Gulfport is advised to document the existence of the ACM in the stucco material in the event of future renovation/demolition activities. The City of Gulfport should follow the appropriate rules and regulations when handling this material. After completion of asbestos abatement of the roof flashing, and the restriction of the stucco mentioned above, no other restrictions are known as a result of the asbestos environmental condition in Building #4.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

#### **5.4.5 Building #5 ACM**

AMI conducted an initial asbestos survey in October 2006 on selected materials in Building #5, and an updated survey was conducted in April 2008. The majority of the ACM in the building has been abated and certificates of final inspection provided in Attachment 4. The updated survey shows that the exterior roof-vent flashing containing over 1% asbestos.

A PEMC Co. representative conducted a visual review of the building on October 31, 2008 and observed the identified ACM in the building had been abated. The roof was not accessible for review.

VA Commitments:

The VA commits to conduct asbestos abatement of the 16,500 linear feet of roof-vent flashing from Building #5. The VA will provide a final certificate of final inspection once the abatement has been completed.

Restrictions:

After the completion of the removal of the roof-vent flashing, there are no known restrictions as a result of an asbestos environmental condition in Building #5.

Future Commitments:

Once the VA commitment is met, no additional commitment exists.

**5.4.6 Building #41 ACM**

AMI conducted an initial asbestos survey in October 2006, and an updated survey in April 2008 on selected materials in Building #41. The surveys identified ACM in building materials the ACM remaining. Abatement of ACM in Building #41 has not been completed. The ACM materials remaining include black floor tile mastic, the fire doors, and the exterior skim coat which has been covered by a newer stucco coating. The exterior skim coat has been covered by newer non-ACM layers of stucco and therefore will remain in place for the transfer of Building #41.

A PEMC Co. representative conducted a visual review of the Building #41 on November 2, 2008, and found identified ACM remained.

VA Commitments:

The VA commits to conduct asbestos abatement of the interior ACM in the floor tile mastic and the fire doors in Building #41. The VA will provide a certificate of final inspection once abatement has been completed.

Restrictions:

The City of Gulfport is advised to document the existence of the ACM in the stucco material in the event of future renovation/demolition activities. The City of Gulfport should follow the appropriate rules and regulations when handling this material. After completion of asbestos abatement of the floor tile mastic and fire door, and the restriction of the stucco mentioned above, no other restrictions are known as a result of the asbestos environmental condition in Building #41.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

**5.4.7 Building #57**

AMI conducted an initial asbestos survey in October 2006, and an updated survey in April 2008, on selected materials in Building #57. The ACM material from interior of the building has been removed. An older layer of exterior skim coat stucco contains ACM. The older exterior ACM containing skim coat has been covered by newer non-ACM layers of stucco and therefore will remain in place for the transfer of Building #57.

AMI conducted final inspections for the interior abatement. The AMI Certificates of Final Inspection are presented in Attachment 4.

A PEMC Co. representative conducted a visual review of the building on November 1, 2008 and found ACM abatement of the interior had been conducted. The ACM exterior skim coat did not appear to be removed.

VA Commitments:

There no VA commitments from this environmental condition in Building #57.

Restrictions:

The City of Gulfport is advised to document the existence of the ACM in the stucco material in the event of future renovation/demolition activities. The City of Gulfport should follow the appropriate rules and regulations when handling this material. Other than the above mentioned stucco restriction, there are no other restrictions from this environmental condition in Building #57.

Future Commitments:

No additional VA commitment exists.

**5.4.8 Building #62**

AMI conducted an initial asbestos survey in October 2006 and an updated survey in April 2008, and second updated survey in December 2008, on selected materials in Building #62 and identified ACM in the building. The ACM identified was predominantly on the exterior of the building, including roof flashing, and roof felt paper.

A PEMC Co. representative conducted a visual review of the building on November 1, 2008 and did not observe the identified ACM. Access to the roof was not available at the time of the review.

VA Commitments:

The VA commits to the abatement of ACM in Building #62. The VA will provide Certificates of Final Inspection for the abatement of these materials.

Restrictions:

After completion of asbestos abatement, there are no restrictions.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

**5.4.9 Building #63**

AMI conducted an initial asbestos survey in October 2006 and an updated survey in April 2008 on selected materials in Building #63. The ACM identified has been abated and removed from the building. AMI conducted a final inspection and the Certificate of Final Inspection sheet is presented in Attachment 4.

A PEMC Co. representative conducted a visual review of the building and found no identified ACM in the building. The building has been cleared to the concrete/block walls, flooring and the roofing timbers and trusses.

VA Commitments:

There are no commitments in Building #63 from this environmental condition.

Restrictions:

There are no restrictions as a result of an asbestos environmental condition.

Future Commitments:

No additional commitment exists.

**5.4.10 Building #64**

AMI conducted an initial asbestos survey in October 2006 and an updated survey in April 2008 on selected materials in Building #64. The identified ACM has been abated and removed from the building. AMI conducted final inspections and the Certificate of Final Inspection sheet is presented in Attachment 4.

A PEMC Co. representative conducted a visual review of the building and found no identified ACM in the building. The building has been cleared to the concrete/block walls, and flooring.

VA Commitments:

There are no commitments in Building #64 from this environmental condition.

Restrictions:

There are no restrictions as a result of an asbestos environmental condition.

Future Commitments:

No additional commitment exists.

## **5.5 Lead Based Paint and Lead in Building Materials**

Lead based paint (LBP) and lead in building materials has been identified in most of the buildings that survived the destruction of Hurricane Katrina, 2005. The following are the reviews of the LBP and lead in building materials for the buildings remaining and to be transferred to the City of Gulfport. The standard for classifying a material as a lead containing building material or lead based paint is specified by the Environmental Protection Agency (EPA) and U.S. Department of Housing and Urban Development (HUD) and the Mississippi Department of Environmental Quality which specify a concentration of 1.0 mg/cm<sup>2</sup> for residential properties using XRF analysis.

Much of the lead paint in the buildings has been removed as part of the cleanup and interior demolition process. All remaining deteriorated lead paint will be addressed by the VA for transfer to the extent possible. Note that certain concealed structural members or other components inherent to the building structure will remain, with any accessible deteriorated paint addressed via removal of loose, flaking, peeling paint, etc., and re-priming for future refinishing (reference attached Lead Work Plans for details, Attachment 5). As the buildings are not in condition of occupancy, HUD clearance standards for lead abatement will not be utilized. The VA will provide a final report upon completion and transfer, indicating the lead that has been removed, and any remaining lead left in the buildings is in good condition. Exterior components will be removed or addressed at the time of replacement, (i.e. doors, windows, roof-related items).

### **5.5.1 Building #1, LBP and Lead in Building Materials**

AMI conducted a lead survey of the building materials in October 2006 and an updated survey in April 2008. The surveys identified materials with lead or LBP which exceeded the 1.0 mg/cm<sup>2</sup> lead content in Building #1. The list of these materials was presented the 2006 and 2008 Survey Reports and submitted to the VA. The AMI lead survey sheets have been included in Attachment 5, and the 2006 and 2008 Survey Reports are included on the disc.

As a result of the interior demolition and cleaning, some materials identified in the original survey have been removed. Complete abatement of Building #1 has not been conducted. A summary table presenting the materials remaining with LBP has been attached.

#### VA Commitments:

The VA commits to the removal and/or abatement of deteriorated and accessible LBP exceeding the 1.0 mg/cm<sup>2</sup> from the building. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI. The VA will provide a final LBP inspection final report.

#### Restrictions:

After the VA commitments are completed, certain concealed or structural items with lead paint will remain in "good" condition, and primed for future refinishing. The City of Gulfport is advised to document and maintain the presence of such lead in the event of

future renovation/demolition activities. EPA and OSHA guidelines may apply to any future work.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

**5.5.2 Building #2, LBP and Lead in Building Materials**

AMI conducted a lead survey of the building materials in October 2006 and an updated survey in April 2008. The surveys identified materials with lead or LBP which exceeded the 1.0 mg/cm<sup>2</sup> lead content in Building #2. The list of these materials was presented the 2006 survey report and 2008 updated survey, and submitted to the VA. The AMI lead survey sheets have been included in Attachment 5, and the 2006 and 2008 Survey Reports are included on the disc.

As a result of the demolition of the north end of the building, the interior demolition and cleaning, some of the LBP materials identified in the original survey have been removed.

The AMI Lead Based Paint Survey – Update Table, TABLE TWO, indicates the LBP on building materials that remains.

VA Commitments:

The VA commits to the removal and/or abatement of deteriorated and accessible LBP exceeding the 1.0 mg/cm<sup>2</sup> from the building. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI. The VA will provide a final LBP inspection final report.

Restrictions:

After the VA commitments are completed, certain concealed or structural items with lead paint will remain in "good" condition, and primed for future refinishing. The City of Gulfport is advised to document and maintain the presence of such lead in the event of future renovation/demolition activities. EPA and OSHA guidelines may apply to any future work.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

**5.5.3 Building #3, LBP and Lead in Building Materials**

AMI conducted a lead survey of the building materials in October 2006 and an updated survey in April 2008. The surveys identified materials with lead or LBP which exceeded the 1.0 mg/cm<sup>2</sup> lead content in Building #3. The list of these materials was presented the 2006 and Survey Reports and submitted to the VA. The AMI lead survey sheets have been included in Attachment 5, and the 2006 and 2008 Survey Reports are included on the disc. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI.

As a result of the interior demolition and cleaning, lead based paint and lead containing building materials have been removed. Completed abatement of LBP in Building #3 has not been completed.

The AMI Lead Based Paint Survey – Update Table, TABLE TWO, indicates the LBP on building materials that remains.

VA Commitments:

The VA commits to the removal and/or abatement of deteriorated and accessible LBP exceeding the 1.0 mg/cm<sup>2</sup> from the building. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI. The VA will provide a final LBP inspection final report.

Restrictions:

After the VA commitments are completed, certain concealed or structural items with lead paint will remain in "good" condition, and primed for future refinishing. The City of Gulfport is advised to document and maintain the presence of such lead in the event of future renovation/demolition activities. EPA and OSHA guidelines may apply to any future work.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

#### **5.5.4 Building #4, LBP and Lead in Building Materials**

AMI conducted a lead survey of the building materials in October 2006 and an updated survey was conducted in April 2008. The surveys identified materials with lead or LBP which exceeded the 1.0 mg/cm<sup>2</sup> lead content in Building #4. The list of these materials was presented the 2006 and 2008 Survey Reports and submitted to the VA. The AMI lead survey sheets have been included in Attachment 5, and the 2006 and 2008 Survey Reports are included on the disc.

The AMI Lead Based Paint Survey – Update Table, TABLE TWO, indicates the LBP on building materials that remains.

VA Commitments:

The VA commits to the removal and/or abatement of deteriorated and accessible LBP exceeding the 1.0 mg/cm<sup>2</sup> from the building. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI. The VA will provide a final LBP inspection final report.

Restrictions:

After the VA commitments are completed, certain concealed or structural items with lead paint will remain in "good" condition, and primed for future refinishing. The City of Gulfport is advised to document and maintain the presence of such lead in the event of future renovation/demolition activities. EPA and OSHA guidelines may apply to any future work.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

**5.5.5 Building #5, LBP and Lead in Building Materials**

AMI conducted a lead survey of the building materials in October 2006 and an updated survey was conducted in April 2008. The survey identified materials with lead or LBP which exceeded the 1.0 mg/cm<sup>2</sup> lead content in Building #5. The list of these materials was presented the 2006 and 2008 Survey Reports and submitted to the VA. The AMI lead survey sheets have been included in Attachment 5, and the 2006 and 2008 Survey Reports are included on the disc.

The AMI Lead Based Paint Survey – Update Table, TABLE TWO, indicates the LBP on building materials that remains in Building #5.

VA Commitments:

The VA commits to the removal and/or abatement of deteriorated and accessible LBP exceeding the 1.0 mg/cm<sup>2</sup> from the building. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI. The VA will provide a final LBP inspection final report.

Restrictions:

After the VA commitments are completed, certain concealed or structural items with lead paint will remain in "good" condition, and primed for future refinishing. The City of Gulfport is advised to document and maintain the presence of such lead in the event of future renovation/demolition activities. EPA and OSHA guidelines may apply to any future work.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

**5.5.6 Building #41, LBP and Lead in Building Materials**

AMI conducted a lead survey of the building materials in October 2006 and an updated survey was conducted in April 2008. The survey identified materials with lead or LBP which exceeded the 1.0 mg/cm<sup>2</sup> lead content in Building #41. The list of these materials was presented the 2006 and 2008 Survey Reports and submitted to the VA. The AMI lead survey sheets have been included in Attachment 5, and the 2006 and 2008 Survey Reports are included on the disc.

The AMI Lead Based Paint Survey – Update Table, TABLE TWO, indicates the LBP on building materials that remains in Building #41.

VA Commitments:

The VA commits to the removal and/or abatement of deteriorated and accessible LBP exceeding the 1.0 mg/cm<sup>2</sup> from the building. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI. The VA will provide a final LBP inspection final report.

Restrictions:

After the VA commitments are completed, certain concealed or structural items with lead paint will remain in "good" condition, and primed for future refinishing. The City of Gulfport is advised to document and maintain the presence of such lead in the event of future renovation/demolition activities. EPA and OSHA guidelines may apply to any future work.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

### **5.5.7 Building #57, LBP and Lead in Building Materials**

AMI conducted a lead survey of the building materials in October 2006 and an updated survey was conducted in April 2008. The survey identified materials with lead or LBP which exceeded the 1.0 mg/cm<sup>2</sup> lead content in Building #57. The list of these materials was presented the 2006 and 2008 Survey Reports and submitted to the VA. The AMI lead survey sheets have been included in Attachment 5, and the 2006 and 2008 Survey Reports are included on the disc.

As a result of the interior demolition and cleaning, some of the lead based paint and lead containing building materials have been removed. Completed abatement of LBP in Building #57 has not been completed.

The AMI Lead Based Paint Survey – Update Table, TABLE TWO, indicates the LBP on building materials that remains.

VA Commitments:

The VA commits to the removal and/or abatement of deteriorated and accessible LBP exceeding the 1.0 mg/cm<sup>2</sup> from the building. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI. The VA will provide a final LBP inspection final report.

Restrictions:

After the VA commitments are completed, certain concealed or structural items with lead paint will remain in "good" condition, and primed for future refinishing. The City of Gulfport is advised to document and maintain the presence of such lead in the event of future renovation/demolition activities. EPA and OSHA guidelines may apply to any future work.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

### **5.5.8 Building #62, LBP and Lead in Building Materials**

AMI conducted a lead survey of the building materials in October 2006 and an updated survey was conducted in April 2008. The survey identified materials with lead or LBP which exceeded the 1.0 mg/cm<sup>2</sup> lead content in Building #62. The list of these materials was presented the 2006 and 2008 Survey Reports and submitted to the VA. The AMI

lead survey sheets have been included in Attachment 5, and the 2006 and 2008 Survey Reports are included on the disc.

As a result of the interior demolition and cleaning, some lead based paint and lead containing building materials have been removed. Completed abatement of LBP in Building #62 has not been completed. The AMI Lead Based Paint Survey – Update Table, TABLE TWO, indicates the LBP on building materials that remains.

VA Commitments:

The VA commits to the removal and/or abatement of deteriorated and accessible LBP exceeding the 1.0 mg/cm<sup>2</sup> from the building. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI. The VA will provide a final LBP inspection final report.

Restrictions:

After the VA commitments are completed, certain concealed or structural items with lead paint will remain in "good" condition, and primed for future refinishing. The City of Gulfport is advised to document and maintain the presence of such lead in the event of future renovation/demolition activities. EPA and OSHA guidelines may apply to any future work.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

### **5.5.9 Building #63, LBP and Lead in Building Materials**

AMI conducted a lead survey of the Building #63 (Chapel) in October 2006. The survey identified materials with lead or LBP which exceeded the 1.0 mg/cm<sup>2</sup> lead content in Building #63. The list of these materials was presented the 2006 and 2008 Survey Reports and submitted to the VA. The AMI lead survey sheets have been included in Attachment 5, and the 2006 and 2008 Survey Reports are included on the disc.

The Chapel has been completely gutted and all building materials removed to the concrete and block walls, and timber framing, joists and trusses and as a result much of the LBP from the interior has been removed. The AMI Lead Based Paint Survey – Update Table, TABLE TWO, indicates the LBP on building materials that remains.

VA Commitments:

The VA commits to the removal and/or abatement of deteriorated and accessible LBP exceeding the 1.0 mg/cm<sup>2</sup> from the building. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI. The VA will provide a final LBP inspection final report.

Restrictions:

After the VA commitments are completed, certain concealed or structural items with lead paint will remain in "good" condition, and primed for future refinishing. The City of Gulfport is advised to document and maintain the presence of such lead in the event of future renovation/demolition activities. EPA and OSHA guidelines may apply to any future work.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

**5.5.10 Building #64, LBP and Lead in Building Materials**

AMI conducted a lead survey of the building materials in October 2006 and an updated survey was conducted in April 2008. The survey identified materials with lead or LBP which exceeded the 1.0 mg/cm<sup>2</sup> lead content in Building #64. The list of these materials was presented the 2006 and 2008 Survey Reports and submitted to the VA. The AMI lead survey sheets have been included in Attachment 5, and the 2006 and 2008 Survey Reports are included on the disc.

The AMI Lead Based Paint Survey – Update Table, TABLE TWO, indicates the LBP on building materials that remains.

VA Commitments:

The VA commits to the removal and/or abatement of deteriorating and accessible LBP exceeding the 1.0 mg/cm<sup>2</sup> from the building. A "Lead Abatement Plan" dated August 1, 2008 has been prepared by AMI. The VA will provide a final LBP inspection final report.

Restrictions:

After the VA commitments are completed, certain concealed or structural items with lead paint will remain in "good" condition, and primed for future refinishing. The City of Gulfport is advised to document and maintain the presence of such lead in the event of future renovation/demolition activities. EPA and OSHA guidelines may apply to any future work.

Future Commitments:

Once the initial VA commitment is met, no additional commitment exists.

**5.5.11 Lead in Soil**

The EPA and HUD guideline for unrestricted residential housing and child-occupied facilities recommends a lead concentration in bare soil not to exceed 400 mg/Kg (parts per million, ppm). The guideline for soils with a concentration of lead between 400 ppm and 5,000 ppm recommends interim controls to alleviate exposures such as vegetative cover, restricting access or cultivation to dilute the content.

OHC collected 20 soil samples in October 2007, in areas of concern near specific buildings, across the facility. The soil was analyzed for eight (8) RCRA metals which included lead. The analytical results from these samples were below the 400 ppm.

AMI collected 15 preliminary soil samples in October 2006, and 96 additional soil samples in April 2008, from around each building that is scheduled to be transferred. The soil samples were specifically analyzed for total lead by EPA Lead in Soil Method SW846 3050B and 7420. The analytical results indicated that several soil samples

around each building exceeded the 400 ppm concentration. The laboratory analysis sheets are presented in Attachment 5. The soil sample locations are illustrated in the attached figures.

The VA has proposed a soil remediation plan for around the buildings where lead in soil exceeded the 400 ppm concentration. The remediation includes over-excavating the soil from the building drip line and extending out approximately 5-feet, and digging up to 6" deep.

VA Commitments:

The VA commits to the proposed remediation of lead in soil and to the HUD concentration requirements. The VA will provide the documentation indicating completion of this remedial action.

Restrictions:

After the soil with lead concentrations above 400 ppm has been removed, there are no known restrictions as a result of this environmental condition.

Future Commitments:

Once the VA commitment is met, no additional commitment exists.

## 6.0 SOIL AND GROUNDWATER CONDITIONS

Soil and groundwater samples were collected in areas of the facility where hazardous materials were used. Samples were analyzed for volatile organics, semi-volatile organics including PAHs and diesel range organics (DROs), and eight (8) RCRA heavy metals. The areas of concern were located at the northeast section near the engineering shops and offices (Buildings #32), the north-central section at the engineering material storage (Building #45 and #117), and the northwest section near the boiler plant (Building #6 and #61). The impacted areas of concern are defined in the following sections.

### 6.1 *Soil Conditions*

OHC Environmental collected soil samples from across the site and found three areas of concern with semi-volatile organics including PAHs from October 2007 through April 2008. The soil samples from the areas at Building #32, Building #6 and #61, and Building #45 and #117 indicated levels of semi-volatiles above the MDEQ Brownfields Tier 1 TRGs for unrestricted use. OHC conducted delineation sampling of the impacted area in the subsequent sampling events. The OHC summary tables presenting the analytical data can be found in Attachment 8. At the bottom of the tables the MDEQ Brownfields TRGs for each specific chemical are shown. The MDEQ Brownfields TRGs can be found in Attachment 9.

Soil samples from the area of Building #32 indicated elevated levels of PAHs, benzo (a) pyrene, exceeded the TRGs.

Soil samples from the Building #6 and #61 area indicated concentrations of PAHs including chrysene, benzo (a) pyrene, benzo (b) fluoranthene, and dibenzo (a,h) anthracene exceeded the TRGs.

Soil samples from the area of Buildings #45 and #117 indicated concentrations of the PAH chemical benzo (a) pyrene exceeded the TRG.

In addition to the 20 soil samples analyzed for the eight (8) RCRA metals, which includes arsenic, 24 soil samples were collected in December 2007 and April 2008 and analyzed specifically for Arsenic at random locations across the facility. No apparent pattern of arsenic concentrations in soil could be determined based on the VA operations. The elevated arsenic levels were discussed with the MDEQ who indicated that elevated arsenic was common in the area. The MDEQ requested a statistical analysis to determine if the levels are greater than would be expected for arsenic in soil for the area and above the background levels. OHC has been contracted to provide the statistical analysis to the MDEQ.

VA Commitments:

The VA is committed to the remediation of the soil. The VA plans to over-excavate soil in areas with the elevated levels of PAHs at Buildings #32, #6 and #61, and #45 and #117. The soil will be removed from the site and properly disposed in a Subtitle D landfill. OHC has prepared contractor specifications to conduct the soil remediation. The VA will provide documentation the remedial action has been completed and subsequent soil sampling indicates concentrations of PAHs below the MDEQ Brownfields TRGs. The OHC Contractor Specifications can be found in Attachment 10.

Restrictions:

After the VA commitment is met, no known restrictions exist as a result of this environmental condition.

Future Commitments:

Once the VA commitment is met, no additional commitment exists.

## **6.2 Groundwater Conditions**

OHC collected groundwater samples from monitoring wells and probe borings installed during the environmental assessments from October 2007 through April 2008.

One (1) groundwater sample from a probe boring indicated to be impacted by semi-volatile and PAH (Benzo (a) pyrene) which exceeded the MDEQ Brownfields TRG from the area south of former Building #45 and #117.

VA Commitments:

The VA is committed to the reduction of the identified elevated PAH in the groundwater to below the MDEQ Brownfields TRG. The groundwater remediation plan includes the removal of the source material, over-excavation of the soil, and then resampling the groundwater. The VA will provide documentation indicating the remedial action has been completed. OHC has prepared Contractor Specifications for the soil removal and resampling of the groundwater, which can be found in Attachment 10.

Restrictions:

After the VA commitment is met, no known restrictions exist as a result of this environmental condition.

Future Commitments:

Once the VA commitment is met, no additional commitment exists.

## 7.0 CONCLUSIONS

The VA intends to transfer the VA in Gulfport, Mississippi to the City of Gulfport. This Final FOST Report was prepared for the south parcel, the portion of the property south of Railroad Street and north of East South Beach Boulevard. The Final FOST Report identified environmental conditions, the remediation/mitigation and abatement conducted or the commitment to complete the activities, and the final reports based on supporting documentation and an on-site visual inspection of the south parcel.

The future use of the property has not been revealed by the City of Gulfport to the VA. Therefore, the environmental remediation/mitigation goals applied were the MDEQ Brownfields Tier 1 Target Remediation Goals for Unrestricted Non-Residential use.

The Final FOST Report has adequately identified the environmental conditions on the property based on the current conditions, past use, and documentation available identifying environmental conditions. Upon completion of the VA commitments, and subject to the restrictions and future commitments identified in this Final FOST Report, the property does not pose a threat to human health or the environment. The VA property south parcel will be suitable for transfer after completion of the VA commitments of the environmental conditions identified in this Final FOST Report.

Concurred by:

---

VA Authorized Representative Signature, Title

---

VA Authorized Representative, Title (Print)

## REFERENCES

*Phase I Environmental Site Assessment Revised, VA Gulfcoast Veterans Health Care System, 200 East Beach Boulevard, Gulfport, Mississippi 39507, OHC Environmental Engineering, June 7, 2007.*

*Soil and Groundwater Sampling Report, V.A. Gulfcoast Veterans Health Care System, 200 East Beach Boulevard, Gulfport, Mississippi, OHC Environmental Engineering, May 14, 2007.*

*Soil and Groundwater Sampling Report – Part IV, V.A. Gulfcoast Veterans Health Care System, 200 East Beach Boulevard, Gulfport, Mississippi, OHC Environmental Engineering, June 2, 2008.*

*Interim Assessment Report, V.A. Medical Center, 200 East Beach Boulevard, Gulfport, Mississippi, OHC Environmental Engineering, October 24, 2007.*

*V.A. CAMPUS BUILDING SCHEDULE Drawing, Department of Veterans Affairs, BR-M Corporation LLC Professional Land Surveyors, January 22, 2007*

*Electrical Utility Plan Drawing, Underground and Aerial Electrical Utilities, Veterans Administration, Gulfport VA, Gulfport, Mississippi, Form 08-6231, October 1978.*

*Certificate of Final Inspection, Asbestos Clearance Sheets for Buildings 3, 5, 57, 60, 63, 64. Asbestos Material Sampling, Gulfport VA Medical Campus, - Gulfport, MS, AMI Environmental, July 27, 2007 through August 26, 2008.*

*Lead Results, Updated Survey Report, Lead – Site Investigation Report, – Lead Based Paint, Lead Containing Paint and Materials, Gulfport VA Medical Campus – Gulfport, MS, AMI Environmental, July 4, 2008.*

Hurricane History Information, Hurricane Camille and Hurricane Katrina, NOAA Coastal Services Center, On-line.

Mississippi Department of Environmental Quality, Underground Storage Tanks Closure Letter, October 20, 2008.

Environmental Science Corp., Report Summary, Laboratory analysis sheets, August 7, 2008.

AMI Environmental, *Lead Soil Sampling Report*, Laboratory analysis sheets and sample locations per building figures, August 1, 2008.

AMI Environmental, *Lead Abatement Plans* for Building 001 through 064, August 1, 2008.

AMI Environmental, *Asbestos and Lead XRF Results Updated Survey Report – April 2008*, Gulfport – VA Medical Campus Buildings 1,2,4,41, 57 and 244.

Mississippi Department of Environmental Quality (MDEQ), Subpart II *RISK EVALUATION PROCEDURES FOR VOLUNTARY CLEANUP AND REDEVELOPMENT OF BROWNFIELD SITES, APPENDIX A, TIER 1 TARGET REMEDIAL GOAL TABLE*, Version Date 02/28/02.

## TABLES

**TABLE ONE**  
**ASBESTOS REMAINING**  
**UPDATED SURVEY as of Dec. 22, 2008**

Building #	Description	Color	%	Type	F NF	Est. Qty.	Comment
Bldg 2	Window Glazing	White	2%	Chry	F	210 Ea.	
Bldg. 3	Roofing- Felt Paper	Black	10%	Chry	F	25,000 LF	
Bldg. 3	Textured Paint	Green/Pink	<1%	Chry	F	2,000 SF	Interior near E. entrance
Bldg. 3	Textured Paint	Tan	2%	Chry	F	"	Interior near E. entrance
Bldg. 3	Textured Paint	Tan	2%	Chry	F		
Bldg. 3	Exterior Skim Coat, Layer 3	Light Gray	<1%	Chry	F	Throughout	Under newer building stucco
Bldg. 3	Exterior Skim Coat, Layer 3	Light Gray	<1%	Chry	F	Throughout	Under newer building stucco
Bldg. 4	Roofing-Flashing	Black	3%	Chry	F	1200 LF	
Bldg. 4	Exterior Skim Coat	White/Tan	4%	Chry	F	Throughout	Under newer building stucco
Bldg. 4	Exterior Skim Coat	Gray	4%	Chry	F	Throughout	Under newer building stucco
Bldg. 5	Roofing-Vent Flashing	Black	2%	Chry	F	15,000 LF	
Bldg. 5	Exterior Skim Coat	White/Tan	<1%	Chry	F	Throughout	Under newer building stucco
Bldg. 5	Roofing-Vent Flashing	Black	7%	Chry	F	1,500 LF	
Bldg. 41	12"x12" VFT	Blue	--	ND	NF	5,000 SF	
Bldg. 41	Mastic	Black	2%	Chry	NF	--	
Bldg. 41	12"x12" VFT	Cream	--	ND	NF	26,000 SF	
Bldg. 41	Mastic	Black	5%	Chry	NF	--	
Bldg. 41	12"x12" VFT	Red	--	ND	NF	5,000 SF	
Bldg. 41	Mastic	Black	2%	Chry	NF	--	

Final FOST Report for South Parcel of Property  
VA Medical Center, Gulfport, MS

048-02-200, J5  
February 26, 2009

TABLE ONE  
ASBESTOS REMAINING  
UPDATED SURVEY as of Dec. 22, 2008

Building #	Description	Color	%	Type	F/NF	Est. Qty.	Comment
Bldg. 41	Fire Doors	White	PACM	--	NF	Unk	Assumed
Bldg. 41	Exterior Skim Coat	White/Tan	5%	Chry	F	Throughout	Under newer building stucco
Bldg. 41	Exterior Skim Coat, Layer 3	Light Gray	<1%	Chry	F	Throughout	Under newer building stucco
Bldg. 57	Exterior-Skimcoat	Tan	3%	Chry	F	Throughout	Under newer building stucco
Bldg. 62	Roofing-Felt Paper	Black	2%	Chry	F	35,000 SF	
Bldg. 62	Roofing-Flashing	Black	3%	Chry	F	"	
Bldg. 62	Roofing-Flashing	Black	10%	Chry	F	"	
Bldg. 62	Exterior Skim Coat	Gray/Tan	<1%	Chry	F	Throughout	Under newer building stucco
Bldg. 62	Exterior Skim Coat	Light Gray	<1%	Chry	F	Throughout	Under newer building stucco

**TABLE TWO**  
**LEAD BASED PAINT and LEAD IN BUILDING MATERIALS REMAINING**  
**SURVEY UPDATE (as of Dec. 22, 2008)**

Building #	Description	Color	Substrate	Reading (mg/cm <sup>2</sup> )
Bldg. 1	Structural Beams	Beige	Steel	>5
Bldg. 1	Stairwell – Hand Rails	Green	Metal	>5
Bldg. 1	Stairwell Walls	Beige	Concrete	>5
Bldg. 1	2 <sup>nd</sup> Floor-West Stairwell Supports	Tan	Metal	6.1
Bldg. 1	2 <sup>nd</sup> Floor Stairwell I-Beams	Tan	Steel	10.1
Bldg. 1	2 <sup>nd</sup> Floor Stairwell Steps	Tan	Metal	5.8
Bldg. 1	2 <sup>nd</sup> Floor Stairwell Hand Rails	Green	Metal	8.2
Bldg. 1	Exit Door Frames	White	Wood	1.3
Bldg. 1	Exterior Stairwell Frames	Silver	Steel	10.1
Bldg. 1	1 <sup>st</sup> Floor Room 107-Ceiling	Beige	Concrete	1.6
Bldg. 1	1 <sup>st</sup> Floor Room 111-Ceiling	Beige	Plaster	5.6
Bldg. 1	1 <sup>st</sup> Floor Room 111- Window Frame	Beige	Wood	1.4
Bldg. 1	1 <sup>st</sup> Floor Room 136- Door Frame	Gray	Metal	6.3
Bldg. 2	Window Frames	White	Wood	1.4
Bldg. 2	Door Frames	White/Brown	Wood/Metal	1.3
Bldg. 2	Railing Components	Silver	Metal	10.1
Bldg. 2	Downspouts/Gutters	Brown/Beige	Metal	2.3
Bldg. 2	Fire Meter	Red	Metal	1.5
Bldg. 2	Exterior Crawl Space Grills	Brown	Metal	2.8
Bldg. 2	1 <sup>st</sup> and 2 <sup>nd</sup> Floor Ceilings	Beige	Concrete	5.6
Bldg. 2	Pipe Hangers	Beige	Metal	2.2
Bldg. 3	Window Frames	White/Beige	Wood	4.3
Bldg. 3	Fire Meter	Red	Metal	1.0
Bldg. 3	Exterior Crawl Space Grills	Brown	Metal	2.8
Bldg. 4	Exterior Water Valve	Red	Cast Iron	2.3
Bldg. 4	Exterior- Old Window Frames	White	Wood	2.7 – 4.4
Bldg. 5	Door Frames	White	Wood	16
Bldg. 5	1 <sup>st</sup> Floor Window Ledges	White	Plaster	5.5
Bldg. 5	1 <sup>st</sup> Floor Window Frames	White	Metal	16
Bldg. 5	2 <sup>nd</sup> Floor Window Frames	White	Metal	18
Bldg. 5	Exterior Fire Hose Connection	Red	Metal	1.9

**TABLE TWO**  
**LEAD BASED PAINT and LEAD IN BUILDING MATERIALS REMAINING**  
**SURVEY UPDATE (as of Dec. 22, 2008)**

Building #	Description	Color	Substrate	Reading (mg/cm <sup>2</sup> )
Bldg. 5	Exterior Grate Covers	Brown	Metal	5.2-6.0
Bldg. 5	Exterior Hand Rails	Brown	Metal	6.1-10.1
Bldg. 41	Wall Chase Cage	White	Metal	12
Bldg. 41	Hand Rails	White	Metal	2.1
Bldg. 41	Stairwell Rails	White	Metal	2.7
Bldg. 41	Exterior Water Valve	Red	Metal	1.7
Bldg. 41	2 <sup>nd</sup> Floor Stairwell-Hand Rail, Riser and Deck	White	Metal	1.7-8.3
Bldg. 41	2 <sup>nd</sup> Floor Stairwell Hand Rails	Beige	Metal	3.0
Bldg. 57	Window Frames	White	Plaster	8.1
Bldg. 57	Fire Hydrant	Yellow	Metal	2.4
Bldg. 57	Loading Dock Area Components	Yellow	Metal	3.9
Bldg. 57	Exterior Grates	Brown	Metal	10.2
Bldg. 57	Loading Dock Guard	Yellow	Metal	8.0
Bldg. 57	Exterior Fire Hydrant	Yellow	Cast Iron	2.2
Bldg. 57	Exterior Wall Below 4'	Beige	Plaster	4.0-4.9
Bldg. 57	Exterior Wall above 4'	Beige	Plaster	2.9-11.3
Bldg. 57	Exterior Wall texture under plaster	Beige	Concrete	12.5
Bldg. 57	1 <sup>st</sup> Floor Stairwell I-Beams	Red	Steel	3.4
Bldg. 57	1 <sup>st</sup> Floor Stairwell Deck	Gray	Steel	1.7
Bldg. 57	Exterior Fire Hose Connections	Red	Metal	1.5
Bldg. 57	Attic I-Beams	Orange	Steel	7.7-13.2
Bldg. 57	Attic Stairwell Hand Rails	Black	Metal	9.9
Bldg. 57	3 <sup>rd</sup> Floor Old Window Frames	White	Metal	4.8
Bldg. 57	2 <sup>nd</sup> Floor Old Window Frames	White	Metal	4.0-20.2
Bldg. 57	2 <sup>nd</sup> Floor Stairwell-Handrail, Riser and Stringers	Gray	Metal	2.5-4.1
Bldg. 62	Exterior Bldg.	Cream	Stucco/Plaster	7.7
Bldg. 62	Window Frames	Cream	Metal	4.2
Bldg. 62	Stairwell Chase	White	Metal	4.4
Bldg. 62	Exterior Bldg.	White	Stucco/Plaster	18
Bldg. 62	Exterior Grates (Cover) to Crawl Space	Brown	Metal	1.4-1.6


**TABLE TWO**  
**LEAD BASED PAINT and LEAD IN BUILDING MATERIALS REMAINING**  
**SURVEY UPDATE (as of Dec. 22, 2008)**

Building #	Description	Color	Substrate	Reading (mg/cm <sup>2</sup> )
Bldg. 62	Exterior Loading Dock Guards	Yellow	Metal	1.4
Bldg. 62	Penthouse Door and Door Frames	Gray	Metal	1.3-1.6
Bldg. 62	Penthouse Stairwell Handrails	Gray	Metal	3.4
Bldg. 62	2 <sup>nd</sup> Floor Central Stairwell Handrails	Green	Metal	1.8-4.6
Bldg. 62	2 <sup>nd</sup> Floor Central Stairwell Cages	White	Metal	4.8
Bldg. 62	2 <sup>nd</sup> Floor Stairwell Deck and Risers	Beige	Metal	1.3-7.4
Bldg. 63	Walkway Railing	Brown	Metal	3.0
Bldg. 63	Structure Beams	Red/Orange	Steel	>5
Bldg. 63	Handrail	Green	Metal	1.2
Bldg. 63	Crawl Space Covers	Brown/Black	Metal	1.1
Bldg. 63	Down Spout	Beige	Metal	1.6
Bldg. 63	Door Frame	Tan	Wood	2.2
Bldg. 63	Window Frame	White	Wood	2.1
Bldg. 64	Crawl Space Covers	Brown	Metal	>5
Bldg. 64	Crawl Space Windows	White	Metal	>5
Bldg. 64	1 <sup>st</sup> Floor Door Frames	Lt. Blue	Metal	3.5
Bldg. 64	1 <sup>st</sup> Floor Windows	Beige	Wood	2.5
Bldg. 64	1 <sup>st</sup> Floor Fireplace	White	Wood	1.4
Bldg. 64	1 <sup>st</sup> Floor Window Sills	White	Wood	>5

Notes: The HUD residential, unrestricted concentration for lead based paint is 1.0 g/cm<sup>2</sup>.

The description is painted item with lead paint exceeding the 1.0 g/cm<sup>2</sup>, unless otherwise noted.

## FIGURES





NOTE:

- = LEAD SOIL SAMPLE > 400 PPM
- ◐ = LEAD SOIL SAMPLE < 400 PPM

C06338 GULFPORT-BUILDING 1  
SOIL SAMPLE LOCATIONS

<b>AMI</b> Environmental		DRAWING TITLE ENVIRONMENTAL ASSESSMENT GULFPORT-VA MEDICAL HOSPITAL 200 EAST BEACH BLVD. GULFPORT MS, 39507		
8802 S. 135th St. SUITE 100 OMAHA NE, 68136		DRAWN BY MICHAEL HAYES	DRAWING NUMBER C06338	DATE 05-07-2008
SIZE	SCALE	AS SHOWN	SHEET	15






C06338 GULFPORT-BUILDING 2  
SOIL SAMPLE LOCATIONS

		DRAWING TITLE ENVIRONMENTAL ASSESSMENT GULFPORT-VA MEDICAL HOSPITAL 200 EAST BEACH BLVD. GULFPORT MS, 39507			
Environmental		DRAWN BY MICHAEL HAYES		DRAWING NUMBER C06338	DATE 05-07-2008
8802 S. 135th St. SUITE 100 OMAHA NE, 68138	PH (402)397-5001 FAX (402)397-3313	SIZE	SCALE	AS SHOWN	SHEET 11






NOTE	
	= LEAD SOIL SAMPLE > 400 PPM
	= LEAD SOIL SAMPLE < 400 PPM

C06338 GULFPORT-BUILDING 3  
SOIL SAMPLE LOCATIONS

<b>AMI</b>		DRAWING TITLE ENVIRONMENTAL ASSESSMENT GULFPORT-VA MEDICAL HOSPITAL 200 EAST BEACH BLVD. GULFPORT MS, 39507		
Environmental		OWN BY MICHAEL HAYES	DRAWING NUMBER C06338	DATE 05-07-2008
8802 S. 135th St SUITE 100 OMAHA NE, 68138	PH (402)397-5001 FAX (402)397-3313	SIZE AS SHOWN	SCALE AS SHOWN	SHEET 11




AMMI



SUITE 100		OMAHA NE, 68138	FAX (402) 397-3313
SUITE 100		PH (402) 397-5001	
MICHAEL HAYES		DATE 05-07-2008	
DRAWING NUMBER		AS SHOWN	11
DRAWING TITLE		ENVIRONMENTAL ASSESSMENT	
GULFPORT-VA MEDICAL HOSPITAL		GULFPORT MS, 39507	
200 EAST BEACH BLVD.			




C06338 GULFPORT-BUILDING 4  
SOIL SAMPLE LOCATIONS



NOTE:

- (Large Circle) = LEAD SOIL SAMPLE > 400 PPM
- (Small Circle) = LEAD SOIL SAMPLE < 400 PPM




**NOTE:**

- = LEAD SOIL SAMPLE > 400 PPM
- = LEAD SOIL SAMPLE < 400 PPM

C06338 GULFPORT-BUILDING 5  
SOIL SAMPLE LOCATIONS

<b>AMI</b>		DRAWING TITLE	ENVIRONMENTAL ASSESSMENT GULFPORT-VA MEDICAL HOSPITAL 200 EAST BEACH BLVD. GULFPORT MS, 39507		
Environmental		OWN BY	DRAWING NUMBER		DATE
8802 S. 133rd St. SUITE 100 OMAHA NE, 68138		MICHAEL HAYES	C06338		05-07-2008
		SIZE	SCALE	AS SHOWN	SHEET
					10






NOTE:

- = LEAD SOIL SAMPLE > 400 PPM
- = LEAD SOIL SAMPLE < 400 PPM

C06338 GULFPORT-BUILDING 41  
SOIL SAMPLE LOCATIONS

<b>AMI</b>	DRAWING TITLE ENVIRONMENTAL ASSESSMENT GULFPORT-VA MEDICAL HOSPITAL 200 EAST BEACH BLVD. GULFPORT MS, 39507		
Environmental	OWN BY MICHAEL HAYES	DRAWING NUMBER C06338	DATE 05-07-2008
8802 S. 135th St. SUITE 100 OMAHA NE, 68136	SIZE PH (402)397-5001 FAX (402)397-3313	SCALE AS SHOWN	SHEET 11






C06338 GULFPORT-BUILDING 57  
SOIL SAMPLE LOCATIONS




<b>AMI</b>		DRAWING TITLE ENVIRONMENTAL ASSESSMENT GULFPORT-VA MEDICAL HOSPITAL 200 EAST BEACH BLVD. GULFPORT MS, 39507		
Environmental		OWN BY MICHAEL HAYES	DRAWING NUMBER C06338	DATE 05-07-2008
8802 S. 135th ST. SUITE 100 OMAHA NE, 68136	PH (402)397-5001 FAX (402)397-3313	SIZE AS SHOWN	SCALE AS SHOWN	SHEET 10



C06338 GULFPORT-BUILDING 62  
SOIL SAMPLE LOCATIONS

	AMI	DRAWING TITLE ENVIRONMENTAL ASSESSMENT GULFPORT-VA MEDICAL HOSPITAL 200 EAST BEACH BLVD. GULFPORT MS, 39507		
Environmental		OWN BY MICHAEL HAYES	DRAWING NUMBER C06338	DATE 05-07-2008
8802 S. 135th St. SUITE 100 OMAHA NE, 68138		SIZE AS SHOWN	SCALE AS SHOWN	SHEET 11





NOTE:


- - LEAD SOIL SAMPLE > 400 PPM
- - LEAD SOIL SAMPLE < 400 PPM

C06338 GULFPORT-BUILDING 64  
SOIL SAMPLE LOCATIONS

	DRAWING TITLE ENVIRONMENTAL ASSESSMENT GULFPORT-VA MEDICAL HOSPITAL 200 EAST BEACH BLVD. GULFPORT MS, 39507		
8802 S. 135th St SUITE 100 OMAHA NE, 68138	OWN BY MICHAEL HAYES	DRAWING NUMBER C06338	DATE 05-07-2008
PH (402)397-5001 FAX (402)397-3313	SIZE AS SHOWN	SCALE AS SHOWN	SHEET 11



ATTACHMENT 1



## ATTACHMENT 2

REVISED PROPERTY DESCRIPTION: (AS PER SURVEY):

COMMENCING FROM A 1" IRON ROD FOUND, BEGINNING THE POINT COMMON TO SECTIONS 35 & 36 TOWNSHIP 7 SOUTH, RANGE 11 WEST & SECTIONS 2 & 1 TOWNSHIP 8 SOUTH, RANGE 11 WEST, LOCATED WITHIN THE CITY OF GULFPORT, FIRST JUDICIAL DISTRICT, HARRISON COUNTY, MISSISSIPPI, MORE PARTICULARLY DESCRIBED AS THE NORTHWEST CORNER OF SECTION 1, TOWNSHIP 8 SOUTH, RANGE 11 WEST; THENCE EAST, A DISTANCE OF 793.12', TO A POINT; THENCE SOUTH, A DISTANCE OF 1316.65', TO A 3" FENCE CORNER ON THE SOUTHERN MARGIN OF THE NOW C.S.X. TRANSPORTATION RAILROAD RIGHT OF WAY, A.K.A. LOUISVILLE AND NASHVILLE RAILROAD, SAID POINT BEING THE (P.O.B.) POINT OF BEGINNING; THENCE S00°18'17"W, A DISTANCE OF 1138.62', TO A (C.M.S.) CONCRETE MONUMENT SET, ON THE NORTHERN MARGIN OF U.S. HIGHWAY 90 MARGIN AND THE POINT OF A NON-TANGENT CURVE, TO THE LEFT, HAVING A RADIUS OF 1777.08', WITH A DELTA ANGLE OF 3°17'54", A CHORD BEARING OF S70°28'14"W AND A CHORD DISTANCE OF 102.29'; THENCE ALONG SAID CURVE AND NORTHERN MARGIN, AN ARC DISTANCE OF 102.30', TO A (C.M.S.) CONCRETE MONUMENT SET; THENCE S67°09'03"W, ALONG SAID MARGIN, A DISTANCE OF 1725.36', TO A 3" FENCE POST, ON THE EAST BOUNDARY OF GREENWOOD ADDITION TO GULFPORT, MISSISSIPPI, RECORDED ON DECEMBER 8, 1906 IN OLD PLAT BOOK 5, PAGE 190; THENCE N0°25'07"W, ALONG THE SAID EAST BOUNDARY OF GREENWOOD ADDITION, A DISTANCE OF 1337.51', TO A (C.M.S.) CONCRETE MONUMENT SET, ON THE SOUTHERN RIGHT OF WAY OF C.S.X. TRANSPORTATION RAILROAD, A.K.A. LOUISVILLE AND NASHVILLE RAILROAD; THENCE N73°28'01"E, A DISTANCE OF 1775.62', TO THE POINT OF BEGINNING.


SAID PROPERTY CONTAINING 48.06 ACRES, MORE OR LESS.

ATTACHMENT 3

BUILDING SCHEDULE

A compass rose at the top left indicates cardinal directions (N, S, E, W) and intermediate points (NE, SE, SW, NW). Below it is a scale bar labeled "SCALE 1:10000".

SCALAR FIELDS



Administration

PROJECT TITLE <b>ELECTRICAL UTILITY PLAN</b>		DATE 10/10/01	PREPARED BY John Doe	REVIEWED BY John Doe	APPROVED BY John Doe
SUBDIVISION Subdivision One		STREET Main Street	SECTION S.E.	LOT NUMBER Lot 1	OWNER John Doe
GENERAL COMMENTS None		NOTICE OF UNDERGROUND & AERIAL ELECTRICAL UTILITIES			
NOTICE IS HEREBY GIVEN THAT THE OWNER OF THE FOREGOING PROPERTY HAS BEEN NOTIFIED AND HAS CONSENTED TO THE LOCATING AND EXCAVATION OF UNDERGROUND AND AERIAL ELECTRICAL UTILITIES IN THE FOREGOING PROPERTY. THESE UTILITIES ARE LOCATED BETWEEN THE POINTS MAIN STREET AND LOT 1.					

8-18-13

B.R.D. NO. 145075, EDITION 1, GRADE 10, UNIT 1, SUBJECT		TRANSLATION
1	1	KODOMO
2	2	KODOMO
3	3	KODOMO
4	4	KODOMO
5	5	KODOMO
6	6	KODOMO
7	7	KODOMO
8	8	KODOMO
9	9	KODOMO
10	10	KODOMO
11	11	KODOMO
12	12	KODOMO
13	13	KODOMO
14	14	KODOMO
15	15	KODOMO
16	16	KODOMO
17	17	KODOMO
18	18	KODOMO
19	19	KODOMO
20	20	KODOMO
21	21	KODOMO
22	22	KODOMO
23	23	KODOMO
24	24	KODOMO
25	25	KODOMO
26	26	KODOMO
27	27	KODOMO
28	28	KODOMO
29	29	KODOMO
30	30	KODOMO
31	31	KODOMO
32	32	KODOMO
33	33	KODOMO
34	34	KODOMO
35	35	KODOMO
36	36	KODOMO
37	37	KODOMO
38	38	KODOMO
39	39	KODOMO
40	40	KODOMO
41	41	KODOMO
42	42	KODOMO
43	43	KODOMO
44	44	KODOMO
45	45	KODOMO
46	46	KODOMO
47	47	KODOMO
48	48	KODOMO
49	49	KODOMO
50	50	KODOMO
51	51	KODOMO
52	52	KODOMO
53	53	KODOMO
54	54	KODOMO
55	55	KODOMO
56	56	KODOMO
57	57	KODOMO
58	58	KODOMO
59	59	KODOMO
60	60	KODOMO
61	61	KODOMO
62	62	KODOMO
63	63	KODOMO
64	64	KODOMO
65	65	KODOMO
66	66	KODOMO
67	67	KODOMO
68	68	KODOMO
69	69	KODOMO
70	70	KODOMO
71	71	KODOMO
72	72	KODOMO
73	73	KODOMO
74	74	KODOMO
75	75	KODOMO
76	76	KODOMO
77	77	KODOMO
78	78	KODOMO
79	79	KODOMO
80	80	KODOMO
81	81	KODOMO
82	82	KODOMO
83	83	KODOMO
84	84	KODOMO
85	85	KODOMO
86	86	KODOMO
87	87	KODOMO
88	88	KODOMO
89	89	KODOMO
90	90	KODOMO
91	91	KODOMO
92	92	KODOMO
93	93	KODOMO
94	94	KODOMO
95	95	KODOMO
96	96	KODOMO
97	97	KODOMO
98	98	KODOMO
99	99	KODOMO
100	100	KODOMO

LSE & ECONOMIC HISTORY OF INSTITUTIONS

二、新編藏書目錄卷之三

1

卷之三

## ATTACHMENT 4

CERTIFICATE OF FINAL INSPECTIONPROJECT NAME: V/A Gulfport - Bld 3DATE: 10/24/07PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: Gulfport V.A.Building Owner Point of Contact: Ben Cox

## Building Owner Representative

Gary Petersen  
Signature

Date: 10/24/07

Gary Petersen  
Printed Name

Title: PMCompany Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Pablo Cerrillo  
Signature

Date: 10/24/07

Pablo Cerrillo  
Printed Name

Title: SupervisorCompany Representing: Sterling Co

## Building Owner's Point of Contact/Representative

Signature

Date: 

Printed Name

Title: Company Representing: 

## Specifics or Limitations to Inspection:

Removal of 25,000 VFT & Mastics from Building

**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: VA Gulfport - Bld 3DATE: 1/23/08PROJECT LOCATION: Gulfport, MSPHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: Gulfport VABuilding Owner Point of Contact: Ben Cole

## Building Owner Representative

Gary Petersen  
Signature

Date: 1/23/08

Gary Petersen  
Printed Name

Title: PMCompany Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Signature

Date: 1/23/08

Pablo Cervillo  
Printed Name

Title: SupervisorCompany Representing: Sterling Co.

## Building Owner's Point of Contact/Representative

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

## Specifics or Limitations to Inspection:

Removal of 25,000 sq ft "Leveler" + Mastic from  
Building

**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: VA Gulfport, Bldg 5DATE: 12/5/07PROJECT LOCATION: Gulfport, MSPHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: VA GulfportBuilding Owner Point of Contact: Ben Coe

## Building Owner Representative

Gary E. Petersen  
Signature

Date: 12/5/07

Gary E Petersen  
Printed Name

Title: PMCompany Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Pablo Cerrillo  
Signature

Date: 12/5/07

PABLO CERRILLO  
Printed Name

Title: SupervisorCompany Representing: STERLING CO.

## Building Owner's Point of Contact/Representative

Signature

Date:

Printed Name

Title:

Company Representing:

## Specifics or Limitations to Inspection:

Removal of 3,600 sq ft of VFT & Mastic + 2 ft TSF from  
Building 5

**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: V.A. GulfportDATE: 2/22/08PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: Gulfport V.A.Building Owner Point of Contact: Ben Coe

## Building Owner Representative

Gary PetersenDate: 2/22/08

Signature

Gary PetersenTitle: PM.

Printed Name

Company Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Signature

Date: 2-22-08CESAR R 2010ynTitle: Supervisor

Printed Name

Company Representing: STERLING

## Building Owner's Point of Contact/Representative

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

## Specifics or Limitations to Inspection:

Bld 57 1<sup>st</sup>, 2<sup>nd</sup>, + 3<sup>rd</sup> Floors A 5,000 Sqft VFT, L evelor, & Mastic Removal.

CERTIFICATE OF FINAL INSPECTIONPROJECT NAME: V.A. GulfportDATE: 8/1/07PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: V.A. GulfportBuilding Owner Point of Contact: Ben Core

## Building Owner Representative

Gary Petersen  
Signature \_\_\_\_\_ Date: 8/1/07

Gary Petersen  
Printed Name \_\_\_\_\_ Title: PM

Company Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Carlos Garcia  
Signature \_\_\_\_\_ Date: 8/2/07

Carlos Garcia  
Printed Name \_\_\_\_\_ Title: Supervisor

Company Representing: D.H. Griffin Wrecking Co.

## Building Owner's Point of Contact/Representative

Signature \_\_\_\_\_ Date: \_\_\_\_\_

Printed Name \_\_\_\_\_ Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

## Specifics or Limitations to Inspection:

Bldg 60, Back room, VFT + Mastic removal, 800 Sq ft, + office, 150 Sq ft,  
Fire Doors are wood Core

# CERTIFICATE OF FINAL INSPECTION

PROJECT NAME: VA, Gulfport  
 PROJECT LOCATION: Gulfport, MS.

DATE: 8/31/07  
 PHASE: II

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: VA, Gulfport

Building Owner Point of Contact: Ben Cole

**Building Owner Representative**

Gary Petersen  
 Signature

Date: 8/31/07  
 Title: PM

Printed Name: Gary Petersen  
 Company Representing: AMI ENVIRONMENTAL

**Remediation Company's Designated Person/Representative**

Scott L. Williams  
 Signature

Date: 8/31/07

Scott L. Williams  
 Printed Name

Title: Super

Company Representing: DH Griffin

**Building Owner's Point of Contact/Representative**

Signature

Date:

Printed Name

Title:

Company Representing:

**Specifics or Limitations to Inspection:**

Bldg 60, Exterior Skin coat removal, Approx 4,400 sq ft.

# CERTIFICATE OF FINAL INSPECTION

PROJECT NAME: V.A.Gulfport - Bld 63

DATE: 8/10/07

PROJECT LOCATION: Gulfport, MS

PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278

Building Owner:

V.A. Gulfport

Building Owner Point of Contact:

Ben Cee

Building Owner Representative

Gary Petersen  
Signature

Date: 8/10/07

Gary Petersen  
Printed Name

Title: PM

Company Representing: AMI ENVIRONMENTAL

Remediation Company's Designated Person/Representative

Saul Rodriguez  
Signature

Date: 8/10/07

Saul Rodriguez  
Printed Name

Title: SUPERVISOR

Company Representing: DH GRIFFIN

Building Owner's Point of Contact/Representative

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

Specifics or Limitations to Inspection:

Chapel - Wall texturing Removal, 2,600 Sq ft

VFT+<sup>Magic</sup> Sheet flooring removal, 3,700 Sq ft

## CERTIFICATE OF FINAL INSPECTION

PROJECT NAME: VA Gulfport Bldg 64DATE: 12/19/07PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: VA Gulfport  
Building Owner Point of Contact: Ben Cac

**Building Owner Representative**

Gary E. Petersen Date: 12/19/07  
*Signature* Title: PM  
Gary E. Petersen  
*Printed Name*

Company Representing: AMI ENVIRONMENTAL**Remediation Company's Designated Person/Representative**

Pablo Cerrillo Date: 12-19-07  
*Signature* Title: Supervisor.  
Pablo Cerrillo  
*Printed Name*

Company Representing: STERLING CO.**Building Owner's Point of Contact/Representative**

*Signature* Date: \_\_\_\_\_  
*Printed Name* Title: \_\_\_\_\_  
Company Representing: \_\_\_\_\_

**Specifics or Limitations to Inspection:**

Removal of 20,000 Sqft VFT & Mastic, 400 L ft TSI Pipes

**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: VA Gulfport - Bldg 64DATE: 3/27/08PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278Building Owner: Vetrans AdministrationBuilding Owner Point of Contact: Ben Coe

## Building Owner Representative

Gary Petersen

Signature

Gary Petersen

Printed Name

Date:

3/27/08PMCompany Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Signature

ECSDR → Zolby

Printed Name

Date:

3-27-08

Title:

SupervisorCompany Representing: C Terrell

## Building Owner's Point of Contact/Representative

Signature

Date:

Printed Name

Title:

Company Representing:

## Specifics or Limitations to Inspection:

Powerwash approx 15,000 Sq ft of Exterior of Building

**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: V.A GulfportDATE: 7/26/07PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: V.A. GulfportBuilding Owner Point of Contact: Ben Cole**Building Owner Representative**

<u>Gary Peterson</u> <i>Signature</i>	Date: <u>7/26/07</u>
<u>Gary Peterson</u> <i>Printed Name</i>	Title: <u>PM</u>

Company Representing: AMI ENVIRONMENTAL**Remediation Company's Designated Person/Representative**

<u>Carlos Garcia</u> <i>Signature</i>	Date: <u>7/31/07</u>
<u>Carlos Garcia</u> <i>Printed Name</i>	Title: <u>Supervisor</u>

Company Representing: DH-Griffith**Building Owner's Point of Contact/Representative**

<i>Signature</i>	Date: _____
<i>Printed Name</i>	Title: _____

Company Representing: \_\_\_\_\_

**Specifics or Limitations to Inspection:**

9x9" VFT + Mastic removal, 8,280 sqft. Bldg 117


**CERTIFICATE OF FINAL INSPECTION**

PROJECT NAME: V. A. Gulfport DATE: 8/26/08  
 PROJECT LOCATION: Gulfport, MS. PHASE: II

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: J.A.  
 Building Owner Point of Contact: TBEN COE

Building Owner Representative	Date:
	<u>8/26/08</u>
Signature	
<u>Tony BATES</u>	Title: <u>Project Manager</u>
Printed Name	
Company Representing:	AMI ENVIRONMENTAL

Remediation Company's Designated Person/Representative	Date:
	<u>8/26/08</u>
Signature	
<u>Rodney Sykes</u>	Title: <u>Supervisor</u>
Printed Name	
Company Representing:	<u>Sterling Construction</u>

Building Owner's Point of Contact/Representative	Date:
	
Signature	
	
Printed Name	
Company Representing:	

Specifics or Limitations to Inspection:	<u>Final inspection on Bldg 3</u>
<u>1st and second floor after all abatement</u>	

# CERTIFICATE OF FINAL INSPECTION

PROJECT NAME: V.A. Gulf Port, MSDATE: 8/14/08PROJECT LOCATION: Gulf Port, MSPHASE: Bldg 5

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: V.A.Building Owner Point of Contact: Ben COE

Building Owner Representative

Signature

Date:

8/14/08

Printed Name

Tony Bates

Title:

Project Manager

Company Representing:

AMI ENVIRONMENTAL

Remediation Company's Designated Person/Representative

Signature

Date:

8/14/08

Printed Name

Rodney Sykes

Title:

SupervisorCompany Representing: Sterling

Building Owner's Point of Contact/Representative

Signature

Date:

Printed Name

Title:

Company Representing:

Specifics or Limitations to Inspection:

Final inspection of Bldg 5After clearances

CERTIFICATE OF FINAL INSPECTIONPROJECT NAME: V.A GulfportDATE: 7/26/07PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: V.A. GulfportBuilding Owner Point of Contact: Ben Core

## Building Owner Representative

Gary Petersen  
Signature  
Gary Petersen  
Printed Name

Date: 7/26/07  
Title: PM

Company Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Carlos Garcia  
Signature  
Carlos Garcia  
Printed Name

Date: 7/31/07  
Title: Supervisor

Company Representing: DH-Griffith

## Building Owner's Point of Contact/Representative

Signature  
  
Printed Name

Date: \_\_\_\_\_  
Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

## Specifics or Limitations to Inspection:

9x9" VFT + Mastic removal, 8,280 sqft. Bldg 117

CERTIFICATE OF FINAL INSPECTIONPROJECT NAME: V.A GulfportDATE: 8/1/07PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: V.A. GulfportBuilding Owner Point of Contact: Ben Core

## Building Owner Representative

Gary Petersen  
Signature \_\_\_\_\_ Date: 8/1/07

Gary Petersen  
Printed Name \_\_\_\_\_ Title: PM

Company Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Carlos Garcia  
Signature \_\_\_\_\_ Date: 8/2/07

Carlos Garcia  
Printed Name \_\_\_\_\_ Title: Supervisor

Company Representing: D.H. Griffin Wrecking Co.

## Building Owner's Point of Contact/Representative

Signature \_\_\_\_\_ Date: \_\_\_\_\_

Printed Name \_\_\_\_\_ Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

## Specifics or Limitations to Inspection:

Bldg 60, Back room, VFT + Mastic removed, 800 Sq ft, +  
office, 150 Sq ft,  
Fire Doors are wood Core

## CERTIFICATE OF FINAL INSPECTION

PROJECT NAME: V.A. Gulfport - Bld 63

DATE: 8/10/07

PROJECT LOCATION: Gulfport, MS

PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278

Building Owner: V.A. Gulfport

Building Owner Point of Contact: Ben Cee

**Building Owner Representative**

Gary Petersen  
Signature

Date: 8/10/07

Gary Petersen  
Printed Name

Title: PM

Company Representing: AMI ENVIRONMENTAL

**Remediation Company's Designated Person/Representative**

Sue Park  
Signature

Date: 8/10/07

Saul Rodriguez  
Printed Name

Title: SUPERVISOR

Company Representing: DH GRIFFIN

**Building Owner's Point of Contact/Representative**

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

**Specifics or Limitations to Inspection:**

Chapel - Wall texturing Removal, 2,600 Sq ft

VFT + <sup>Mastic</sup> Sheet flooring removal, 3,700 Sq ft

# CERTIFICATE OF FINAL INSPECTION

PROJECT NAME: VA, Gulfport

DATE: 8/31/07

PROJECT LOCATION: Gulfport, MS.

PHASE: II

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278

Building Owner: VA, Gulfport

Building Owner Point of Contact: Ben Cole

**Building Owner Representative:**

Gary Petersen  
Signature

Date: 8/31/07

Gary Petersen  
Printed Name

Title: PM

Company Representing: AMERICAN ENVIRONMENTAL

**Remediation Company's Designated Person/Representative**

Deonika Williams  
Signature

Date: 8/31/07

Deonika Williams  
Printed Name

Title: Super

Company Representing: DH Griffin

**Building Owner's Point of Contact/Representative**

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

**Specifics or Limitations to Inspection:**

Bldg 60, Exterior Skin coat removal, Approx 4,400 sq ft.

## CERTIFICATE OF FINAL INSPECTION

PROJECT NAME: VA Gulfport - Bid 3DATE: 10/24/07PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: Co7278Building Owner: Gulfport V.A.Building Owner Point of Contact: Ben Cox**Building Owner Representative**

Gary Petersen  
Signature

Date: 10/24/07

Gary Petersen  
Printed Name

Title: PMCompany Representing: AMI ENVIRONMENTAL**Remediation Company's Designated Person/Representative**

Pablo Cerrillo  
Signature

Date: 10/24/07

Pablo Cerrillo  
Printed Name

Title: SupervisorCompany Representing: Sterling Co**Building Owner's Point of Contact/Representative**

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

**Specifics or Limitations to Inspection:**

Removal of 25,000 VFT & Mastics from Building

**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: VA Gulfport, Bldg 5DATE: 12/15/07PROJECT LOCATION: Gulfport, MSPHASE: TII

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278Building Owner: VA GulfportBuilding Owner Point of Contact: Ben Coe

## Building Owner Representative

Gary E. Petersen  
Signature

Date: 12/15/07

Gary E Petersen  
Printed Name

Title: PMCompany Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Pablo Cerrillo  
Signature

Date: 12/15/07

PABLO CERRILLO  
Printed Name

Title: SUPERVISORCompany Representing: STERLING CO.

## Building Owner's Point of Contact/Representative

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

## Specifics or Limitations to Inspection:

Removal of 3,600 sq ft of VFT + Mastic + 2 ft TSF from  
Building 5

**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: VA Gulfport Bldg 64DATE: 12/19/07PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: VA Gulfport  
 Building Owner Point of Contact: Ben Case

## Building Owner Representative

Gary E. Petersen Signature Date: 12/19/07  
Gary E. Petersen Printed Name Title: PM

Company Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Pablo Cerrillo Signature Date: 12-19-07  
Pablo Cerrillo Printed Name Title: Supervisor.

Company Representing: STERLING CO.

## Building Owner's Point of Contact/Representative

Signature Date: \_\_\_\_\_  
 Printed Name Title: \_\_\_\_\_  
 Company Representing: \_\_\_\_\_

## Specifics or Limitations to Inspection:

Removal of 20,000 Sqft VFT & Mastic, 700 L ft TSI Pipes

CERTIFICATE OF FINAL INSPECTIONPROJECT NAME: VA Gulfport - Bld 3DATE: 1/23/08PROJECT LOCATION: Gulfport, MSPHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: Co7278Building Owner: Gulfport VABuilding Owner Point of Contact: Ben Cole

## Building Owner Representative

Gary Petersen  
Signature

Date: 1/23/08

Gary Petersen  
Printed Name

Title: PMCompany Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Signature

Pablo Cervillo  
Printed Name

Date: 1/23/08Title: SupervisorCompany Representing: Sterling Co.

## Building Owner's Point of Contact/Representative

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

## Specifics or Limitations to Inspection:

Removal of 25,000 Sq ft "Leveler" & Mastic from  
Building

**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: V.A. GulfportDATE: 2/22/08PROJECT LOCATION: Gulfport, MS.PHASE: DF

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: Gulfport V.A.Building Owner Point of Contact: Ben Coe

## Building Owner Representative

Gary Petersen

Signature

Date: 2/22/08Gary Petersen

Printed Name

Title: PM.Company Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Signature

CesarDate: 2-22-08

Printed Name

CESAR 12 26/08/08Title: SupervisorCompany Representing: Stealing

## Building Owner's Point of Contact/Representative

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

## Specifies or Limitations to Inspection:

Bld 57 1<sup>st</sup>, 2<sup>nd</sup>, + 3<sup>rd</sup> Floors A 5,000 Sq Ft VFT, L evelor, + Mastic Removal.

**CERTIFICATE OF FINAL INSPECTION**

PROJECT NAME: VA Gulfport - Bldg 64

DATE: 3/27/08

PROJECT LOCATION: Gulfport, MS.

PHASE: TH


In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278


Building Owner: Veterans Administration

Building Owner Point of Contact: Ben Cre

Building Owner Representative



Signature



Printed Name

Date:


3/27/08

Title:

PM

Company Representing: AMI ENVIRONMENTAL

Remediation Company's Designated Person/Representative



Date:


3-27-08



Title:

Supervisor

Company Representing:



Building Owner's Point of Contact/Representative




Date:



Title:

Company Representing:

Specifics or Limitations to Inspection:




**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: V.A GulfportDATE: 8/14/08PROJECT LOCATION: Gulfport, MSPHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: V.A.Building Owner Point of Contact: Benjamin Coe

Building Owner Representative

Signature

  
Tony Bates

Printed Name

Company Representing: AMI ENVIRONMENTAL

Date:

8/14/08

Title:

Project Manager

## Remediation Company's Designated Person/Representative

Signature

Date:

Printed Name

Title:

Company Representing: Sterling

## Building Owner's Point of Contact/Representative

Signature

Date:

Printed Name

Title:

Company Representing:

Specifics or Limitations to Inspection: Bldg 5 1<sup>st</sup> And 2<sup>nd</sup> floortile, Mastic, ceiling removed.Exterior skim coat @ c1% remainsRoof vent flashing @ 2% remains

# CERTIFICATE OF FINAL INSPECTION

PROJECT NAME: V.A. GulfportDATE: 8/26/08PROJECT LOCATION: Gulfport, MS.PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: CO728Building Owner: V.A.Building Owner Point of Contact: Benjamin Coe

Building Owner Representative

Signature

Date:

8/26/08

Printed Name

Tony Bates

Title:

Project ManagerCompany Representing: AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Signature

Date:

Printed Name

Title:

Company Representing: Dell Griffin Sterling

## Building Owner's Point of Contact/Representative

Signature

Date:

Printed Name

Title:

Company Representing:

Specifics or Limitations to Inspection: Bldg 3 1<sup>st</sup> And 2<sup>nd</sup> floor  
tile and mastic removed. Textured Paint @ 2% and  
≤ 1% remains. Exterior Skim coat @ < 1% remains  
Roofing paper @ 10% remains

**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: V.A. Gulfport  
PROJECT LOCATION: Gulfport, MS.DATE: 10/23/08  
PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: 087278 Building Owner: V.A.Building Owner Point of Contact: Ben Coe

Building Owner Representative	
Signature	Date: <u>10/23/08</u>
<u>Tony L. Bates</u>	Title: <u>Project Manager</u>
Printed Name	
Company Representing:	AMI ENVIRONMENTAL

Remediation Company's Designated Person/Representative	
Signature	Date: <u>10/23/08</u>
<u>Scottie Williams</u>	Title: <u>Supervisor</u>
Printed Name	
Company Representing:	<u>D. H. Griffin</u>

Building Owner's Point of Contact/Representative	
Signature	Date: <u>10/23/08</u>
Printed Name	Title: <u>Resident Engineer</u>
Company Representing:	<u>V.A.</u>

Specifics or Limitations to Inspection:	<u>Building 2 second floor floor tile and mastic, first floor floor tile and mastic, outside skim coat. Building demolished after visual and clearances good. Back half</u>
---	---

089

8802 S. 135<sup>th</sup> Street, Suite 100  
Omaha, NE 68138  
Phone (402)397-5001  
Fax (402)397-3313

# CERTIFICATE OF FINAL INSPECTION


PROJECT NAME: V.A. Gulfport  
PROJECT LOCATION: Gulfport, MS.

DATE: 12/4/08  
PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: 007278 Building Owner: V.A.

Building Owner Point of Contact: Benjamin Coe

Building Owner Representative	
	Date: <u>12/4/08</u>
Signature	
<u>Tony Bates</u>	Title: <u>Project Manager</u>
Printed Name	
Company Representing:	AMI ENVIRONMENTAL

Remediation Company's Designated Person/Representative	
Signature	Date: _____
Printed Name	Title: _____
Company Representing:	<u>D.H. Griffin</u>

Building Owner's Point of Contact/Representative	
Signature	Date: _____
Printed Name	Title: _____
Company Representing:	

Specifics or Limitations to Inspection:	<u>Bldg 4 1<sup>st</sup> and 2<sup>nd</sup> Floor</u>
<u>tile, mastic, ceiling removed</u>	
<u>Exterior Skimcoat @ 4% remains</u>	
<u>Roof Flashing @ 3% remains</u>	

# CERTIFICATE OF FINAL INSPECTION

PROJECT NAME: V.A. Gulfport  
PROJECT LOCATION: Gulfport, MS.

DATE: 12-10-08  
PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: V.A.

Building Owner Point of Contact: Benjamin Coe

Building Owner Representative

Signature

Date: 12-10-08

Printed Name

Tony Bates

Title: Project Manager

Company Representing:

AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: D.H. Griffin

## Building Owner's Point of Contact/Representative

Signature

Date: \_\_\_\_\_

Printed Name

Title: \_\_\_\_\_

Company Representing: \_\_\_\_\_

Specifics or Limitations to Inspection: Building 57 Spot removal of skin coat after Stairtower Demo  
Exterior skin coat @ 3% remains on rest of building HVAC @ 1% remains.

**CERTIFICATE OF FINAL INSPECTION**PROJECT NAME: V.A. GulfportDATE: 12/16/08

PROJECT LOCATION:

PHASE: III

In accordance with the Removal and Disposal Plan, I hereby certify that I have visually inspected the designated work area(s) and that all surfaces have been found to be clean of visual dust, debris, or residue. The area(s) is designated by the scope of work on file with the appropriate State or Local Governmental Regulatory Agency.

AMI Project Number: C07278 Building Owner: V.A.Building Owner Point of Contact: Benjamin Coe

## Building Owner Representative

Signature

  
Tony Bates

Printed Name

Date:

12/16/08

Title:

Project Manager

Company Representing:

AMI ENVIRONMENTAL

## Remediation Company's Designated Person/Representative

Signature

Date:

Printed Name

Title:

Company Representing: D.H. Griffin

## Building Owner's Point of Contact/Representative

Signature

Date:

Printed Name

Title:

Company Representing:

Specifics or Limitations to Inspection: Bldg 2 1<sup>st</sup> and 2<sup>nd</sup> Floortile removed. 4" Mech fitting removed. Sink removedCeiling removed. Outside skimcoat removed.Window Glazing remains.

ATTACHMENT 5

**Lead Abatement Plan**  
**Gulfport VA, Building 001 – TO No. 45**  
Gulfport, MS

4. Waste Disposal Documentation
5. Negative Pressure Enclosure Recordings

## 7.0 Lead Material Identification

The following quantities outlined below, represent the materials scheduled for lead hazard abatement, removal, disposal and/or demolition.

Material	Description	Estimated Quantity
Ceramic Wall Tile (1")	1"x1" ceramic wall tiles (orange, red,	460 Sq Ft
Structural beams	Beige paint on interior structural beams/components	Throughout
Railing	Green paint on metal stair railing components	750 Ln Ft
Concrete Wall	Beige paint on concrete stairwell walls	2 @ 1,400 Sq Ft
X-ray Room Components	Olive painted x-ray room walls (either lead paint and/or lead sheeting within wall), view window, and door	2 @ 600 Sq Ft
Grills	Brown paint on exterior grills covering crawlspace openings	10 @ 4 Sq Ft
Sink	White porcelain glazed slop sink	4 @ 8 Sq Ft
Metal Stairwell components	Tan paint on stairwell steps, handrail, and beam/supports	3 @ 900 Sq Ft

**Lead Abatement Plan**  
**Gulfport VA, Building 002 - TO No. 45**  
**Gulfport, MS**

2. Bulk Sampling Reports
3. Final Clearance Statement
4. Waste Disposal Documentation
5. Negative Pressure Enclosure Recordings

## 7.0 Lead Material Identification

The following quantities outlined below, represent the materials scheduled for lead hazard abatement, removal, disposal and/or demolition.

Material	Description	Estimated Quantity
Exterior concrete	Beige and white paint on exterior concrete walls	46,200 Sq Ft
Windows	White and beige paint on wood window frame components	227 @ 26 Ln Ft
Door Frames	Gray, white paint on interior door frames	188 @ 16 Ln Ft
Door Frames	White, and brown paint on exterior door frames (wood and metal)	16 @ 16 Ln Ft
Stairwell components	Beige paint on interior stairwell components	3 @ 600 Sq Ft
Railing/components	Silver paint on exterior metal railing components	3 @ 200 Ln Ft
Railing/components	Silver paint on metal railing components	3 @ 100 Ln Ft
Gutters/downspouts/related components	Brown and beige paint on exterior gutter and downspout components, roof drains, and supports	24 @ 40 Ln Ft
Fire Hose Connection	Red paint at connection point and valve	3 @ 4 Sq Ft
Grills	Black paint on exterior grills covering crawlspace openings	38 @ 4 Sq Ft
Glazed Block	Peach and beige lead glazed wall block	2,000 Sq Ft
Ceramic tile	Black and white and off-white, yellow, & green glazed ceramic wall tile (4"x4", 2"x6" in kitchen area)	7,500 Sq Ft

**Lead Abatement Plan**  
**Gulfport VA, Building 002 – TO No. 45**  
**Gulfport, MS**

<b>Walls</b>	Gray and light gray paint on interior walls and columns	40,000 Sq Ft
<b>Ceilings</b>	Beige paint on concrete and plaster ceilings	28,000 Sq Ft
<b>Drinking Fountain</b>	White porcelain glazed fountain	1 @ 2 Sq Ft
<b>Sink</b>	White porcelain glazed bathroom sink	1 @ 4 Sq Ft
<b>Pipe Hangers</b>	Beige painted metal pipe hangers	20 @ 2 Sq Ft
<b>Concrete Columns</b>	Beige paint on exterior concrete columns	Included with Exterior

## 8.0 Sub-Contractors

A project sequencing and scheduling outline will be developed indicating the scope of work, date of use and duration of work for each Subcontractor. The following subcontractors have been selected and will be used during the course of this work:

Service	SubContractor	Point of Contact
Lead Abatement Contractor	[to be determined]	[to be determined]
Air Monitoring, Inspection DIH and IHT	[to be determined]	[to be determined]
Transportation	[to be determined]	[to be determined]
Disposal	[to be determined]	[to be determined]

## 9.0 Air, Bulk, Wipe and Waste Sampling

An independent Designated Industrial Hygienist (DIH) will ensure that hazardous materials are sampled in accordance with applicable OSHA and EPA standards, good industrial hygiene practices, and as required for lead based paint removal operations. Air, bulk and wipe sampling will be performed by an independent, qualified Industrial Hygiene Technician (IHT) approved by and under the direction of the DIH prior to work in each abatement area, during removal and at the completion of removal operations.

All air monitoring records will include the pump identification number, rotometer used, current calibration certificate, sample number, worker name and social security number, a detailed description of the nature and location of work, pump time on and time off,

**Lead Abatement Plan**  
 Gulfport VA, Building 003 - TO No. 45  
Gulfport, MS

2. Bulk Sampling Reports
3. Final Clearance Statement
4. Waste Disposal Documentation
5. Negative Pressure Enclosure Recordings

## 7.0 Lead Material Identification

The following quantities outlined below, represent the materials scheduled for lead hazard abatement, removal, disposal and/or demolition.

Material	Description	Estimated Quantity
Windows ✓	White and beige paint on wood window components (int/ext)	189 @ 12 Ln Ft
Ceramic tile ⚡	White glazed ceramic wall tile (4"x4") and red 1"x1" wall tile	1,100 Sq Ft
Sink ⚡	White porcelain glazed sinks	17 @ 4 Sq Ft
Tub ⚡	White porcelain glazed tubs	7 @ 45 Sq Ft
Toilets ⚡	White porcelain glazed Toilets	11 @ 6 Sq Ft
Water Inlet ✓	Red paint on cast water meter inlet, exterior, (Fire)	3 @ 5 Sq Ft
Walls ✓	Blue, pink, green and light green paint on plaster walls	3,600 Sq Ft
Grills ✓	Black painted crawl space grills	15 @ 4 Sq Ft

Check yellow and  
 white (ceiling and columns  
 on SW side)

**Lead Abatement Plan**

Gulfport VA, Building 004 – TO No. 45  
Gulfport, MS

2. Bulk Sampling Reports
3. Final Clearance Statement
4. Waste Disposal Documentation
5. Negative Pressure Enclosure Recordings

## **7.0 Lead Material Identification**

The following quantities outlined below, represent the materials scheduled for lead hazard abatement, removal, disposal and/or demolition.

Material	Description	Estimated Quantity
Windows	White paint on wood window frame (int/ext)	150 @ 12 Ln Ft
Grills	Black painted crawl space grills	16 @ 2 Sq Ft
Ceramic tile	White-glazed ceramic wall tile and wall base (4"x4"); red and orange wall tile (1"x1")	3,000 Sq Ft
Sinks	White porcelain glazed sink	33 @ 4 Sq Ft
Slopp Sinks	White porcelain glazed slopp Sinks	4 @ 6 Sq Ft
Toilet	White porcelain glazed toilets	36 @ 9 Sq Ft
Tub Fixtures	White porcelain glazed tub fixtures	7 @ 45 Sq Ft
Drinking Fountains	White porcelain glazed drinking fountains	1 @ 9 Sq Ft
Metal conduit	Orange paint on electrical conduit	2 @ 5' X 5"
Water valve	Red paint on cast iron exterior valve	2 @ 4 Sq Ft
Concrete Columns	Yellow paint on columns (behind drywall)	15+ @ 50 Sq Ft

**Lead Abatement Plan**  
 Gulfport VA, Building 005 - TO No. 45  
 Gulfport, MS

2. Bulk Sampling Reports
3. Final Clearance Statement
4. Waste Disposal Documentation
5. Negative Pressure Enclosure Recordings

## 7.0 Lead Material Identification

The following quantities outlined below, represent the materials scheduled for lead hazard abatement, removal, disposal and/or demolition.

Material	Description	Estimated Quantity
Windows ✓	White paint on wood window frames (int/ext)	81 @ 12 Ln Ft
Door frames ✓	White paint on wood door frame components (int/ext)	37 @ 16 Ln Ft
Railing ✓	Brown and tan paint on exterior metal railing components	260 Ln Ft
Grills ✓	Brown paint on exterior grills covering crawlspace openings	11 @ 6 Sq Ft
Ceramic tile ⚡	White-glazed ceramic wall tile (4"x4")	900 Sq Ft
Sink ⚡	White porcelain glazed slopp sink	1 @ 4 Sq Ft
Fire Hose Connections	Red paint one exterior fire hose connection	1 @ 4 Sq Ft

**Lead Abatement Plan**  
**Gulfport VA, Building 041 – TO No. 45**  
**Gulfport, MS**

2. Bulk Sampling Reports
3. Final Clearance Statement
4. Waste Disposal Documentation
5. Negative Pressure Enclosure Recordings

## 7.0 Lead Material Identification

The following quantities outlined below, represent the materials scheduled for lead hazard abatement, removal, disposal and/or demolition.

Material	Description	Estimated Quantity
Door/frame	Beige paint on attic door and frame components	4 @ 10 Ln Ft
Stairwell components	White, beige and green paint on stairwell components (risers, deck, handrail)	5 @ 700 Sq Ft
Railing	White paint on metal handrailing components	1,500 Ln Ft
Ceramic tile	White and orange glazed ceramic wall tile (1"x1")	1,200 Sq Ft
Sink	White porcelain glazed sinks	
Metal Cage	White paint on metal wall chase cage; beige paint on attic access cage	46 @ 4 Sq Ft 2 @ 960 Sq Ft
Water Valve	Red paint on exterior water valve	3 @ 4 Sq Ft
Electrical Conduit	Orange paint on electrical conduit	10 Ln Ft
Concrete floor	Red and tan paint on concrete penthouse floor	400 Sq Ft
Crown molding	White paint on interior crown molding	80 Ln Ft
Walls	Green paint on interior wall plaster	600 Sq Ft
Grills	Black painted crawlspace grills	27 @ 2 Sq Ft
I Beams	Orange I Beams in attic	2 @ 250 Ln Ft

**Lead Abatement Plan**  
**Gulfport VA, Building 057 - TO No. 45**  
Gulfport, MS

2. Bulk Sampling Reports
3. Final Clearance Statement
4. Waste Disposal Documentation
5. Negative Pressure Enclosure Recordings

## 7.0 Lead Material Identification

The following quantities outlined below, represent the materials scheduled for lead hazard abatement, removal, disposal and/or demolition.

Material	Description	Estimated Quantity
Exterior plaster walls	Beige paint on exterior wall components	63,000 Sq Ft
Windows	Gray paint on window frame components	208 @ 12 Ln Ft
Stair components	Gray and red paint on metal stair components	5 @ 700 Sq Ft
Grills	Brown paint on exterior grills covering crawlspace openings	10 @ 4 Sq Ft
Glazed block	Beige and green glazed wall blocks	3,400 Sq Ft
Fire Hydrants	Yellow paint on fire hydrants	1 @ 6 Sq Ft
Loading Dock components	Yellow paint on metal loading dock components	30 Ln Ft
Fire Hose Connection	Red paint at fire hose connection	3 @ 4 Sq Ft
Attic Stairwell	Black paint on attic stairwell components	90 Sq Ft

**Lead Abatement Plan**

Gulfport VA, Building 062 - TO No. 45  
*Gulfport, MS*

2. Bulk Sampling Reports
3. Final Clearance Statement
4. Waste Disposal Documentation
5. Negative Pressure Enclosure Recordings

## 7.0 Lead Material Identification

The following quantities outlined below, represent the materials scheduled for lead hazard abatement, removal, disposal and/or demolition.

Material	Description	Estimated Quantity
Exterior stucco and trim ✓	White/cream and beige paint on exterior stucco and trim components	40,000 Sq Ft
Exterior concrete ✓	White paint on exterior concrete foundation and decorative components; gray paint on concrete stair components	3,600 Sq Ft
Windows ✓	White/cream, blue, and beige paint on metal and wood window frames (int/ext)	197 @ 12 Ln Ft
Door trim ✓	White and blue paint on exterior wood door components	5 @ 16 Ln Ft
Stairwell components ✓	White, beige gray, blue, and green paint on metal stairwell and railing components	5 @ 700 Sq Ft
Grills ✓	Brown and black paint on exterior grills covering crawlspace openings	12 @ 4 Sq Ft
Walls	White paint on plaster stairwell walls; white on interior concrete walls; white on exterior mechanical room walls; white paint on plaster sunroom walls	7,000 Sq Ft
Ceramic tile ✓	glazed ceramic wall tile green tile (4"x4")	30 Sq Ft
Loading dock components ✓	Yellow paint on metal loading dock components	50 Ln Ft

**Lead Abatement Plan**Gulfport VA, Building 062 - TO No. 45  
Gulfport, MS

Water valve ✓	Red paint on metal water valve components, exterior	1 @ 4 Sq Ft
Penthouse components ✓	Gray paint on metal penthouse door, frame, and handrail components	150 Sq Ft door, 40 Ln Ft rail,
I Beam ✓	Gray	200 Sq Ft stair
Fire Hose Cabinet	Red paint on metal cabinet	100 Sq Ft 1 @ 8 Sq Ft

**Lead Abatement Plan**  
**Gulfport VA, Building 064 - TO No. 45**  
**Gulfport, MS**

2. Bulk Sampling Reports
3. Final Clearance Statement
4. Waste Disposal Documentation
5. Negative Pressure Enclosure Recordings

## 7.0 Lead Material Identification

The following quantities outlined below, represent the materials scheduled for lead hazard abatement, removal, disposal and/or demolition.

Material	Description	Estimated Quantity
Windows ✓	Beige and white paint on wood window components (int/ext)	43 @ 26 Ln Ft
Doors/Components ✓	Lt. Blue paint on metal door frame components	21 @ 30 Ln Ft
Door Frames ✓	White paint on wood exterior door frames	51 @ 30 Ln Ft
Porch components ✓	White paint on wood porch components	19,000 Sq Ft
Stairwell Railing ✓	Lt. Blue paint on metal stairwell railing	120 Ln Ft
Grills ✓	Beige paint on exterior grills covering crawlspace openings	14 @ 6 Sq Ft
Windows ✓	Blue paint on metal crawlspace window components	4 @ 2 Sq Ft
Fireplace ✓	White paint on wood fireplace components	50 Sq Ft



6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

#### ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
#1 Far NE Corner	0610202-01	Soil	10/13/06 09:00	10/17/06 16:25
#2 Mid East	0610202-02	Soil	10/13/06 09:00	10/17/06 16:25
#3 South East Around Pool Area	0610202-03	Soil	10/13/06 09:00	10/17/06 16:25
#4 South Between 63 & 64	0610202-04	Soil	10/13/06 09:00	10/17/06 16:25
#5 South Between 57 & 63	0610202-05	Soil	10/13/06 09:00	10/17/06 16:25
#6 Southwest Around 119 West of 57	0610202-06	Soil	10/13/06 09:00	10/17/06 16:25
#7 West Around 62 & 76 pool	0610202-07	Soil	10/13/06 09:00	10/17/06 16:25
#8 NW Corner Around 40, 6 Boiler, 61	0610202-08	Soil	10/13/06 09:00	10/17/06 16:25
#9 North Around 49, 60 West of 2	0610202-09	Soil	10/13/06 09:00	10/17/06 16:25
#10 North Around 2 & West of 117	0610202-10	Soil	10/13/06 09:00	10/17/06 16:25
#11 Mid Field Between 3 & 4	0610202-11	Soil	10/13/06 09:00	10/17/06 16:25
#12 Mid Around 5, 62, 3	0610202-12	Soil	10/13/06 09:00	10/17/06 16:25
#13 Mid Around 1 & North of 4	0610202-13	Soil	10/13/06 09:00	10/17/06 16:25
#14 Mid Around 4	0610202-14	Soil	10/13/06 09:00	10/17/06 16:25
#15 Mid North of 63 & South of 3	0610202-15	Soil	10/13/06 09:00	10/17/06 16:25
			10/13/06 09:00	10/17/06 16:25



6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

## Case Narrative

### METALS CASE NARRATIVE

#### Holding Times:

The sample(s) were analyzed within the required holding time. 6010B

#### Method Blanks:

Lab/Method Blanks were below the Reporting Limit. 6010B

#### Instrument Calibration:

The instrument(s) calibration met the acceptance criteria. 6010B

#### Lab Control(s):

Lab Control Sample(s) within acceptance criteria range. 6010B

#### Matrix Spike(s):

Matrix Spike Sample(s) within acceptance criteria range. 6010B

#### Qualifiers:

DW: See Notes and Definitions. 6010B

#### Analysis Comments:

Sample results/reporting limits calculated on Dry Weight Basis. 6010B



6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

#1 Far NE Corner  
0610202-01 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
<b>Micro-Methods Laboratory, Inc.</b>									
<u>Metals</u>									
Lead	547	2.49	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

## #2 Mid East

0610202-02 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
<b>Micro-Methods Laboratory, Inc.</b>									
Metals									
Lead	25.6	2.50	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



# MICRO-METHODS

LABORATORY, INC.

6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

#3 South East Around Pool Area  
0610202-03 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
<b>Micro-Methods Laboratory, Inc.</b>									
Metals									
Lead	41.8	2.48	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



6500 Sunplex Drive  
 Ocean Springs, MS 39564  
 228-875-6420 Phone  
 228-875-6423 Fax

AMI Environmental  
 8802 South 35th Street, Suite 100  
 Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
 Project Number: [none]  
 Project Manager: Jeff Mongar

Reported:  
 10/24/06 09:46

#4 South Between 63 & 64  
 0610202-04 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
<b>Micro-Methods Laboratory, Inc.</b>									
Metals									
Lead	141	2.48	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



# MICRO-METHODS

LABORATORY, INC.

6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

**#5 South Between 57 & 63**  
**0610202-05 (Soil)**

Analytic	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
<b>Micro-Methods Laboratory, Inc.</b>									
<b>Metals</b>									
<b>Lead</b>	260	2.48	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



# MICRO-METHODS

LABORATORY, INC.

6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

#6 Southwest Around 119 West of 57  
0610202-06 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Micro-Methods Laboratory, Inc.									
<b>Metals</b>									
Lead	85.0	2.49	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

#7 West Around 62 & 76 pool  
0610202-07 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
<b>Micro-Methods Laboratory, Inc.</b>									
<b>Metals</b>									
<b>Lead</b>	<b>57.6</b>	2.47	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



6500 Sunplex Drive  
 Ocean Springs, MS 39564  
 228-875-6420 Phone  
 228-875-6423 Fax

AMI Environmental  
 8802 South 35th Street, Suite 100  
 Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
 Project Number: [none]  
 Project Manager: Jeff Mongar

Reported:  
 10/24/06 09:46

#8 NW Corner Around 40, 6 Boiler, 61  
 0610202-08 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
<b>Micro-Methods Laboratory, Inc.</b>									
Metals									
Lead	163	2.49	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



# MICRO-METHODS

LABORATORY, INC.

6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

#9 North Around 49, 60 West of 2  
0610202-09 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Micro-Methods Laboratory, Inc.									
Metals									
Lead	276	2.49	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



# MICRO-METHODS

LABORATORY, INC.

6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

#10 North Around 2 & West of 117

0610202-10 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Micro-Methods Laboratory, Inc.									
Metals Lead	244	2.46	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

## #11 Mid Field Between 3 &amp; 4

0610202-11 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
<b>Micro-Methods Laboratory, Inc.</b>									
<b>Metals</b>									
Lead	55.0	2.50	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

#12 Mid Around 5, 62, 3  
0610202-12 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Micro-Methods Laboratory, Inc.									
Metals									
Lead	217	2.47	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

#13 Mid Around 1 & North of 4  
0610202-13 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Micro-Methods Laboratory, Inc.									
Metals									
Lead	41.6	2.48	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

## #14 Mid Around 4

0610202-14 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Micro-Methods Laboratory, Inc.									
Metals									
Lead	622	2.49	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

## #14 Mid Around 4

0610202-14 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Micro-Methods Laboratory, Inc.									
Metals Lead	622	2.49	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW



# MICRO-METHODS

LABORATORY, INC.

6500 Sunplex Drive  
Ocean Springs, MS 39564  
228-875-6420 Phone  
228-875-6423 Fax

AMI Environmental  
8802 South 35th Street, Suite 100  
Omaha NE, 68138

Project: Gulfport, VA Soil Samples  
Project Number: [none]  
Project Manager: Jeff Mongar

Reported:  
10/24/06 09:46

#15 Mid North of 63 & South of 3  
0610202-15 (Soil)

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
<b>Micro-Methods Laboratory, Inc.</b>									
Metals									
Lead	77.6	2.49	mg/kg	1	6J19008	10/19/06	10/20/06	SW 6010B	DW

ATTACHMENT 6



STATE OF MISSISSIPPI  
HALEY BARBOUR  
GOVERNOR  
MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY  
TRUDY D. FISHER, EXECUTIVE DIRECTOR

June 5, 2007

Brian Nunan  
AdvantaClean  
2953 Interstate Street  
Charlotte, North Carolina 28208-3607

Re: VA Medical Center  
Bldg. 61, 40, & 76  
200 Beach Boulevard  
Gulfport, MS 39507

Dear Mr. Nunan:


The Mississippi Department of Environmental Quality has received your notification for demolition activity involving the referenced property. As a result, it appears that regulation notification requirements have been satisfied for this project.

If you should have questions, or wish to discuss any requirements of the regulations, please let us know. You may contact us by calling (601) 961-5171.

Sincerely,

A handwritten signature in cursive script that reads "Carolyn Bergeron".

Carolyn Bergeron  
Asbestos Projects Section




OFFICE OF POLLUTION CONTROL

POST OFFICE BOX 10385 • JACKSON, MISSISSIPPI 39289-0385 • TEL: (601) 961-5171 • FAX: (601) 354-6612 • [www.deq.state.ms.us](http://www.deq.state.ms.us)  
AN EQUAL OPPORTUNITY EMPLOYER



STATE OF MISSISSIPPI  
**HALEY BARBOUR**  
 GOVERNOR  
 MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY  
 TRUDY D. FISHER, EXECUTIVE DIRECTOR



June 5, 2007

Brian Nunan  
 Advanta Clean  
 2953 Interstate Street  
 Charlotte, North Carolina 28208-3607

Re: VA Medical Center  
 Bldgs. 33, 60, 63, 117  
 200 Beach Boulevard  
 Gulfport, MS 39507

Dear Mr. Nunan:

The Mississippi Department of Environmental Quality has received your notification for demolition activity involving the referenced property. As a result, it appears that regulation notification requirements have been satisfied for this project.

If you should have questions, or wish to discuss any requirements of the regulations, please let us know. You may contact us by calling (601) 961-5171.

Sincerely,

*Carolyn Bergeron*

Carolyn Bergeron  
 Asbestos Projects Section

ATTACHMENT 7

STATE OF MISSISSIPPI  
HALF BARBOUR  
GOVERNOR  
MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY  
TRUDY D. FISHER, EXECUTIVE DIRECTOR

October 20, 2008

FILE COPY

Benjamin B. Coe  
Gulfport VA Medical Center  
400 Veterans Avenue  
Building 8  
Biloxi, MS 39531

**RE: UNDERGROUND STORAGE TANKS (USTs)**  
Gulfport VA Medical Center  
200 East Beach Blvd  
Gulfport, Mississippi  
Facility I.D. # 1808

Dear Mr. Coe:

The Office of Pollution Control (OPC) has reviewed the analytical results of the soil/ water samples taken during the closure activity at the referenced location. According to the results, the Polynuclear Aromatic Hydrocarbons (PAH) concentrations pose no current or potential threat to human health and environment and are below the maximum allowable action levels. Therefore, the closure activity requires no further action at this time.

We appreciate your cooperation in this matter. If you should have questions and/or comments, please contact me at (601) 961-5575.

Sincerely,

*Sandra Dowty*  
Sandra Dowty  
UST BRANCH

CC: Mitigation Services, Inc.

## APPENDIX D

**UNDERGROUND STORAGE TANK SYSTEM CLOSURE REPORT**

Referee: Department of Environmental Quality  
 Sub-Referee: Office of Pollution Control  
 File No.: M1-PAK-2681  
 Date: October 20, 1998  
 Location: Jackson MS 39225-2261

Facility ID No.:  
 Date Prepared by: MDEQ

**Location of Tank System**

Name: V.A.  
 Address: 201 1/2 85th Street Blvd.  
 City: Gulfport County: Harrison

**Ownership of Tank System**

Name: V.A.  
 Address: 400 1/2 Taylor Blvd. MS 39531  
 City: Biloxi State: MS Zip: 39531

**TYPE OF UNDERGROUND STORAGE TANK SYSTEM CLOSURE**

Tank or piping removed  Tank and piping in place  
 Tank replaced  Tank closure in place only  
 Piping replaced only  piping closure in place only

New tank(s) installed  Yes any new piping installed   
 Number of active tanks remaining: 3

**Description of Underground Storage Tanks (Complete for each closed tank at this location.)****I. Tank Information**

| Tank No. |
|----------|----------|----------|----------|----------|----------|
| 1        | 2        | 3        | 4        | 5        |          |
| 33       | 33       | 33       | 33       | 33       |          |
| 50%      | 40%      | 60%      | 60%      | 60%      |          |

Estimated age of tank in years:

Estimated tank capacity in gallons:

Estimated volume in tank:

**II. Tank Closure Information**

The tank was removed from underground completely.  
 The tank was removed by excavator only.  
 It is not in place at the same location used during  
 removal due to slope and earth movement.

Off-site off-site off-site off-site

**Disposition of excavated backfill material**

Note: All backfill materials must  
 be handled in accordance with  
 the Mississippi Department of  
 Environmental Quality's (MDEQ)  
 Guidelines for the Permanent  
 Closure of UST Systems

Disposed of in landfill  
 Returned to excavation   
 Stockpiled on site  
 Hauled off site  
 Hauled off site

**Submit the following supporting documentation with this Closure Report:**

1. Lab analytical results of samples
2. Sampler's name and activity
3. Site Drawing
4. Average dimensions of tank(s) based on backfill materials used for closure

**III. Site Assessment Information**

Site is considered to be free of contamination:  No   
 Any known oil or UST-related debris?  No   
 Any potential hazards present?  No

**To be completed by the tank owner: (Please print or type all but signature)**

Oath: I certify that the information concerning closure is true to the best of my belief and knowledge  
 Owner's Name:

*Patricia B. Lee*

Owner's Signature:

Date: *10/08/98*

**To be completed by person certified by MDEQ to Permanently Close:**

Name of person certified by MDEQ to close system:

*Cathy R. Lee*

MDEQ Certified Contractor's Company:

*Patricia Lee & Son Inc.*

Date: *10/08/98*

MDEQ Certified Contractor's Signature:

*Cathy R. Lee*

MDEQ Certification No.:

*CAB 1331*

Produced by the Mississippi Department of Environmental Quality, Office of Pollution Control, UST Branch  
 P.O. Box 2381 Jackson, MS 39225-2381 (601) 961-8171 Fax (601) 961-6083 [www.doe.state.ms.us](http://www.doe.state.ms.us)

Printed after signing: *Patricia B. Lee*

Date: *10/08/98*



ENVIRONMENTAL  
SCIENCE CORP.

1000B Lakewood Rd.  
Mt. Juliet, TN 37120  
(615) 781-3433  
(615) 781-3439  
Fax: (615) 781-3439  
Fax U.S.: 800-423-1423  
Tel: 1-800

Mr. Koen Hassim  
Engineering Group  
3850 N. Causeway Blvd., Suite 1800  
Bethesda, MD 20802

Report Summary

Thursday August 07, 2008

Report Number: L358097

Samples Received: 08/05/08

Client Project: 10060

Description: Sampling for UST Removal

The analytical results in this report are based upon information supplied by you, the client, and are for your exclusive use. If you have any questions regarding this data package, please do not hesitate to call.

Entire Report Reviewed By:

Laboratory Certification Numbers

T. Alan Harrell, ESL Representative

AZLA - 1461-01, ATHA - 02221, AL - 40660, CA - 1-2327, CT - PR-0197, FL - 827487  
GA - 923, IN - C-TG-01, HI - 90010, ETOST - 0016, NC - ENV375, DW21704, ND - R-140  
NJ - 76002, SC - 84004, TN - 2066, VA - 00109, WI - 233  
AZ - 7612, MN - 047-999-598, NY - L1742, WI - 998093910

This report may not be reproduced, except in full, without written approval from Environmental Science Corp.  
5 samples reported: CH/UT/BB 11/08 Printed: 08/07/08 11:11  
Page 1 of 3

**ENVIRONMENTAL  
SCIENCE CORP.**

42055 LeBaron Rd.  
St. Julian, CA 91312  
602-738-8844  
1-800-767-8852  
Fax (619) 738-8852

Tax I.D. #2-014289

FAX: 1970

Mr. Fred Hassan  
Bioengineering Group  
3630 N. Ciceroay Blvd., Suite 1600  
Metairie, LA 70001

REPORT OF ANALYSIS

August 07, 2008

Date Received : August 06, 2008  
 Prescription : Sampling for ODF Removal  
 Sample ID : 9811-2 ZONE  
 Collected By : Fred Hassan  
 Collection Date : 08/07/08 11:00

ESQ Sample #: L328097-02  
 Site ID : ER 1  
 Project #: 10068

22,000 Bldg #1

Parameter	Result	Det. Limit	Units	Method	Date	DL
<b>Polyaromatic Hydrocarbons</b>						
Anthracene	5.6	1.6	ug/kg	8270C-SIM	08/06/08	300
Acenaphthene	4.9	1.6	ug/kg	8270C-SIM	08/06/08	300
Acenaphthylene						
Fluorene (1,2,3)	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Benzo(a)anthracene	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Benzo(a)pyrene	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Benzo(b,f)fluoranthene	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Benzo(g,h,i)perylene	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Benzo(k)fluoranthene	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Chrysene	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Dibenz(a,h)anthracene	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Fluoranthene	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Fluorene	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Indeno(1,2,3)perylene	1.0	1.6	ug/kg	8270C-SIM	08/06/08	300
Septahexene	BDL	1.6	ug/kg	8270C-SIM	08/06/08	300
Phenanthrene	3.6	1.6	ug/kg	8270C-SIM	08/06/08	300
Pyrene	2.1	1.6	ug/kg	8270C-SIM	08/06/08	300
$\beta$ -Methylnaphthalene	2.6	1.6	ug/kg	8270C-SIM	08/06/08	300
$\delta$ -Methylnaphthalene	1.5	1.6	ug/kg	8270C-SIM	08/06/08	300
2-Chloronaphthalene	1.80	1.6	ug/kg	8270C-SIM	08/06/08	300
Surrogate Recovery	BDL	0.5	ug/kg	8270C-SIM	08/06/08	300
Nitrobenzene-d5						
$\alpha$ -Ziclorodiphenyl	112.		% Rec.	8270C-SIM	08/06/08	300
$\gamma$ -Terphenyl-d14	105.		% Rec.	8270C-SIM	08/06/08	300
	126		% Rec.	8270C-SIM	08/06/08	300

BDL = Below Detection Limit

Det. Limit = Practical Quantitation Limit (ug/kg)

Note:

The reported analytical results relate only to the sample submitted.

This report shall not be reproduced, except in full, without the written approval from ESC.

Reproduced: 08/07/08 11:39 Printed: 08/07/08 11:49



ENVIRONMENTAL  
SCIENCE CORP.

12001 Devonian Dr.  
Mt. Juliet, TN 37122  
(615) 755-5858  
(800) 761-5858  
Fax: (615) 755-5859

Tax I.D. #1-0616388  
EIN: 1772

Mr. Komi Hassan  
Bisengiwereng Corp.  
3840 N. Causeway Blvd., Suite 1600  
Metairie, LA 70002

REPORT OF ANALYSIS

August 07, 2008

Date Received : August 03, 2008  
 Description : Sampling for CRT Removal  
 Sample ID : WZXL 4-XCE  
 Collected By : Komi Hassan  
 Collection Date : 08/02/08 11:45

ESQ Sample #: 5336027-04  
 Site ID : QR 1  
 Project #: 10060

4,080  
BEN  
241

Parameter	Result	Detect. Limit	Units	Method	Date	DL
<b>Polyaromatic Aromatic Hydrocarbons</b>						
Anthracene	200	30	ug/kg	82700-SIM	08/06/08	15000
Acenaphthene	150	90	ug/kg	82700-SIM	08/06/08	15000
Acenaphthriene	200	90	ug/kg	82700-SIM	08/06/08	15000
Benz(a)anthracene	200	90	ug/kg	82700-SIM	08/06/08	15000
Benz(a)pyrene	200	90	ug/kg	82700-SIM	08/06/08	15000
Benz(b)fluoranthene	200	90	ug/kg	82700-SIM	08/06/08	15000
Benz(c,h,i)perylene	200	90	ug/kg	82700-SIM	08/06/08	15000
Benz(k)fluoranthene	200	90	ug/kg	82700-SIM	08/06/08	15000
Chrysene	200	90	ug/kg	82700-SIM	08/06/08	15000
Dibenz(a,h)anthracene	200	90	ug/kg	82700-SIM	08/06/08	15000
Dibenzanthene	200	90	ug/kg	82700-SIM	08/06/08	15000
Fluorene	200	90	ug/kg	82700-SIM	08/06/08	15000
Indeno[1,2,1-od]pyrene	500	90	ug/kg	82700-SIM	08/06/08	15000
Phenanthrene	200	90	ug/kg	82700-SIM	08/06/08	15000
Phenanthrylene	1000	90	ug/kg	82700-SIM	08/06/08	15000
Pyrene	970	90	ug/kg	82700-SIM	08/06/08	15000
1-Methylimaphthalic acid	130	90	ug/kg	82700-SIM	08/06/08	15000
1-Methylimaphthalane	2300	90	ug/kg	82700-SIM	08/06/08	15000
2-Chloronaphthalene	6900	90	ug/kg	82700-SIM	08/06/08	15000
Surrogate Recovery	200	500	ug/kg	82700-SIM	08/06/08	15000
Nitrobenzene-d3						
D-fluorobiphenyl	0.00		% Recd.	82700-SIM	08/06/08	15000
P-Terphenyl-d4	0.00		% Recd.	82700-SIM	08/06/08	15000
	0.00		% Recd.	82700-SIM	08/06/08	15000

BGL = Below Detection Limit

Detect. limit = Practical Quantitation Limit (PQL)

Note:

The reported analytical results relate only to the sample submitted.

This report shall not be reproduced, except in full, without the written approval from ESQ.

Reported: 08/07/08 11:59 Printed: 08/07/08 11:57



ENVIRONMENTAL  
SCIENCE CORP.

22960 Lawson Rd.  
Mt. Juliet, TN 37130  
1-815-715-8888  
1-800-747-8888  
800-1811-715-8888  
Fax: 1-800-747-8888  
E-mail: 1870

Mr. Koen Haesem  
Bicengineering Group  
3850 N. Causeway Blvd., Suite 1600  
Metairie, LA 70002

REPORT OF ANALYSIS

August 07, 2008

Date Received : August 05, 2008  
 Description : Sampling for GST Removal  
 Sample ID : WHEL 3 GKS  
 Collected By : Koen Haesem  
 Collection Date : 08/02/08 14:50

ESQ Sample #: L358037-05  
 Site ID : GA 1  
 Project #: 10000

Parameter	Result	Det. Limit	Units	Method	Date	DL
<b>Polyaromatic Hydrocarbons</b>						
anthracene	120	90.	ug/kg	8270C-SIM	08/06/08	15000
Acenaphthene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Acenaphthylene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Benz(a)anthracene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Benzo(a)pyrene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Benzo(b)fluoranthene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Benzo(k)fluoranthene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Benzo(1,4,5-h,j)perylene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Benzo(1,2,4,5-h,i)fluoranthene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Chrysene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Dibenz(A,b)anthracene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Fluoranthene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Fluorene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Indeno(1,2,3-ij)perylene	270	90.	ug/kg	8270C-SIM	08/06/08	15000
Kaphthlene	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
Phenanthrene	660	90.	ug/kg	8270C-SIM	08/06/08	15000
Pyrene	480	90.	ug/kg	8270C-SIM	08/06/08	15000
1-Naphthylmethane	BDL	90.	ug/kg	8270C-SIM	08/06/08	15000
2-Naphthylmethane	1500	90.	ug/kg	8270C-SIM	08/06/08	15000
2-Chloronaphthalene	2900	90.	ug/kg	8270C-SIM	08/06/08	15000
Surrogate Recovery	BDL	900	ug/kg	8270C-SIM	08/06/08	15000
Nitrobenzene-DB	0.00		% Rec.	8270C-SIM	08/06/08	15000
2-Fluorobiphenyl	0.00		% Rec.	8270C-SIM	08/06/08	15000
p-Terphenyl-oil	0.00		% Rec.	8270C-SIM	08/06/08	15000

BDL = Below Detection Limit

Det. Limit = Practical Quantitation Limit (PQL)

Note:

The reported analytical results relate only to the sample submitted.

This report shall not be reproduced, except in full, without the written approval from ESC.

Reported: 08/07/08 11:39 Printed: 08/07/08 11:42

Attachment A  
List of Analytes with GC Qualifiers

Sample #	Analyte	Qualifier
L358097-01	Mix: benzene-d6	37
	2-Fluorobiphenyl	37
	p-Terphenyl-d14	37
L358097-03	Mix:benzene-d6	37
	2-Fluorobiphenyl	37
	p-Terphenyl-d14	37
L358097-04	Mix:benzene-d6	37
	2-Fluorobiphenyl	37
	p-Terphenyl-d14	37
L358097-05	Mix:benzene-d6	37
	2-Fluorobiphenyl	37
	p-Terphenyl-d14	37
L358097-06	Mix:benzene-d6	37
	2-Fluorobiphenyl	37
	p-Terphenyl-d14	37

**Attachment H**  
**Explanation of QC Qualifier Codes**

Qualifier	Meaning
4?	Surrogate recovery limits cannot be evaluated; surrogates were diluted out

**Qualifier Report Information**

EBC utilizes sample and result qualifiers as set forth by the EPA Contract Laboratory Program and as required by most certifying bodies including NELAC. In addition to the EPA qualifiers adopted by EBC, we have implemented EBC qualifiers to provide more information pertaining to our analytical results. Each qualifier is designated in the qualifier explanation as either EPA or EBC. Data qualifiers are intended to provide the EBC client with more detailed information concerning the potential bias of reported data. Because of the wide range of constituents and variety of matrices incorporated by most EPA methods, it is common for some compounds to fall outside of established ranges. These exceptions are evaluated and all reported data is valid and useable unless qualified as 'X' (Rejected).

**Definitions**

**Accuracy** - The relationship of the observed value of a known sample to the true value of a known sample. Represented by percent recovery and relevant to samples such as: control samples, matrix spike recoveries, surrogate recoveries, etc.

**Precision** - The agreement between a set of samples or between duplicate samples. Refers to how close together the results are and is represented by Relative Percent Difference.

**Surrogate** - Organic compounds that are similar in chemical composition, extraction, and chromatography to analytes of interest. The surrogates are used to determine the probable response of the group of analytes that are chemically related to the surrogate compound. Surrogates are added to the sample and carried through all stages of preparation and analysis.

**TC** - Tentatively Identified Compound: Compounds detected in samples that are not target compounds, internal standards, system monitoring compounds, or surrogates.

Summary of Remarks for Samples Printed  
08/07/08 at 11:38

TSR Signatory Report: 030  
H2 - Bush Two Day

Sample: L358091-01 Account: 820CHMLA Received: 08/05/08 09:00 Due Date: 08/07/08 00:00 RPT Date: 08/07/08 10:39  
Diesel product.  
Sample: L358091-02 Ac. 820CHMLA Received: 08/05/08 09:00 Due Date: 08/07/08 00:00 RPT Date: 08/07/08 10:39  
Diesel product.  
Sample: L358091-03 Account: 820CHMLA Received: 08/05/08 09:00 Due Date: 08/07/08 00:00 RPT Date: 08/07/08 11:39  
Diesel product.  
Sample: L358091-04 Account: 820CHMLA Received: 08/05/08 09:00 Due Date: 08/07/08 00:00 RPT Date: 08/07/08 11:39  
Diesel product.  
Sample: L358091-05 Account: 820CHMLA Received: 08/05/08 09:00 Due Date: 08/07/08 00:00 RPT Date: 08/07/08 11:39  
Diesel product.

ATTACHMENT 8

Table 1. Sample Locations

Sample Number	Location	Rationale for Sample
MW-1	Former B-76	Establish baseline concentration of Bis (2-ethylhexyl phthalate)
MW-2	West of B-62	Establish baseline concentration of Bis (2-ethylhexyl phthalate)
DP-67	B-45/B-117	Delineate the lateral extent of Benzo (a) pyrene in the soil.
DP-68	B-45/B-117	Delineate the lateral extent of Benzo (a) pyrene in the soil and groundwater.
DP-69	B-45/B-117	Delineate the lateral extent of Benzo (a) pyrene in the soil.
DP-70	B-45/B-117	Delineate the lateral extent of Benzo (a) pyrene in the groundwater
DP-71	B-45/B-117	Delineate the lateral extent of Benzo (a) pyrene in the groundwater
DP-72	Not Collected	Sample deemed unnecessary.
DP-73	B-45/B-117	Delineate the lateral extent of Benzo (a) pyrene in the groundwater
DP-74	B-45/B-117	Delineate the lateral extent of Benzo (a) pyrene in the groundwater
DP-75	B-45/B-117	Delineate the lateral extent of Benzo (a) pyrene in the groundwater
DP-76	B-45/B-117	Delineate the lateral extent of Benzo (a) pyrene in the groundwater
DP-77	Former B-32	Delineate lateral extent of Chrysene and Benzo (a) pyrene in the soil.
DP-78	Former B-32	Delineate lateral extent of Chrysene and Benzo (a) pyrene in the soil.
DP-79	Former B-32	Delineate lateral extent of Chrysene and Benzo (a) pyrene in the soil.
DP80	Former B-32	Delineate lateral extent of Chrysene and Benzo (a) pyrene in the soil.
DP-81	SE corner	Determine background concentrations of Arsenic in the soil.
DP-82	65 ft west of south gate	Determine background concentrations of Arsenic in the soil.
DP-83	217 ft east of B-4	Determine background concentrations of Arsenic in the soil.
DP-84	NW corner	Determine background concentrations of Arsenic in the soil.
DP-85	Former B-6	Delineate lateral extent of Arsenic in the soil.
DP-86	Former B-6	Delineate lateral extent of Arsenic in the soil.

Sample Number	Location	Rationale for Sample
DP-87	Former B-6	Delineate lateral extent of Arsenic in the soil.
DP-88	Former B-32	Delineate lateral extent of Arsenic in the soil.
DP-89	Former B-32	Delineate lateral extent of Arsenic in the soil.
DP-90	Former B-32	Delineate lateral extent of Arsenic in the soil.
DP-91	Former B-76	Delineate lateral extent of Arsenic in the soil.
DP-92	Former B-76	Delineate lateral extent of Arsenic in the soil.
DP-93	Former B-76	Delineate lateral extent of Arsenic in the soil.
DP-94	Former B-6	Delineate lateral extent of Benzo (b) flouranthene in the soil.
DP-95	Former B-6	Delineate lateral extent of Benzo (b) flouranthene in the soil.
DP-96	Former B-6	Delineate lateral extent of Benzo (b) flouranthene in the soil.
DP-97	Former DP-25	Determine filtered Lead concentration.
DP-98	Electrical vault	Determine concentrations of BTEX, PAHs and PCBs in the soil and groundwater at former location of in-ground electrical vault.
DP-99	Former B-61	Delineate lateral extent of Benzo (b) flouranthene in the soil.
DP-100	Former B-61	Delineate lateral extent of Benzo (b) flouranthene in the soil.
DP-101	Former B-61	Delineate lateral extent of Benzo (b) flouranthene in the soil.
DP-102	Former B-61	Delineate lateral extent of Benzo (b) flouranthene in the soil.
DP-103	Former B-61	Delineate lateral extent of Benzo (b) flouranthene in the soil.
DP-104	B-45/B-117	Delineate the lateral extent of Benzo (a) pyrene in the soil.

TABLE 1A  
SURFACE WATER AND GROUNDWATER ANALYTICAL RESULTS  
(Organochlorine Pesticides, Volatile Organic Compounds, Diesel Range Organics and Eight RCRA Metals)

Facility Name: VA Gulfcoast Veterans Health Care System	Sample #	Sample Location	Date Collected	EPA Method 808/1A	Benzene	Toluene	Ethylbenzene	Total Xylenes	Total BTEX	DRO	Total As Ba	Total Cd	Dissolved Cr	Total Pb	Dissolved Pb	Total Hg	Dissolved Hg	Total Se	Total Ag	
DPW-1	Pit #1	2/28/2007	NA	NA	NA	NA	NA	NA	NA	119	NA	NA	NA	NA	NA	NA	NA	NA		
DPW-2	Pit #2	2/28/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
DPW-4	Pond #1	2/28/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
DPW-5	Pond #2	3/1/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
DPW-7	Tank Pit #1	2/28/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
DPW-8	Tank Pit #2	2/28/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
DPW-9	Tank Pit #2	2/28/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
MMB-1	Tank Pit #2	2/28/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
DPW-11	Tank Pit #3	3/1/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
DPW-12	Tank Pit #3	3/1/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
DPW-13	Tank Pit #4	3/1/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
DPW-14	Tank Pit #4	3/1/2007	NA	NA	<5	<5	<5	<10	<25	NA	<100	NA	NA	NA	NA	NA	NA	NA		
DPW-15	Pond #3	3/1/2007	NA	NA	NA	NA	NA	NA	NA	147	NA	NA	NA	NA	NA	NA	NA	NA		
DPW-16	B-33	10/10/2007	BDL*	NA	NA	NA	NA	NA	NA	<100	<50	134	<5	61	NA	<50	NA	<50		
DPW-17	B-50	10/10/2007	BDL*	NA	NA	NA	NA	NA	NA	<25	<100	<50	63	<5	35	NA	<2	NA	<50	
DPW-18	PIL	10/10/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	94	<5	44	NA	<2	NA	<50
DPW-19	B-32	10/11/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	63	<5	10	NA	<2	NA	<50
DPW-20	B-59	10/12/2007	BDL*	NA	NA	NA	NA	NA	NA	<25	<100	<50	126	<5	55	NA	6	NA	<50	
DPW-21	B-117	10/11/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	148	<5	31	NA	8	NA	<50
DPW-22	B-60	10/11/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	48	<5	14	NA	4	NA	<50
DPW-23	E-602	10/11/2007	BDL*	NA	NA	NA	NA	NA	NA	<25	<100	<50	470	<5	79	NA	26	NA	<50	
DPW-24	B-6	10/11/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	95	<5	44	NA	<1	NA	<50
DPW-25	B-6	10/12/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	149	<5	11	NA	<2	NA	<50
DPW-26	B-61	10/11/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	175	<5	54	NA	2	NA	<50
DPW-27	B-76	10/11/2007	BDL*	NA	NA	NA	NA	NA	NA	<25	<100	<50	146	<5	24	NA	6	NA	<50	
DPW-28	E-119	10/11/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	64	<5	45	NA	2	NA	<50
DPW-29	E-245	10/12/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	60	<5	50	NA	12	NA	<50
DPW-30	Water of B-62	10/11/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	111	<5	11	NA	<1	NA	<50
DPW-31	Water of B-62	12/5/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	192	<5	66	NA	40	NA	<50
DPW-32	B-1/B-5	10/10/2007	BDL*	NA	NA	NA	NA	NA	NA	<25	<100	<50	175	<5	54	NA	6	NA	<50	
DPW-33	B-1/B-5	12/5/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	62	<5	24	NA	156	NA	<50
DPW-34	B-45	10/10/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	60	<5	45	NA	2	NA	<50
DPW-35	B-45	10/11/2007	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	150	<5	50	NA	111	NA	<50
DPW-36	Pond #3	4/21/2008	BDL*	NA	NA	NA	NA	NA	NA	<10	<25	<100	<50	71	<5	16	NA	8	NA	<50
DPW-37	Electrical Vault	4/24/2008	NA	<0.19	<0.28	<0.29	<0.28	<0.74	<1.5	NA	NA	NA	NA	153	<5	<10	NA	2	NA	<50
MDEQ UST Typical Cleanup Levels	NE	NE	NE	NE	NE	NE	NE	NE	NE	18,000	NE	NE	NE	NE	NE	NE	NE	NE	NE	
MDEQ Brownfields Tier 1 TRGs	NE	5	1,000	700	10,000	NE	NE	NE	NE	10	2,000	5	100	100	15	15	2	2	2	
All results in µg/l, except DRO which is expressed in mg/l.																				
Bolted results equal or exceed applicable cleanup goal.																				
MTBE	-																			
Total Xylenes	-																			
BTEX	-																			
DRO	-																			
NA	-																			
TRG	<																			

All results in µg/l, except DRO which is expressed in mg/l.  
 Bolted results equal or exceed applicable cleanup goal.  
 MTBE - Methyl Ter-Butyl Ether  
 Total Xylenes - Sum of ortho-, para-, and meta-xylene  
 BTEX - Benzene, Toluene, Ethylbenzene, Total Xylenes  
 DRO - Not tested for this Analyte  
 NA - Not tested for this Analyte  
 TRG - Target Remediation Goal  
 Less than

BOL\*

DW

NE

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

No analysis in the indicated method group were detected.

-Drinking Water

-Not Established

-Secondary DW Standard

-Primary

-Result is given for Total Chromium; a sum of trivalent and hexavalent

Chromium. TRG is given for lower of trivalent and hexavalent values

-Underground Storage Tank

#

UST

TABLE 1B  
GROUNDWATER ANALYTICAL RESULTS  
(Semivolatile Organic Compounds)

Facility Name: VA Gulfcoast Veterans Health Care System

Sample #	Sample Location	Date Collected	SEMI-VOLATILE AROMATIC COMPOUNDS											
			POLYNUCLEAR AROMATIC HYDROCARBONS			BENZO(a,anthracene)			BENZO(k)FLUORANTHENE			BENZO(a)PYRENE		
Phthalates	Bis(2-ethylhexyl)phthalate	Naphthalene	2-Methyl naphthalene	Acenaphthyrene	Fluorene	Phenanthrene	Anthracene	Fluoranthene	Pyrene	Chrysene	Dibenz(a,h)anthracene	Benzo(g,h,i)perylene	Indeno(1,2,3-cd)pyrene	
GPW-1	P/L #1	2/28/2007	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
GPW-2	P/L #2	2/28/2007	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-4	Pond #1	2/28/2007	< 10.1	< 10.1	< 10.1	< 10.1	< 10.1	< 10.1	< 10.1	< 10.1	< 10.1	< 10.1	< 10.1	NA
DPW-5	Pond #2	3/1/2007	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.1
DPW-7	Tank Pit #1	2/28/2007	NA	< 10.7	< 10.7	< 10.7	< 10.7	< 10.7	< 10.7	< 10.7	< 10.7	< 10.7	< 10.7	< 10.1
DPW-8	Tank Pit #1	2/28/2007	NA	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.9
DPW-9	Tank Pit #2	2/28/2007	NA	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.9
MVW-B41	Tank Pit #2	2/28/2007	NA	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.7
DPW-11	Tank Pit #3	3/1/2007	NA	< 11	< 11	< 11	< 11	< 11	< 11	< 11	< 11	< 11	< 11	< 10.7
DPW-12	Tank Pit #3	3/1/2007	NA	< 10.6	< 10.5	< 10.5	< 10.5	< 10.5	< 10.5	< 10.5	< 10.5	< 10.5	< 10.5	< 10.7
DPW-13	Tank Pit #4	3/1/2007	NA	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3	< 10.3
DPW-14	Tank Pit #4	3/1/2007	NA	< 10.2	< 10.2	< 10.2	< 10.2	< 10.2	< 10.2	< 10.2	< 10.2	< 10.2	< 10.2	< 10.3
DPW-15	Pond #3	3/1/2007	NA	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.9	< 10.3
DPW-16	B-33	10/10/2007	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12
DPW-17	B-50	10/10/2007	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12
DPW-18	P/L	10/10/2007	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12
DPW-19	B-32	10/11/2007	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15
DPW-20	B-59	10/12/2007	< 6.25	< 6.25	< 6.25	< 6.25	< 6.25	< 6.25	< 6.25	< 6.25	< 6.25	< 6.25	< 6.25	< 6.25
DPW-21	B-117	10/11/2007	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15
DPW-22	B-60	10/11/2007	< 6.19	< 6.19	< 6.19	< 6.19	< 6.19	< 6.19	< 6.19	< 6.19	< 6.19	< 6.19	< 6.19	< 6.19
DPW-23	B-602	10/11/2007	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12	< 6.12
DPW-24	B-6	10/11/2007	< 6.09	< 6.09	< 6.09	< 6.09	< 6.09	< 6.09	< 6.09	< 6.09	< 6.09	< 6.09	< 6.09	< 6.09
DPW-25	B-6	12/5/2007	< 6.03	< 6.03	< 6.03	< 6.03	< 6.03	< 6.03	< 6.03	< 6.03	< 6.03	< 6.03	< 6.03	< 6.03
DPW-26	B-61	10/11/2007	< 6.52	< 6.52	< 6.52	< 6.52	< 6.52	< 6.52	< 6.52	< 6.52	< 6.52	< 6.52	< 6.52	< 6.52
DPW-27	B-76	10/11/2007	18.7	< 6.22	< 6.22	< 6.22	< 6.22	< 6.22	< 6.22	< 6.22	< 6.22	< 6.22	< 6.22	< 6.22
DPW-28	B-219	10/11/2007	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15	< 6.15
DPW-29	B-245	10/12/2007	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59
DPW-30	West of B-62	10/11/2007	< 6.53	< 6.53	< 6.53	< 6.53	< 6.53	< 6.53	< 6.53	< 6.53	< 6.53	< 6.53	< 6.53	< 6.53
DPW-31	Burn Pit	10/10/2007	< 6.06	< 6.06	< 6.06	< 6.06	< 6.06	< 6.06	< 6.06	< 6.06	< 6.06	< 6.06	< 6.06	< 6.06
DPW-32	B-1(B-5)	10/10/2007	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59	< 6.59
DPW-33	B-45	10/10/2007	< 6.42	< 6.42	< 6.42	< 6.42	< 6.42	< 6.42	< 6.42	< 6.42	< 6.42	< 6.42	< 6.42	< 6.42
DPW-34	Pond #3	10/12/2007	< 6.35	< 6.35	< 6.35	< 6.35	< 6.35	< 6.35	< 6.35	< 6.35	< 6.35	< 6.35	< 6.35	< 6.35
MDEQ UST Typical Cleanup Levels*	NE	730	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE
EPA National Primary DW Stds.	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE
MDEQ BROWNFIELDS TIER 1 TRGs	6.00	< 6.2	122	2,190	365	243	43	1,460	183	0.0917	9.17	< 0.0917	0.2	0.0917

Bolded results exceed applicable cleanup goal  
- Diesel sites  
< - Less Than

NA - Not tested for this analyte  
NE - Diesel sites  
UST - Underground Storage Tank  
TRG - Target Remediation Goal

**TABLE 1B**  
**GROUNDWATER ANALYTICAL RESULTS**  
**(Semivolatile Organic Compounds)**

Facility Name: VA Gulfcoast Veterans Health Care System

Sample #	Sample Location	Date Collected	SEMI-VOLATILE ORGANIC COMPOUNDS												PAHs						
			POLYNUCLEAR AROMATIC HYDROCARBONS						PAHs												
			Phthalates	Bis(2-ethylhexyl phthalate)	Naphthalene	2-Methyl naphthalene	Acenaphthylene	Acenaphthene	Fluorene	Phenanthrene	Anthracene	Flouranthene	Pyrene	Chrysene	Benzo(a)anthracene	Benzo(b)fluoranthene	Benzo(a)pyrene	Dibenzo(a,h)anthracene	Benzo(a)perylene	Benzo(g,h,i)perylene	Indeno[1,2,3-cd]pyrene
DPW-35	West of B-62	12/4/2007	< 6.19	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-36	West of B-62	12/4/2007	< 6.45	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-37	North of B-76	12/4/2007	< 6.12	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-38	West of B-62	12/4/2007	< 6.32	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-39	B-76	12/4/2007	< 6.09	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-40	B-76	12/4/2007	< 6.38	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-41	B-76	12/4/2007	< 6.25	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-52	B-117	12/5/2007	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-53	B-117	12/5/2007	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-54	B-117	12/5/2007	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-55	B-117	12/5/2007	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
MV-1	B-76	4/25/2008	< 4.2	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
MV-2	West of B-62	4/25/2008	< 4.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-68	B-45/B-117	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB
DPW-70	B-45/B-117	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB
DPW-71	B-45/B-117	4/21/2008	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-72	-	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC
DPW-73	B-45/B-117	4/21/2008	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-74	B-45/B-117	4/21/2008	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-75	B-45/B-117	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB	RB
DPW-76	B-45/B-117	4/21/2008	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPW-98	Electrical Vault	4/24/2008	NA	< 0.0029	< 0.0031	< 0.0029	< 0.0029	< 0.003	< 0.0029	< 0.0029	< 0.0029	< 0.0029	< 0.0029	< 0.0029	< 0.0029	< 0.0029	< 0.0029	< 0.0029	< 0.0029	< 0.0029	< 0.0029
MDEQ UST Typical Cleanup Levels*																					
EPA National Primary DW Stns.																					
MDEQ BROWNFIELD TIER 1 TRGs																					
All results in ug/L		6.00	< 6.2	122	2,190	365	243	243	43	1,460	183	0.0917	9.17	< 0.0917	< 0.917	0.2	0.00917	1,100	0.0917	< 0.0027	< 0.0027
Bolded results exceed applicable cleanup goal																					
< - Diesel sites																					
< - Less Than																					
NA - Not tested for this analyte																					
RB - Received broken																					
NC - Not collected																					

MDEQ UST typical cleanup levels\*  
 EPA National Primary DW Stns.  
 MDEQ BROWNFIELD TIER 1 TRGs  
 All results in ug/L  
 Bolded results exceed applicable cleanup goal  
 < - Diesel sites  
 - Less Than  
 NA - Not tested for this analyte  
 RB - Received broken  
 NC - Not collected

UST - Underground Storage Tank  
 TRG - Target Remediation Goal

Location: Gulfport, MS  
 EPA National Primary DW Stns.  
 MDEQ BROWNFIELD TIER 1 TRGs  
 All results in ug/L  
 Bolded results exceed applicable cleanup goal  
 < - Diesel sites  
 - Less Than  
 NA - Not tested for this analyte  
 RB - Received broken  
 NC - Not collected

**TABLE 2A**  
**SOIL ANALYTICAL RESULTS**  
**(Volatile Organic Compounds, Diesel Range Organics and Eight RCRA Metals)**

Facility Name: VA Gulfcoast Veterans Health Care System												Location: Gulfport, MS									
Sample #	Sample Location	Date Collected	EPA Method 8260								MTBE	DRO	As	Ba	Cd	Cr	Pb	Hg	Se	Ag	
			Acetone	2-Butanone	Benzene	Ethyl benzene	Toluene	Total Xylenes	BTX	MTBE											
DPS-1	P/L #1	2/28/2007	NA	NA	NA	NA	NA	NA	NA	NA	56	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPS-2	P/L #2	2/28/2007	NA	NA	NA	NA	NA	NA	NA	NA	49.50	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
DPS-7	Tank Pit #1	2/28/2007	NA	NA	< 0.0197	< 0.006	< 0.010	< 0.0397	< 0.005	< 0.07585	< 0.010	< 0.025	< 0.005	< 0.005	< 0.33	NA	NA	NA	NA	NA	NA
DPS-8	Tank Pit #1	2/28/2007	NA	NA	< 0.005	0.0551	0.00575	< 0.010	< 0.07585	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.33	NA	NA	NA	NA	NA	NA
DPS-9	Tank Pit #2	2/28/2007	NA	NA	< 0.005	< 0.005	< 0.005	< 0.010	< 0.010	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	NA	NA	NA	NA	NA	NA
DPS-11	Tank Pit #3	3/1/2007	NA	NA	< 0.005	0.00549	< 0.005	< 0.010	< 0.0255	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.33	NA	NA	NA	NA	NA	NA
DPS-12	Tank Pit #3	3/1/2007	NA	NA	< 0.005	< 0.005	< 0.005	< 0.010	< 0.010	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	NA	NA	NA	NA	NA	NA
DPS-13	Tank Pit #4	3/1/2007	NA	NA	< 0.005	0.00672	< 0.005	< 0.010	< 0.027	< 0.005	< 0.027	< 0.005	< 0.005	< 0.005	< 0.33	NA	NA	NA	NA	NA	NA
DPS-14	Tank Pit #4	3/1/2007	NA	NA	< 0.01	< 0.005	< 0.010	< 0.03	< 0.005	< 0.03	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	NA	NA	NA	NA	NA	NA
DPS-15	Pond #3	3/1/2007	NA	NA	< 0.005	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.33	NA	NA	NA	NA	NA	NA
DPS-16	B-33	10/10/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.44	12.8	< 0.489	2.72	11.8	0.029
DPS-17	B-50	10/10/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.42	1.19	< 0.484	< 0.484	< 2.42	< 0.025
DPS-18	P/L	10/10/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.33	15	< 0.466	7.21	5.41	< 0.025
DPS-19	B-32	10/11/2007	< 0.020	< 0.010	< 0.005	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.33	< 2.44	14.8	< 0.487	8.14	5.02	0.028
DPS-20	B-59	10/12/2007	< 0.020	< 0.010	< 0.005	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.33	< 2.44	13.4	< 0.472	3.53	4.59	< 0.025
DPS-21	B-117	10/12/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.42	3.7	< 0.484	2.73	51.3	0.066
DPS-22	B-60	10/11/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.42	1.19	< 0.484	< 0.484	< 2.42	< 0.025
DPS-23	B-602	10/11/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.42	1.19	< 0.484	< 0.484	< 2.42	< 0.025
DPS-24	B-6	10/11/2007	0.323	0.0362	< 0.005	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.33	< 2.43	17.3	< 0.487	5.8	26	0.078
DPS-25	B-6	12/5/2007	144	< 0.0481	< 0.024	< 0.024	< 0.048	< 0.024	< 0.012	< 0.025	< 0.012	< 0.012	< 0.012	< 0.012	< 0.33	< 2.43	10.8	< 0.478	10.8	356	2.26
DPS-26	B-61	10/11/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.43	10.8	< 0.478	10.8	356	2.26
DPS-27	B-76	10/11/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.43	10.8	< 0.478	10.8	356	2.26
DPS-28	B-119	10/11/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.43	10.8	< 0.478	10.8	356	2.26
DPS-29	B-245	10/12/2007	< 0.020	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.43	10.8	< 0.478	10.8	356	2.26
DPS-30	West of B-62	10/11/2007	< 0.02	< 0.01	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.43	10.8	< 0.478	10.8	356	2.26
DPS-31	Burn Pit	10/10/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.43	10.8	< 0.478	10.8	356	2.26
DPS-32	B-1/B-5	10/10/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.43	10.8	< 0.478	10.8	356	2.26
DPS-33	B-45	10/10/2007	< 0.050	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.43	10.8	< 0.478	10.8	356	2.26
DPS-34	Pond #3	10/12/2007	0.02558	< 0.010	< 0.005	< 0.005	< 0.010	< 0.025	< 0.005	< 0.025	< 0.005	< 0.005	< 0.005	< 0.005	< 0.33	< 2.43	10.8	< 0.478	10.8	356	2.26
MDEQ UST Typical Cleanup Levels*	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE
MDEQ Brownfields Tier 1	Unrestricted	7.820	84.5	0.887	395	38	318	3.910	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE
1 TRGs Restricted	104,000	84.5	1.36	395	38	318	8.740	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE

All results in mg/kg

Bolted results exceed applicable cleanup goal

MTBE - Methyl tert-Butyl Ether

BTX - Benzene, Toluene, Ethylbenzene, Total Xylenes

DRO - Diesel Range Organics

\* Diesel sites

\*\* -100 mg/kg at gasoline sites

NE - Not Established

As - Arsenic

Ba - Barium

Cr - Chromium

Cd - Cadmium

Hg - Mercury

Pb - Lead

Se - Selenium

Ag - Silver

# Result is given for Total Chromium, a sum of trivalent and hexavalent

Chromium, TRG is given for lower of trivalent and hexavalent values

Target Remediation Goal

Chromium, TRG is given for lower of trivalent and hexavalent values

TABLE 2A  
SOIL ANALYTICAL RESULTS  
(Volatile Organic Compounds, Diesel Range Organics and Eight RCRA Metals)

Facility Name: VA Gulfcoast Veterans Health Care System

Location: Gulfport, MS

Sample #	Sample Location	Date Collected	EPA Method 8260							MTBE	DRO	As	Ba	Cd	Cr	Pb	Hg	Se	Ag
			Acetone	Butanone	2-Benzene	Ethyl benzene	Toluene	Total Xylenes	BTEX										
DPS-49	B-6	12/5/2007	NA	NA	NA	NA	NA	NA	NA	3.6	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-50	B-6	12/5/2007	NA	NA	NA	NA	NA	NA	NA	11.1	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-51	B-6	12/5/2007	NA	NA	NA	NA	NA	NA	NA	10.5	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-59	B-32	12/3/2007	NA	NA	NA	NA	NA	NA	NA	<2.44	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-80	B-32	12/5/2007	NA	NA	NA	NA	NA	NA	NA	2.6	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-81	B-32	12/3/2007	NA	NA	NA	NA	NA	NA	NA	<1.67	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-82	B-32	12/3/2007	NA	NA	NA	NA	NA	NA	NA	5.41	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-67	B-61	12/5/2007	NA	NA	NA	NA	NA	NA	NA	<2.27	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-68	B-61	12/5/2007	NA	NA	NA	NA	NA	NA	NA	2.29	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-69	B-61	12/5/2007	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-70	B-61	12/5/2007	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-81	SE Corner 65 ft west of south gate	4/22/2008	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-82	217 ft east of B-4	4/22/2008	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-83	NW Corner	4/22/2008	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-84	B-6	4/24/2008	NA	NA	NA	NA	NA	NA	NA	0.83	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-85	B-6	4/24/2008	NA	NA	NA	NA	NA	NA	NA	1.94	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-86	B-6	4/24/2008	NA	NA	NA	NA	NA	NA	NA	2.71	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-87	B-6	4/24/2008	NA	NA	NA	NA	NA	NA	NA	2.97	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-88	B-32	4/24/2008	NA	NA	NA	NA	NA	NA	NA	1.86	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-89	B-32	4/24/2008	NA	NA	NA	NA	NA	NA	NA	1.34	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-90	B-32	4/24/2008	NA	NA	NA	NA	NA	NA	NA	<0.633	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-91	B-76	4/24/2008	NA	NA	NA	NA	NA	NA	NA	1.1	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-92	B-76	4/24/2008	NA	NA	NA	NA	NA	NA	NA	0.963	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-93	B-76	4/24/2008	NA	NA	NA	NA	NA	NA	NA	2.48	NA	NA	NA	NA	NA	NA	NA	NA	
DPS-98	Electrical Vault	4/24/2008	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
All results in mg/kg			<0.00025	<0.00032	<0.0003	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	
MDEQ UST Typical Cleanup Levels*	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	NE	
MDEQ Brownfields Tier 1 TRGs	Unrestricted	7,820	84.5	0.887	395	38	318	3,910	NE	300	0.426	5,480	39.1	227#	400	10	391	391	
	Restrictied	104,000	84.5	1.36	395	38	318	8,740	NE	350	3.28	14,300	1,020	381#	17.00	61.3	1,020	1,020	

Bolded results exceed applicable cleanup goal

MTBE - Methyl tert-Butyl Ether

BTEX - Benzene, Toluene, Ethylbenzene, Total Xylenes

DRO - Diesel Range Organics

\* Diesel sites

- 100 mg/kg at gasoline sites

\*\*

NE

#

Result is given for Total Chromium, a sum of trivalent and hexavalent Chromium. TRG is given for lower of trivalent and hexavalent values

Target Remediation Goal

Cr - Chromium  
Pb - Lead  
Ba - Barium  
Co - Cadmium  
Hg - Mercury

Ag - Silver

Se - Selenium

**TABLE 2B**  
**SOIL ANALYTICAL RESULTS**  
**(Semivolatile Organic Compounds)**

Facility Name: VA Gulfcoast Veterans Health Care System

Sample #	Sample Location	Date Collected	EPA Method 8081	SEMI-VOLATILE ORGANIC COMPOUNDS												POLYNUCLEAR AROMATIC HYDROCARBONS				Location: Gulfport, MS
				Phthalates	Bis(2-ethylhexyl phthalate)	Naphthalene	2-Methyl-naphthalene	Acenaphthylene	Acenaphthene	Fluorene	Phenanthrene	Pyrene	Benzo(a)anthracene	Chrysene	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Dibenzo(a,h)anthracene	Benzo(a)pyrene	Indeno[1,2,3-cd]pyrene	
DPS-1	P/L #1	2/28/2007	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	Indeno[1,2,3-cd]pyrene	
DPS-2	P/L #2	2/28/2007	NA	NA	NA	NA	<0.63	<0.63	<0.63	<0.63	1.68	1.53	0.77	0.8	0.81	<0.63	<0.63	<0.63	<0.63	
DPS-7	Tank Pit #1	2/28/2007	NA	NA	NA	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33		
DPS-8	Tank Pit #2	2/28/2007	NA	NA	NA	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33		
DPS-9	Tank Pit #3	2/28/2007	NA	NA	NA	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33		
DPS-11	Tank Pit #5	3/1/2007	NA	NA	NA	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33		
DPS-12	Tank Pit #3	3/1/2007	NA	NA	NA	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33		
DPS-13	Tank Pit #4	3/1/2007	NA	NA	NA	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33		
DPS-14	Tank Pit #4	3/1/2007	NA	NA	NA	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33		
DPS-15	Pond #3	3/1/2007	NA	NA	NA	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33		
DPS-16	B-33	10/10/2007	BDL*	0.43	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030		
DPS-17	B-50	10/10/2007	BDL*	0.59	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030		
DPS-18	P/L	10/10/2007	BDL*	0.44	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030		
DPS-19	B-32	10/11/2007	BDL*	0.48	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030		
DPS-20	B-59	10/12/2007	BDL*	0.08	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	0.07	<0.03	0.27	0.28	0.15	0.16	0.25	0.11	0.19	
DPS-21	B-117	10/11/2007	BDL*	0.21	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	0.11	
DPS-22	B-60	10/11/2007	BDL*	0.15	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	0.1	
DPS-23	B-602	10/11/2007	BDL*	0.19	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	
DPS-24	B-6	10/11/2007	BDL*	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	0.37	<0.33	0.48	0.34	<0.33	<0.33	<0.33	<0.33	<0.33	
DPS-25	B-6	12/5/2007	BDL*	0.07	0.36	0.11	<0.03	0.26	0.37	0.37	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	
DPS-26	B-61	10/11/2007	BDL*	0.51	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	<0.33	
DPS-27	B-76	10/11/2007	BDL*	0.25	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	0.11	
DPS-28	B-119	10/11/2007	BDL*	0.32	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	0.04	<0.03	0.07	0.05	<0.03	<0.03	<0.03	<0.03	0.57	
DPS-29	B-245	10/12/2007	BDL*	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	
DPS-30	West of B-62	10/11/2007	BDL*	0.40	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	
DPS-31	Burn Pit	10/10/2007	BDL*	0.24	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.03	
DPS-32	B-1/B-5	10/10/2007	BDL*	0.51	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.03	
DPS-33	B-45	10/10/2007	BDL*	0.22	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	
DPS-34	Pond #3	10/12/2007	BDL*	<0.73	<0.73	<0.73	<0.73	1.05	1.15	2.19	7.52	8.19	5	5.14	6.64	2.3	4.58	0.77	2.24	
MDEQ Brownfields Tier 1	Unrestricted TRGs	NE	45.6	9.8	NE	9.5	NE	NE	NE	NE	NE	NE	1	0.086	0.42	NE	NE	NE		
All results in mg/kg		409	247	40.900	123,000	123,000	81,700	61,300	613,000	81,700	23,500	3,130	NA	NA	NA	NA	NA	NA		
Bolted results exceed applicable cleanup goals																				
* - Diesel sites																				
TRG Target Remediation Goal																				
UST Underground Storage Tank																				

All results in mg/kg  
 Bolted results exceed applicable cleanup goals  
 \* - Diesel sites  
 TRG Target Remediation Goal  
 UST Underground Storage Tank  
 NE - Not Tested for this analyte  
 NA - Not Established  
 < - Less than BDL\*      No analyses in the indicated method group were detected.  
 Note: Dibenzofuran (0.21 mg/kg) and phenol (0.14 mg/kg) were detected in DPS-25. The TRGs are:  
 Dibenzofuran (313 mg/kg) and phenol (46,900 mg/kg).

**TABLE 2B**  
**SOIL ANALYTICAL RESULTS**  
**(Semivolatile Organic Compounds)**

Facility Name: VA Gulfcoast Veterans Health Care System

- Diesel sites

Target Remediation Goal:

Underground Storage Tank

ATTACHMENT 9

**SUBPART II**

**MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY**

**RISK EVALUATION PROCEDURES FOR**

**VOLUNTARY CLEANUP AND REDEVELOPMENT OF**

**BROWNFIELD SITES**

**APPENDIX A**

**TIER 1 TARGET REMEDIAL GOAL TABLE**

**MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY  
TIER 1 TRG TABLE**

CHEMICAL	CAS No.	Groundwater		Soil			
				Restricted		Unrestricted	
		ug/l	Notes	mg/kg	Notes	mg/kg	Notes
ACENAPHTHENE	83329	3.65E+02	N R	1.23E+05	N Ing	4.69E+03	N Ing
ACENAPHTHYLENE	208968	2.19E+03	N	1.23E+05	N Ing	4.69E+03	N Ing
ACEPHATE	30560191	7.70E+00	C	6.58E+02	C Ing	7.34E+01	C Ing
ACETALDEHYDE	75070	1.63E+00	C R	2.34E+01	C Inh	1.53E+01	C Ing
ACETOCHLOR	34256821	7.30E+02	N	4.09E+04	N Ing	1.56E+03	N Ing
ACETONE (DIMETHYL KETONE)	67641	6.08E+02	N R	1.04E+05	Csat	7.82E+03	N Ing
ACETONITRILE (CYANOMETHANE)	75058	1.25E+02	N R	1.11E+02	N Ing	1.11E+02	N Ing
ACETOPHENONE	75058	4.16E-02	N R	2.63E+03	Csat	2.63E+03	Csat
ACROLEIN	98862	4.16E-02	N R	4.09E+04	N Ing	1.56E+03	N Ing
ACRYLAMIDE	107028	4.16E-02	N R	2.04E+02	N Ing	1.42E-01	C Ing
ACRYLONITRILE	79061	1.49E-02	C	1.27E+00	C Ing	1.18E+00	C Ing
ALACHLOR	107131	3.67E-02	C	1.06E+01	C Ing	7.98E+00	C Ing
ALAR	15972608	2.00E+00	MCL	7.15E+01	C Ing	7.82E+01	N Ing
ALDICARB	1596845	5.48E+03	N	3.07E+05	N Ing	1.17E+04	N Ing
ALDICARB SULFONE	116063	3.65E+01	N R	2.04E+02	N Ing	7.82E+01	N Ing
ALDRIN	1646884	3.65E+01	N	2.04E+03	N Ing	7.82E+01	N Ing
ALUMINUM	309002	3.94E-03	C R	3.37E-01	C Ing	3.76E-02	C Ing
AMINODINITROTOLUENES	7429905	3.65E+04	N	2.04E+06	N Ing	7.82E+04	N Ing
4-AMINOPYRIDINE				2.19E+00	N	1.23E+02	N Ing
AMMONIA	504245	7.30E-01	N	4.09E+01	N Ing	4.69E+00	N Ing
ANILINE	7664417	2.09E+02	N			1.56E+00	N Ing
ANTHRACENTE	62533	1.17E+01	C	1.00E+03	C Ing	1.12E+02	C Ing
ANTIMONY	120127	4.34E+01	Csol	6.13E+05	N Ing	2.35E+04	N Ing
ANTIMONY PENTOXIDE	7440360	6.00E+00	MCL	8.17E+01	N Ing	3.13E+01	N Ing
ANTIMONY TETROXIDE	1314609	1.83E+01	N	1.02E+02	N Ing	3.91E+01	N Ing
ANTIMONY TRIOXIDE	1332816	1.46E+01	N	8.17E+01	N Ing	3.13E+01	N Ing
ARSENIC	1309644	1.46E+01	N	8.17E+01	N Ing	3.13E+01	N Ing
ARSINE	7440382	5.00E+01	MCL	3.82E+00	C Ing	4.26E-01	C Ing
ASSURE	7784421	1.02E-01	N				
ATRAZINE	76578148	3.29E+02	N	1.84E+04	N Ing	7.04E+02	N Ing
AZOBENZENE	1912249	3.00E+00	MCL	2.58E+01	C Ing	2.88E+00	C Ing
BARIUM	103333	6.09E-01	C	5.20E+01	C Ing	5.81E+00	C Ing
BAYGON	7440393	2.00E+03	MCL	1.43E+04	N Ing	5.48E+03	N Ing
BAYTHROID	114261	1.46E+02	N	8.18E+03	N Ing	3.13E+02	N Ing
BENTAZON	68359375	9.13E+02	N	5.11E+04	N Ing	1.96E+03	N Ing
BENZ[A]ANTHRACENE	25057890	1.10E+03	N	6.13E+04	N Ing	2.35E+03	N Ing
BENZALDEHYDE	56553	9.17E-02	C R	7.84E+00	C Ing	8.75E-01	C Ing
BENZENE	100527	3.65E+03	N	2.04E+05	N Ing	7.82E+03	N Ing
BENZENETHIOL	71432	5.00E+00	MCL	1.36E+00	C Inh	1.88E-01	C Ing
BENZIDINE	108985	8.08E-02	N	2.04E+01	N Ing	7.82E-01	N Ing
BENZOIC ACID	92875	2.91E-04	C	2.49E-02	C Ing	2.78E-03	C Ing
BENZO(A)PYRENE	65850	1.48E+05	N R	8.17E+05	N Ing	3.13E+05	N Ing
BENZO(B)FLUORANTHENE	50328	2.00E-01	MCL	7.84E-01	C Ing	8.75E-02	C Ing
BENZO(G,H,I)PERYLENE	205992	9.17E-02	C R	7.84E+00	C Ing	8.75E-01	C Ing
BENZO(K)FLUORANTHENE	191242	1.10E+03	N	6.13E+04	N Ing	2.35E+03	N Ing
BENZYL ALCOHOL	207089	9.17E-01	C R	7.84E+01	C Ing	8.75E+00	C Ing
BENZYL CHLORIDE (CHLOROMETHYLBENZENE)	100516	1.10E+04	N	2.04E+05	N Ing	2.35E+04	N Ing
BERYLLIUM	100447	6.21E-02	C R	3.37E+01	C Ing	3.76E+00	C Ing
BIPHENYL	7440417	4.00E+00	MCL	1.02E+03	N Ing	1.56E+02	N Ing
BIS(2-CHLOROETHYL)ETHER	92524	3.04E+02	N R	1.02E+04	N Ing	3.91E+03	N Ing
BIS(2-CHLOROISOPROPYL)ETHER	111444	9.20E-03	C R	4.19E-01	C Inh	1.273E-01	C Ing
BIS(CHLOROMETHYL)ETHER	108801	2.60E-01	C R	9.08E+00	C Inh	1.593E+00	C Ing
BIS(2-ETHYLHEXYL)PHthalate	542881	4.80E-05	C	2.60E-02	C Ing	2.90E-03	C Ing
BORON	117817	6.00E+00	MCL	4.09E+02	C Ing	4.58E+01	C Ing
BROMODICHLOROMETHANE (DICHLOROBROMOMETHANE)	7440428	3.29E+03	N	4.08E+03	N Ing	4.08E+03	N Ing
BROMOETHENE (VINYL BROMIDE)	75274	1.68E-01	C R	1.89E+00	C Ing	1.24E+00	C Ing
BROMOFORM (METHYL TRIBROMIDE)	593602	1.12E-01	C R	1.26E-01	N Ing	1.26E-01	N Ing
BROMOMETHANE (METHYL BROMIDE)	75252	8.48E+00	C R	9.01E+01	C Ing	5.88E+01	C Ing
BROMOPHOS	74839	8.52E+00	N R	2.97E+00	N Ing	2.97E+00	N Ing
1,3-BUTADIENE	2104963	1.83E+02	N	1.02E+04	N Ing	3.91E+02	N Ing
1-BUTANOL	106990	6.96E-03	C				
2-BUTANONE (METHYL ETHYL KETONE)	71363	3.65E+03	N R	1.05E+04	Csat	7.82E+03	N Ing
BUTYLBENZYLPHthalate	78933	1.91E+03	N R	8.45E+01	N Ing	8.45E+01	N Ing
BUTYLATE	85687	2.69E+03	Csol	9.28E+02	Csat	9.28E+02	Csat
N-BUTYLBENZENE	2008415	1.83E+03	N	1.02E+04	N Ing	3.91E+03	N Ing
SEC-BUTYLBENZENE	104518	2.43E+02	N	8.18E+04	N Ing	3.13E+03	N Ing
TERT-BUTYLBENZENE	135988	2.43E+02	N	8.18E+04	N Ing	3.13E+03	N Ing
CADMIUM	98066	2.43E+02	N	8.18E+04	N Ing	3.13E+03	N Ing
CALCIUM CYANIDE	7440439	5.00E+00	MCL	1.02E+03	N Ing	3.91E+01	N Ing
	592018	1.46E+03	N	8.17E+03	N Ing	3.13E+03	N Ing

**MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY  
TIER 1 TRG TABLE**

CHEMICAL	CAS No.	Groundwater		Soil						
				Restricted		Unrestricted				
		ug/l	Notes	mg/kg	Notes	mg/kg	Notes			
CAPROLACTAM	105602	1.83E+04	N	1.02E+05	N	3.91E+04	N			
CARBARYL	63252	3.65E+03	N	2.04E+04	N	7.82E+03	N			
CARBAZOLE	86748	3.35E+00	C R	2.80E+02	C	3.19E+01	C			
CARBOFURAN	1563662	4.00E+01		MCL	1.02E+03	N	3.91E+02	N		
CARBON CHLORIDE (CARBON TETRACHLORIDE)	56235	5.00E+00		MCL	5.69E-01	C	3.71E-01	C		
CARBON DISULFIDE	75150	1.04E+03	N R	7.97E+00	N	1	3.71E-01	C	Inh	1
CARBON TETRACHLORIDE (CARBON CHLORIDE)	56235	5.00E+00		MCL	5.69E-01	C	3.71E-01	C	Inh	1
CARBOSULFAN	55285148	3.65E+02	N	2.04E+04	N	7.82E+02	N	Inh		
CHLORAL HYDRATE	302170	3.65E+03	N	4.08E+03	N	4.08E+03	N	Inh		
CHLORANIL	118752	1.66E-01	C	1.42E+01	C	1.58E+00	C	Inh		
CHLORDANE	57749	2.00E+00		MCL	1.23E+01	N	1.82E+00	C	Inh	
CHLORINE	7782505	4.16E-01	N	2.04E+05	N	7.82E+03	N	Inh		
CHLORINE DIOXIDE	10049044	4.17E-01	N	6.13E+04	N	2.35E+03	N	Inh		
CHLORITE	7758192	1.10E+03	N	6.13E+04	N	2.35E+03	N	Inh		
CHLOROACETIC ACID	79118	7.30E+01	N	4.08E+03	N	1.56E+02	N	Inh		
4-CHLOROANILINE	106478	1.46E+02	N R	8.17E+02	N	3.13E+02	N	Inh		
CHLOROBENZENE (MONOCHLOROBENZENE)	108907	1.00E+02		MCL	1.19E+00	N	1.19E+00	N	Inh	1
CHLOROBENZILATE	510156	2.48E-01	C	2.12E+01	C	2.37E+00	C	Inh		
P-CHLOROBENZOIC ACID	74113	7.30E+03	N	4.08E+05	N	1.56E+04	N	Inh		
CHLORO-1,3-BUTADIENE	126998	1.43E+01	N	4.08E+03	N	1.56E+03	N	Inh		
1-CHLOROBUTANE	109693	2.43E+03	N	1.84E+05	N	3.13E+04	N	Inh		
CHLORODIBROMOMETHANE (DIBROMOCHLOROMETHANE)	124481	1.26E-01	C R	6.81E+01	C	7.60E+00	C	Inh		
1-CHLORO-1,1-DIFLUOROETHANE	75683	1.02E+05	N							
CHLORODIFLUOROMETHANE (DIFLUOROCHLOROMETHANE)	75456	1.02E+05	N							
CHLOROETHANE	75003	3.64E+00	C	1.97E+03	C	2.20E+02	C	Inh		
CHLOROETHENE (VINYL CHLORIDE)	75014	2.00E+00		MCL	9.39E-01	C	4.26E-01	C	Inh	
CHLOROFORM (METHANE TRICHLORIDE)	67663	1.55E-01	C R	4.78E-01	C	1	3.12E-01	C	Inh	1
CHLOROMETHANE (METHYL CHLORIDE)	74873	1.43E+00	C	4.40E+02	C	4.91E+01	C	Inh		
4-CHLORO-2-METHYLANILINE	95692	1.15E-01	C	9.87E+00	C	1.10E+00	C	Inh		
CHLOROMETHYLBENZENE (BENZYL CHLORIDE)	100447	6.21E-02	C R	3.37E+01	C	3.76E+00	C	Inh		
4-CHLORO-3-METHYLPHENOL (P-CHLORO-M-CRESOL)	59507	7.30E+04	N R	4.08E+05	N	1.56E+05	N	Inh		
BETA-CHLORONAPHTHALENE	91587	4.87E+02	N	1.64E+05	N	6.26E+03	N	Inh		
O-CHLORONITROBENZENE	88733	4.22E-01	C	2.29E+02	C	2.55E+01	C	Inh		
P-CHLORONITROBENZENE	100005	5.86E-01	C	3.18E+02	C	3.55E+01	C	Inh		
2-CHLOROPHENOL	95578	3.04E+01	N R	1.02E+04	N	3.91E+02	N	Inh		
2-CHLOROPROPANE	75296	2.12E+02	N							
O-CHLOROTOLUENE	95498	1.22E+02	N	4.08E+04	N	1.56E+03	N	Inh		
CHLORPYRIFOS	2921882	1.10E+02	N	6.13E+02	N	2.35E+02	N	Inh		
CHLORPYRIFOS-METHYL	5598130	3.65E+02	N	2.04E+03	N	7.82E+02	N	Inh		
CHROMIUM III	16065831	5.48E+04	N	3.07E+06	N	1.17E+05	N	Inh		
CHROMIUM VI	18540299	1.00E+02		MCL	3.81E+02	C	2.27E+02	C	Inh	2
CHRYSENE	218019	9.17E+00	C R	7.84E+02	C	8.75E+01	C	Inh		
COBALT	7440484	2.19E+03	N	1.23E+04	N	4.69E+03	N	Inh		
COKE OVEN EMISSIONS (COAL TAR)	8007452	5.69E-03	C							
COPPER	7440508	1.30E+03		MCL	8.17E+03	N	3.13E+03	N	Inh	
COPPER CYANIDE	544923	1.83E+02	N	1.02E+04	N	3.91E+02	N	Inh		
o-CRESOL (2-METHYLPHENOL)	95487	1.83E+03	N	1.02E+05	N	3.91E+03	N	Inh		
m-CRESOL (3-METHYLPHENOL)	108394	1.83E+03	N	1.02E+05	N	3.91E+03	N	Inh		
p-CRESOL (4-METHYLPHENOL)	106445	1.83E+02	N	1.02E+04	N	3.91E+02	N	Inh		
CROTONALDEHYDE	123739	5.59E-03	C	3.01E+00	C	3.38E-01	C	Inh		
CUMENE (ISOPROPYL BENZENE)	98828	6.79E+02	N R	9.43E+00	N	1	9.43E+00	N	Inh	1
CYANAZINE	21725462	7.97E-02	C	6.81E+00	C	7.60E-01	C	Inh		
CYANIDE (FREE)	57125	2.00E+02		MCL	4.08E+03	N	1.56E+03	N	Inh	
CALCIUM CYANIDE	592018	1.46E+03	N	8.17E+03	N	3.13E+03	N	Inh		
COPPER CYANIDE	544923	1.83E+02	N	1.02E+04	N	3.91E+02	N	Inh		
CYANAZINE	21725462	7.97E-02	C	6.81E+00	C	7.60E-01	C	Inh		
CYANOGEN	460195	2.43E+02	N	8.18E+04	N	3.13E+03	N	Inh		
CYANOGEN BROMIDE	506683	3.29E+03	N	1.84E+05	N	7.04E+03	N	Inh		
CYANOGEN CHLORIDE	506774	1.83E+03	N	1.02E+05	N	3.91E+03	N	Inh		
HYDROGEN CYANIDE	74908	6.22E+00	N	4.08E+04	N	1.56E+03	N	Inh		
POTASSIUM CYANIDE	151508	1.83E+03	N	1.02E+04	N	3.91E+03	N	Inh		
POTASSIUM SILVER CYANIDE	506616	7.30E+03	N	4.08E+04	N	1.56E+04	N	Inh		
SILVER CYANIDE	506649	3.65E+03	N	2.04E+04	N	7.82E+03	N	Inh		
SODIUM CYANIDE	143339	1.46E+03	N	8.17E+03	N	3.13E+03	N	Inh		
THIOCYANATE		1.83E+03	N	1.02E+05	N	3.91E+03	N	Inh		
ZINC CYANIDE	557211	1.83E+03	N	1.02E+04	N	3.91E+03	N	Inh		
CYANOMETHANE (ACETONITRILE)	75058	1.25E+02	N R	1.11E+02	N	1.11E+02	N	Inh	1	
CYCLOHEXANONE	108941	1.83E+05	N	1.02E+07	N	3.91E+05	N	Inh		
CYCLONITE (RDX)	121824	6.09E-01	C	5.20E+01	C	5.81E+00	C	Inh		

**MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY  
TIER 1 TRG TABLE**

CHEMICAL	CAS No.	Groundwater		Soil			
				Restricted		Unrestricted	
		ug/l	Notes	mg/kg	Notes	mg/kg	Notes
CYHALOTHRIN/KARATE	68085858	1.83E+02	N	1.02E+04	N	3.91E+02	N
CYPERMETHRIN	52315078	3.65E+02	N	2.04E+04	N	7.82E+02	N
DACTHAL	1861321	3.65E+02	N	2.04E+04	N	7.82E+02	N
DALAPON	75990	2.00E+02	MCL	6.13E+03	N	2.35E+03	N
DDD	72548	2.79E-01	C R	2.38E+01	C	2.66E+00	C
DDE	72559	1.97E-01	C R	1.68E+01	C	1.88E+00	C
DDT	50293	1.97E-01	C R	1.68E+01	C	1.88E+00	C
DIAZINON	333415	3.29E+01	N	1.84E+03	N	7.04E+01	N
DIBENZOFURAN	132649	2.43E+01	N	8.18E+03	N	3.13E+02	N
DIBENZ[A,H]ANTHRACENE	53703	9.17E-03	C R	7.84E-01	C	8.75E-02	C
1,4-DIBROMOBENZENE	106376	3.65E+02	N	2.04E+04	N	7.82E+02	N
DIBROMOCHLOROMETHANE (CHLORODIBROMOMETHANE)	124481	1.26E-01	C R	6.81E+01	C	7.60E+00	C
1,2-DIBROMO-3-CHLOROPROPANE	96128	2.00E-01	MCL	9.99E-02	N	1 9.99E-02	N
DIBROMOMETHANE (METHYLENE BROMIDE)	74953	6.08E+01	N	2.04E+04	N	7.82E+02	N
1,2-DIBROMOETHANE (ETHYLENE DIBROMIDE)	106934	5.00E-02	MCL	6.73E-02	C	7.51E-03	C
DI-N-BUTYLPHthalate	84742	3.65E+03	N R	2.28E+03	Csat	2.28E+03	Csat
DICAMBA	1918009	1.10E+03	N	6.13E+04	N	2.35E+03	N
1,2-DICHLOROBENZENE	95501	6.00E+02	MCL	2.79E+02	N	1 2.79E+02	N
1,3-DICHLOROBENZENE	541731	5.48E+00	N	1.84E+03	N	7.04E+01	N
1,4-DICHLOROBENZENE	106467	7.50E+01	MCL	2.38E+02	C	2.66E+01	C
3,3-DICHLOROBENZIDINE	91941	1.49E-01	C R	1.27E+01	C	1.42E+00	C
DICHLOROBROMOMETHANE (BROMODICHLOROMETHANE)	75274	1.68E-01	C R	1.89E+00	C	1 1.24E+00	C
1,4-DICHLORO-2-BUTENE	764410	1.35E-03	C				
DICHLORODIFLUOROMETHANE	75718	3.48E+02	N	4.09E+05	N	1.56E+04	N
1,1-DICHLOROETHANE	75343	7.98E+02	N R	1.16E+02	N	1 1.16E+02	N
1,2-DICHLOROETHANE (ETHYLENE DICHLORIDE)	107062	5.00E+00	MCL	6.21E-01	C	1 4.06E-01	C
1,1-DICHLOROETHENE (1,1 - DCE)	75354	7.00E+00	MCL	1.18E-01	C	1 7.72E-02	C
CIS-1,2-DICHLOROETHENE	156592	7.00E+01	MCL	1.21E+03	Csat	7.82E+02	N
TRANS-1,2-DICHLOROETHENE	156605	1.00E+02	MCL	3.07E+03	Csat	1.56E+03	N
DICHLOROMETHANE (METHYLENE CHLORIDE)	75092	5.00E+00	MCL	2.19E+01	C	1 1.43E+01	C
2,4-DICHLOROPHENOL	120832	1.10E+02	N R	6.13E+02	N	2.35E+02	N
2,4-DICHLOROPHOXYACETIC ACID (2,4-D)	94757	7.00E+01	MCL	2.04E+03	N	7.82E+02	N
4-(2-DICHLOROPHOXY)BUTYRIC ACID	94826	2.92E+02	N	1.64E+04	N	6.26E+02	N
1,2-DICHLOROPROPANE	78875	5.00E+00	MCL	4.45E-01	N	1 4.45E-01	N
2,3-DICHLOROPROPANOL	616239	1.10E+02	N	6.13E+03	N	2.35E+02	N
1,3-DICHLOROPROPENE (1,3-DICHLOROPROPYLENE, CIS + TRANS)	542756	8.42E-02	C R	3.52E-01	N	1 3.52E-01	N
DICHLORVOS	82737	2.31E-01	C	1.97E+01	C	2.20E+00	C
DICCFOL	115322	1.52E-01	C	1.30E+01	C	1.45E+00	C
DICYCLOPENTADIENE	77736	4.38E-01	N	6.13E+04	N	2.35E+03	N
DIELDRIN	60571	4.19E-03	C R	3.58E-01	C	3.99E-02	C
DIETHYLPHthalate	84662	2.92E+04	N R	1.97E+03	Csat	1.97E+03	Csat
DIETHYLENE GLYCOL, MONOETHYL ETHER	111900	7.30E+04	N	4.09E+06	N	1.56E+05	N
DI(2-ETHYLHEXYL)ADIPATE	103231	4.00E+02	MCL	4.77E+03	C	5.32E+02	C
DIETHYLSTILBESTROL	56531	1.42E-05	C	1.22E-03	C	1.36E-04	C
DIFENOZOQUAT (AVENGE)	43222486	2.92E+03	N	1.64E+05	N	6.26E+03	N
DIFLUOROCHLOROMETHANE (CHLORODIFLUOROMETHANE)	75456	1.02E+05	N				
1,1-DIFLUOROETHANE	75376	8.03E+04	N				
DIISOPROPYL METHYLPHOSPHONATE (DIMP)	1445756	2.92E+03	N	1.64E+05	N	6.26E+03	N
3,3-DIMETHOXYBENZIDINE	119904	4.78E+00	C	4.09E+02	C	4.56E+01	C
2,4-DIMETHYLANILINE HYDROCHLORIDE	21436964	1.15E-01	C	9.87E+00	C	1.10E+00	C
2,4-DIMETHYLANILINE	95681	8.93E-02	C	7.63E+00	C	8.52E-01	C
N,N-DIMETHYLANILINE	121697	7.30E+01	N	4.08E+03	N	1.56E+02	N
3,3-DIMETHYLBENZIDINE	119937	7.28E-03	C	6.22E-01	C	6.94E-02	C
1,1-DIMETHYLHYDRAZINE	57147	2.58E-02	C	2.20E+00	C	2.46E-01	C
1,2-DIMETHYLHYDRAZINE	540738	1.81E-03	C	1.55E-01	C	1.73E-02	C
DIMETHYL KETONE (ACETONE)	67641	6.08E+02	N R	1.04E+05	Csat	7.82E+03	N
2,4-DIMETHYLPHENOL	105679	7.30E+02	N R	4.08E+04	N	1.56E+03	N
2,6-DIMETHYLPHENOL	576261	2.19E+01	N	1.23E+03	N	4.69E+01	N
3,4-DIMETHYLPHENOL	95658	3.65E+01	N	2.04E+03	N	7.82E+01	N
DIMETHYLPHthalate	131113	3.65E+05	N	2.04E+07	N	7.82E+05	N
1,2-DINITROBENZENE	528290	1.46E+01	N	8.17E+02	N	3.13E+01	N
1,3-DINITROBENZENE	99650	3.65E+00	N	2.04E+02	N	7.82E+00	N
1,4-DINITROBENZENE	100254	1.46E+01	N	8.17E+02	N	3.13E+01	N
4,6-DINITRO-O-CYCLOHEXYL PHENOL	131895	7.30E+01	N	4.09E+03	N	1.56E+02	N
4,6-DINITRO-2-METHYLPHENOL	534521	3.65E+00	N	2.04E+02	N	7.82E+00	N
2,4-DINITROPHENOL	51285	7.30E+01	N R	4.08E+02	N	1.56E+02	N
DINITROTOLUENE MIXTURE		9.85E-02	C	8.42E+00	C	9.39E-01	C
2,4-DINITROTOLUENE	121142	7.30E+01	N R	4.08E+02	N	1.56E+02	N
2,6-DINITROTOLUENE	606202	3.65E+01	N R	2.04E+03	N	7.82E+01	N

**MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY**  
**TIER 1 TRG TABLE**

CHEMICAL	CAS No.	Groundwater		Soil			
				Restricted		Unrestricted	
		ug/l	Notes	mg/kg	Notes	mg/kg	Notes
DINOSEB	88857	7.00E+00	MCL	2.04E+02	N	7.82E+01	N
DI-N-OCTYLPHthalATE	117840	2.00E+01	Csol	4.08E+03	N	1.56E+03	N
1,4-DIOXANE	123911	6.09E+00	C	5.20E+02	C	5.81E+01	C
DIOXATHION	78342	5.48E+01	N	3.07E+03	N	1.17E+02	N
DIOXINS & FURANS							
2,3,7,8-TETRACHLORODIBENZO-P-DIOXIN (TCDD)	1746016	3.00E-05	MCL	3.82E-05	C	4.26E-06	C
1,2,3,4,6,7,8-HEPTACHLORODIBENZO-P-DIOXIN (HpCDD)	35822469	4.46E-05	C	3.82E-03	C	4.26E-04	C
1,2,3,4,7,8-HEXAChLORODIBENZO-P-DIOXIN (HxCDD)	39227286	4.46E-06	C	3.82E-04	C	4.26E-05	C
1,2,3,6,7,8-HEXAChLORODIBENZO-P-DIOXIN (HxCDD)	57653857	1.08E-05	C	9.23E-04	C	1.03E-04	C
1,2,3,7,8,9-HEXAChLORODIBENZO-P-DIOXIN (HxCDD)	19408743	1.08E-05	C	9.23E-04	C	1.03E-04	C
1,2,3,4,6,7,8,9-OCTAChLORODIBENZO-P-DIOXIN (OCDD)	3268879	4.46E-04	C	3.82E-02	C	4.26E-03	C
1,2,3,7,8-PENTACHLORODIBENZO-P-DIOXIN (PeCDD)	40321764	8.93E-07	C	7.63E-05	C	8.52E-06	C
1,2,3,4,6,7,8-HEPTACHLORODIBENZOFURAN (HpCDF)	67562394	4.46E-05	C	3.82E-03	C	4.26E-04	C
1,2,3,4,7,8,9-HEPTACHLORODIBENZOFURAN (HpCDF)	55673897	4.46E-05	C	3.82E-03	C	4.26E-04	C
1,2,3,4,7,8-HEXAChLORODIBENZOFURAN (HxCDF)	70648269	4.46E-06	C	3.82E-04	C	4.26E-05	C
1,2,3,6,7,8-HEXAChLORODIBENZOFURAN (HxCDF)	57117449	4.46E-06	C	3.82E-04	C	4.26E-05	C
1,2,3,7,8,9-HEXAChLORODIBENZOFURAN (HxCDF)	72918219	4.46E-06	C	3.82E-04	C	4.26E-05	C
2,3,4,6,7,8-HEXAChLORODIBENZOFURAN (HxCDF)	60851345	4.46E-06	C	3.82E-04	C	4.26E-05	C
1,2,3,4,6,7,8,9-OCTAChLORODIBENZOFURAN (OCDF)	39001020	4.46E-04	C	3.82E-02	C	4.26E-03	C
1,2,3,7,8-PENTACHLORODIBENZOFURAN (PeCDF)	57117416	8.93E-06	C	7.63E-04	C	8.52E-05	C
2,3,4,7,8-PENTACHLORODIBENZOFURAN (PeCDF)	57117314	8.93E-07	C	7.63E-05	C	8.52E-06	C
2,3,7,8-TETRACHLORODIBENZOFURAN (TCDF)	51207319	4.46E-06	C	3.82E-04	C	4.26E-05	C
DIPHENYLAMINE	122394	9.13E+02	N	5.10E+03	N	1.96E+03	N
1,2-DIPHENYLHYDRAZINE	122667	8.37E-02	C	7.15E+00	C	7.98E-01	C
DIQUAT	85007	2.00E+01	MCL	4.50E+03	N	1.72E+02	N
DISULFOTON	298044	1.46E+00	N	8.17E+00	N	3.13E+00	N
1,4-DITHIANE	505293	3.65E+02	N	2.04E+04	N	7.82E+02	N
DIURON	330541	7.30E+01	N	4.09E+03	N	1.56E+02	N
ENDOSULFAN	115297	2.19E+02	N R	1.23E+03	N	4.69E+02	N
ENDRIN	72208	2.00E+00	MCL	6.13E+01	N	2.35E+01	N
EPICHLOROHYDRIN	106898	2.03E+00	N	4.08E+02	N	6.45E+01	C
ETHION	563122	1.83E+01	N	1.02E+03	N	3.91E+01	N
2-ETHOXYETHANOL	110805	1.46E+04	N	1.02E+05	N	3.13E+04	N
ETHYL ACETATE	141786	5.48E+03	N	1.84E+06	N	7.04E+04	N
ETHYL BENZENE	100414	7.00E+02	MCL	3.85E+02	Csat	3.95E+02	Csat
ETHYLENE DIAMINE	107153	7.30E+02	N	4.08E+03	N	1.56E+03	N
ETHYLENE DIBROMIDE (1,2-DIBROMOETHANE)	106934	5.00E-02	MCL	6.73E-02	C	7.51E-03	C
ETHYLENE DICHLORIDE (1,2-DICHLOROETHANE)	107062	5.00E+00	MCL	6.21E-01	C Inh	1 4.06E-01	C Inh
ETHYLENE GLYCOL	107211	7.30E+04	N	4.08E+05	N	1.56E+05	N
ETHYLENE GLYCOL MONOBUTYL ETHER (2-BUTOXYETHANOL)	111762	1.08E+04	N	1.02E+06	N	3.91E+04	N
ETHYLENE OXIDE	75218	2.32E-02	C	5.61E+00	C	6.26E-01	C
ETHYLENE THIOUREA	96457	6.09E-01	C	1.63E+01	N	5.81E+00	C
ETHYLETHER	60297	1.22E+03	N	4.08E+05	N	1.56E+04	N
ETHYL METHACRYLATE	97632	5.48E+02	N	1.84E+04	N	7.04E+03	N
FENAMIPHOS	22224926	9.13E+00	N	5.11E+02	N	1.96E+01	N
FLUOMETURON	2164172	4.75E+02	N	2.66E+04	N	1.02E+03	N
FLUORANTHENE	206440	1.46E+03	N R	8.17E+04	N	3.13E+03	N
FLUORENE	86737	2.43E+02	N R	8.17E+04	N	3.13E+03	N
FLUORINE (SOLUBLE FLUORIDE)	7782414	4.00E+03	MCL	1.23E+04	N	4.69E+03	N
FOMESAFEN	72178020	3.52E-01	C	3.01E+01	C	3.36E+00	C
FONOFO	944229	7.30E+01	N	4.09E+03	N	1.56E+02	N
FORMALDEHYDE	50000	7.30E+03	N	4.08E+04	N	1.56E+04	N
FORMIC ACID	64186	7.30E+04	N	4.08E+05	N	1.56E+05	N
FURAN	110009	6.08E+00	N	2.04E+03	N	7.82E+01	N
FURAZOLIDONE	67458	1.76E-02	C	1.51E+00	C	1.68E-01	C
FURFURAL	98011	1.10E+02	N	6.13E+03	N	2.35E+02	N
GLYCIDALDEHYDE	765344	1.46E+01	N	8.17E+02	N	3.13E+01	N
GLYPHOSATE	1071836	7.00E+02	MCL	2.04E+05	N	7.82E+03	N
HEPTACHLOR	76448	4.00E-01	MCL	1.95E-01	C Inh	1 1.27E-01	C Inh
HEPTACHLOR EPOXIDE	1024573	2.00E-01	MCL	6.29E-01	C	7.02E-02	C
1,2,3,4,6,7,8-HEPTACHLORODIBENZOFURAN (HpCDF)	67562394	4.46E-05	C	3.82E-03	C	4.26E-04	C
1,2,3,4,7,8,9-HEPTACHLORODIBENZOFURAN (HpCDF)	55673897	4.46E-05	C	3.82E-03	C	4.26E-04	C
1,2,3,4,6,7,8-HEPTACHLORODIBENZO-P-DIOXIN (HpCDD)	35822469	4.46E-05	C	3.82E-03	C	4.26E-04	C
HEXBROMOBENZENE	87821	7.30E+01	N	4.08E+03	N	1.56E+02	N
HEXAChLOROBENZENE	118741	1.00E+00	MCL	1.65E+00	C Inh	1 3.99E-01	C Inh
HEXAChLOROBUTADIENE	87683	8.59E-01	C R	1.35E-01	C Inh	1 8.82E-02	C Inh
ALPHA-HCH	319845	1.06E-02	C R	9.08E-01	C	1.01E-01	C
BETA-HCH	319857	3.72E-02	C R	3.18E+00	C	3.55E-01	C
GAMMA-HCH (LINDANE)	58899	2.00E-01	MCL	4.40E+00	C	4.91E-01	C
TECHNICAL HCH	608731	3.72E-02	C	3.18E+00	C	3.55E-01	C

**MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY**  
**TIER 1 TRG TABLE**

CHEMICAL	CAS No.	Groundwater		Soil					
				Restricted		Unrestricted			
		ug/l	Notes	mg/kg	Notes	mg/kg	Notes		
HEXAChLOROCYCLOPENTADIENE	77474	5.00E+01	MCL	9.51E-01	N Inh	1	9.51E-01	N Inh	1
1,2,3,4,7,8-HEXAChLORODIBENZOFURAN (HxCDF)	70648269	4.46E-06	C	3.82E-04	C Ing		4.26E-05	C Ing	
1,2,3,6,7,8-HEXAChLORODIBENZOFURAN (HxCDF)	57117449	4.46E-06	C	3.82E-04	C Ing		4.26E-05	C Ing	
1,2,3,7,8,9-HEXAChLORODIBENZOFURAN (HxCDF)	72918219	4.46E-06	C	3.82E-04	C Ing		4.26E-05	C Ing	
2,3,4,6,7,8-HEXAChLORODIBENZOFURAN (HxCDF)	60851345	4.46E-06	C	3.82E-04	C Ing		4.26E-05	C Ing	
1,2,3,4,7,8-HEXAChLORODIBENZO-P-DIOXIN (HxCDD)	39227286	4.46E-06	C	3.82E-04	C Ing		4.26E-05	C Ing	
1,2,3,6,7,8-HEXAChLORODIBENZO-P-DIOXIN (HxCDD)	57653857	1.08E-05	C	9.23E-04	C Ing		1.03E-04	C Ing	
1,2,3,7,8,9-HEXAChLORODIBENZO-P-DIOXIN (HxCDD)	19408743	1.08E-05	C	9.23E-04	C Ing		1.03E-04	C Ing	
HEXAChLOROETHANE	67721	4.78E+00	C R	9.33E+01	C Inh	1	4.56E+01	C Ing	
HEXAChLOROPHENe	70304	1.10E+01	N	6.13E+02	N Ing		2.35E+01	N Ing	
1,6-HEXAMETHYLENE DIISOCYANATE	822060	2.09E-02	N		C			N	
HEXANE	110543	3.50E+02	N R	1.60E+00	N Inh	1	1.60E+00	N Inh	1
2-HEXANONE	591786	1.46E+03	N	8.18E+04	N Ing		3.13E+03	N Ing	
HEXAZINONE	51235042	1.20E+03	N	6.75E+04	N Ing		2.58E+03	N Ing	
HMX	2691410	1.63E+03	N	1.02E+05	N Ing		3.81E+03	N Ing	
HYDRAZINE	302012	2.23E-02	C	1.91E+00	C Ing		2.13E-01	C Ing	
HYDROGEN CYANIDE	74908	6.22E+00	N	4.09E+04	N Ing		1.56E+03	N Ing	
HYDROGEN SULFIDE	7783064	1.10E+02	N	6.13E+03	N Ing		2.35E+02	N Ing	
HYDROQUINONE	123319	1.46E+03	N	8.17E+04	N Ing		3.13E+03	N Ing	
INDENO[1,2,3-C,D]PYRENE	193395	9.17E-02	C R	7.84E+00	C Ing		8.75E-01	C Ing	
IRON	7439896	1.10E+04	N	6.13E+05	N Ing		2.35E+04	N Ing	
ISOBUTANOL	78831	1.83E+03	N	6.13E+05	N Ing		2.35E+04	N Ing	
ISOPHORONE	78591	7.05E+01	C R	4.57E+03	Csat		6.72E+02	C Ing	
ISOPROPALIN	33820530	5.48E+02	N	3.06E+04	N Ing		1.17E+03	N Ing	
ISOPROPYL BENZENE (CUMENE)	98828	6.79E+02	N R	9.43E+00	N Inh	1	9.43E+00	N Inh	1
ISOPROPYL METHYL PHOSPHONIC ACID	1832548	3.65E+03	N	2.04E+05	N Ing		7.82E+03	N Ing	
LEAD	7439921	1.50E+01	MCL	1.70E+03	C Ing		4.00E+02	C Ing	4
LEAD (TETRAETHYL LEAD)	78002	3.65E-03	N	2.04E-01	N Ing		7.82E-03	N Ing	
LINDANE (GAMMA-HCH)	58899	2.00E-01	MCL	4.40E+00	C Ing		4.91E-01	C Ing	
LITHIUM	7439932	7.30E+02	N	4.09E+04	N Ing		1.56E+03	N Ing	
MALATHION	121755	7.30E+02	N	4.08E+03	N Ing		1.56E+03	N Ing	
MALEIC ANHYDRIDE	108316	3.65E+03	N	2.04E+04	N Ing		7.82E+03	N Ing	
MANGANESE	7439965	7.30E+02	N	4.08E+03	N Ing		1.56E+03	N Ing	
MEPHOSFOLAN	950107	3.29E+00	N	1.84E+02	N Ing		7.04E+00	N Ing	5
MEPIQUAT CHLORIDE	24307264	1.10E+03	N	6.13E+04	N Ing		2.35E+03	N Ing	
MERCURIC CHLORIDE	7487947	1.10E+01	N	6.13E+01	N Ing		2.35E+01	N Ing	
MERCURY (INORGANIC)	7439976	2.00E+00	MCL	6.13E+01	N Ing		1.00E+01	N Inh	2
METHYL MERCURY	22067926	3.65E+00	N	2.04E+02	N Ing		7.82E+00	N Ing	
METHACRYLONITRILE	126987	1.04E+00	N	2.04E+02	N Ing		7.82E+00	N Ing	
METHANE TRICHLORIDE (CHLOROFORM)	67663	#VALUE!	C R	4.78E-01	C Inh	1	3.12E-01	C Inh	1
METHANOL	67561	1.83E+04	N	1.02E+06	N Ing		3.91E+04	N Ing	
METHIDATHION	950378	3.65E+01	N	2.04E+03	N Ing		7.82E+01	N Ing	
METHOXYCHLOR	72435	4.00E+01	MCL	1.02E+03	N Ing		3.91E+02	N Ing	
METHYL ACETATE	79209	6.08E+03	N	2.04E+06	N Ing		7.82E+04	N Ing	
METHYL ACRYLATE	96333	1.83E+02	N	6.13E+03	N Ing		2.35E+03	N Ing	
METHYL BROMIDE (BROMOMETHANE)	74839	8.52E+00	N R	2.97E+00	N Inh	1	2.97E+00	N Inh	1
METHYL CHLORIDE (CHLOROMETHANE)	74873	1.43E+00	C	4.40E+02	C Ing		4.91E+01	C Ing	
2-METHYLANILINE	95534	2.79E-01	C	2.38E+01	C Ing		2.66E+00	C Ing	
4-(2-METHYL-4-CHLOROPHOXY) BUTYRIC ACID	94815	3.65E+02	N	2.04E+04	N Ing		7.82E+02	N Ing	
2-METHYL-4-CHLOROPHOXYACETIC ACID (MCPA)	94746	1.83E+01	N	1.02E+03	N Ing		3.91E+01	N Ing	
2-(2-METHYL-4-CHLOROPHOXY)PROPIONIC ACID (MCPP)	93652	3.65E+01	N	2.04E+03	N Ing		7.82E+01	N Ing	
METHYLENE BROMIDE (DIBROMOMETHANE)	74953	6.08E+01	N	2.04E+04	N Ing		7.82E+02	N Ing	
METHYLENE CHLORIDE (DICHLOROMETHANE)	75092	5.00E+00	MCL	2.19E+01	C Inh	1	1.43E+01	C Inh	1
4,4'-METHYLENE BIS(2-CHLOROANILINE)	101144	5.15E-01	C	4.40E+01	C Ing		4.91E+00	C Ing	
4,4'-METHYLENE BIS(N,N-DIMETHYL)ANILINE	101611	1.46E+00	C	1.24E+02	C Ing		1.39E+01	C Ing	
METHYL ETHYL KETONE (2-BUTANONE)	78933	1.91E+03	N R	8.45E+01	N Inh	1	8.45E+01	N Inh	1
METHYL HYDRAZINE	60344	6.09E-02	C	5.20E+00	C Ing		5.81E-01	C Ing	
METHYL ISOBUTYL KETONE (4-METHYL-2-PENTANONE)	108101	1.39E+02	N	1.63E+05	N Ing		6.26E+03	N Ing	
METHYL METHACRYLATE	80626	1.42E+03	N	1.63E+04	N Ing		1.63E+04	N Ing	
2-METHYLNAPHTHALENE	91576	1.22E+02	N	4.09E+04	N Ing		1.56E+03	N Ing	
2-METHYL-5-NITROANILINE	99558	2.03E+00	C	1.73E+02	C Ing		1.94E+01	C Ing	
METHYL PARATHION	298000	9.13E+00	N	4.08E+02	N Ing		1.96E+01	N Ing	
2-METHYLPHENOL (o-CRESOL)	95487	1.83E+03	N	1.02E+05	N Ing		3.91E+03	N Ing	
3-METHYLPHENOL (m-CRESOL)	108394	1.83E+03	N	1.02E+05	N Ing		3.91E+03	N Ing	
4-METHYLPHENOL (p-CRESOL)	106445	1.83E+02	N	1.02E+04	N Ing		3.91E+02	N Ing	
METHYLSTYRENE MIX	25013154	5.48E+01	N	1.23E+03	N Ing		4.69E+02	N Ing	
ALPHA-METHYLSTYRENE	98839	4.26E+02	N	1.43E+05	N Ing		5.48E+03	N Ing	
METHYL TERT BUTYL ETHER (MTBE)	1634044	4.00E+01	H	8.74E+03	Csat		3.91E+03	N Ing	
METHYL TRIBROMIDE (BROMOFORM)	75252	8.48E+00	C R	9.01E+01	C Inh	1	5.88E+01	C Inh	1

**MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY  
TIER 1 TRG TABLE**

CHEMICAL	CAS No.	Groundwater		Soil			
				Restricted		Unrestricted	
		ug/l	Notes	mg/kg	Notes	mg/kg	Notes
METOLACHLOR (DUAL)	51218452	5.48E+03	N	3.08E+04	N	1.17E+04	N
MIREX	2385855	7.30E+00	N	4.08E+01	N	1.56E+01	N
MOLYBDENUM	7439987	1.83E+02	N	1.02E+03	N	3.91E+02	N
MONOCHLORAMINE	10599903	3.65E+03	N	2.04E+04	N	7.82E+03	N
MONOCHLOROBENZENE (CHLOROBENZENE)	108907	1.00E+02	MCL	1.19E+00	N	1.19E+00	N
NALED	300765	7.30E+01	N	4.09E+03	N	1.56E+02	N
NAPHTHALENE	91203	6.20E+00	N	2.47E+02	N	1.94E+02	N
NICKEL	7440020	7.30E+02	N	4.08E+03	N	1.56E+03	N
NITRATE	14797558	1.00E+04	MCL	3.27E+05	N	1.25E+05	N
NITRIC OXIDE	10102439	6.08E+02	N	2.04E+05	N	7.82E+03	N
NITRITE	14797650	1.00E+03	MCL	2.04E+04	N	7.82E+03	N
2-NITROANILINE	88744	4.17E-01	N	4.92E-01	N	4.92E-01	N
NITROBENZENE	99953	3.53E+00	N	8.41E+00	N	8.41E+00	N
NITROFURANTOIN	67209	2.56E+03	N	1.43E+05	N	5.48E+03	N
NITROFURAZONE	59870	4.46E-02	C	3.82E+00	C	4.26E-01	C
NITROGEN DIOXIDE	10102440	6.08E+03	N	2.04E+06	N	7.82E+04	N
NITROGLYCERIN	55630	4.78E+00	C	4.09E+02	C	4.56E+01	C
2-NITROPHENOL	88755	4.16E-01	N				
4-NITROPHENOL	100027	2.92E+02	N	1.64E+04	N	6.26E+02	N
2-NITROPROPANE	79469	1.33E-03	C	2.38E-02	C	1.55E-02	C
N-NITROSO-DI-N-BUTYLAMINE	924163	1.89E-03	C	1.06E+00	C	1.18E-01	C
N-NITROSOETHANOLAMINE	1116547	2.39E-02	C	2.04E+00	C	2.28E-01	C
N-NITROSOETHYLAMINE	55185	4.46E-04	C	3.82E-02	C	4.26E-03	C
N-NITROSODIMETHYLAMINE	62759	1.31E-03	C	1.12E-01	C	1.25E-02	C
N-NITROSODIPHENYLAMINE	86306	1.37E+01	C	1.17E+03	C	1.30E+02	C
N-NITROSDIPROPYLAMINE	621647	9.57E-03	C	8.18E-01	C	9.12E-02	C
N-NITROSO-N-ETHYLUREA	759739	4.78E-04	C	4.09E-02	C	4.56E-03	C
N-NITROSO-N-METHYLETHYLAMINE	10595956	3.04E-03	C	2.60E-01	C	2.90E-02	C
N-NITROSPYRROLIDINE	930552	3.19E-02	C	2.73E+00	C	3.04E-01	C
M-NITROTOLUENE	99081	6.08E+01	N	2.04E+04	N	7.82E+02	N
O-NITROTOLUENE	88722	6.08E+01	N	2.04E+04	N	7.82E+02	N
P-NITROTOLUENE	99990	6.08E+01	N	2.04E+04	N	7.82E+02	N
NUSTAR	85509199	2.56E+01	N	1.43E+03	N	5.48E+01	N
1,2,3,4,6,7,8,9-OCTACHLORODIBENZOFURAN (OCDF)	39001020	4.46E-04	C	3.82E-02	C	4.26E-03	C
1,2,3,4,6,7,8,9-OCTACHLORODIBENZO-P-DIOXIN (OCDD)	3268879	4.46E-04	C	3.82E-02	C	4.26E-03	C
ORYZALIN	19044883	1.83E+03	N	1.02E+05	N	3.91E+03	N
OXADIAZON	19666309	1.83E+02	N	1.02E+04	N	3.91E+02	N
OXAMYL	23135220	2.00E+02	MCL	5.11E+04	N	1.96E+03	N
OXYFLUORFEN	42874033	1.10E+02	N	8.13E+03	N	2.35E+02	N
PARAQUAT DICHLORIDE	1910425	1.64E+02	N	9.20E+03	N	3.52E+02	N
PARATHION	56382	2.19E+02	N	1.23E+03	N	4.69E+02	N
PENTACHLOROBENZENE	608935	2.92E+01	N	1.63E+03	N	6.26E+01	N
1,2,3,7,8-PENTACHLORODIBENZOFURAN (PeCDF)	57117416	8.93E-06	C	7.63E-04	C	8.52E-05	C
2,3,4,7,8-PENTACHLORODIBENZOFURAN (PeCDF)	57117314	8.93E-07	C	7.63E-05	C	8.52E-06	C
1,2,3,7,8-PENTACHLORODIBENZO-P-DIOXIN (PeCDD)	40321764	8.93E-07	C	7.63E-05	C	8.52E-06	C
PENTACHLORONITROBENZENE	82688	2.58E-01	C	2.20E+01	C	2.46E+00	C
PENTACHLOROPHENOL	87865	1.00E+00	MCL	2.38E+01	N	2.68E+00	C
PERCHLOROETHENE (TETRACHLOROETHENE) (PCE)	127184	5.00E+00	MCL	1.82E+01	C	1.19E+01	C
PERMETHRIN	52645531	1.83E+03	N	1.02E+05	N	3.91E+03	N
PHENANTHRENE	85018	1.10E+03	N	6.13E+04	N	2.35E+03	N
PHENOL	108952	2.19E+04	N	1.23E+05	N	4.69E+04	N
M-PHENYLENEDIAMINE	108452	2.19E+02	N	1.23E+04	N	4.69E+02	N
O-PHENYLENEDIAMINE	95545	1.42E+00	C	1.22E+02	C	1.36E+01	C
P-PHENYLENEDIAMINE	106503	6.94E+03	N	3.88E+05	N	1.49E+04	N
2-PHENYLPHENOL	90437	3.45E+01	C	2.95E+03	C	3.29E+02	C
PHOSPHINE	7803512	5.92E-01	N	6.13E+01	N	2.35E+01	N
PHOSPHORIC ACID	7664382	2.09E+01	N	5.72E+34	C	6.39E+33	C
PHOSPHORUS (WHITE)	7723140	7.30E-01	N	4.09E+01	N	1.56E+00	N
P-PHTHALIC ACID	100210	3.65E+04	N	2.04E+05	N	7.82E+04	N
PHthalic Anhydride	85449	7.30E+04	N	4.08E+05	N	1.56E+05	N
POLYBROMINATED BIPHENYLS (PBBS)	1336363	7.52E-03	C	6.43E-01	C	7.18E-02	C
POLYCHLORINATED BIPHENYLS (PCBs)	12674112	9.57E-01	C	1.00E+01	C	1.00E+00	C
AROCLOR-1016	11104282	3.35E-02	C	1.00E+01	C	1.00E+00	C
AROCLOR-1221	11141165	3.35E-02	C	1.00E+01	C	1.00E+00	C
AROCLOR-1232	53469219	3.35E-02	C	1.00E+01	C	1.00E+00	C
AROCLOR-1242	12672296	3.35E-02	C	1.00E+01	C	1.00E+00	C
AROCLOR-1248	11097691	3.35E-02	C	1.00E+01	C	1.00E+00	C
AROCLOR-1254	11096825	3.35E-02	C	1.00E+01	C	1.00E+00	C
AROCLOR-1260	61788338	1.49E-02	C	1.27E+00	C	1.42E-01	C
POLYCHLORINATED TERPHENYLS				Ing			

**MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY  
TIER 1 TRG TABLE**

CHEMICAL	CAS No.	Groundwater		Soil			
				Restricted		Unrestricted	
		ug/l	Notes	mg/kg	Notes	mg/kg	Notes
POLYNUCLEAR AROMATIC HYDROCARBONS:							
ACENAPHTHENE	83329	3.65E+02	N R	1.23E+05	N Ing	4.69E+03	N Ing
ACENAPHTHYLENE	208968	2.19E+03	N	1.23E+05	N Ing	4.69E+03	N Ing
ANTHRACENE	120127	4.34E+01	Csol	6.13E+05	N Ing	2.35E+04	N Ing
BENZ[AJ]ANTHRACENE	56553	9.17E-02	C R	7.84E+00	C Ing	8.75E-01	C Ing
BENZO[AI]PYRENE	50328	2.00E-01	MCL	7.84E-01	C Ing	8.75E-02	C Ing
BENZO[BIFLUORANTHENE	205992	9.17E-02	C R	7.84E+00	C Ing	8.75E-01	C Ing
BENZO[G,H,I]PERYLENE	191242	1.10E+03	N	6.13E+04	N Ing	2.35E+03	N Ing
BENZO[K]FLUORANTHENE	207089	9.17E-01	C R	7.84E+01	C Ing	8.75E+00	C Ing
CHRYSENE	218019	9.17E+00	C R	7.84E+02	C Ing	8.75E+01	C Ing
DIBENZA[A,H]ANTHRACENE	53703	9.17E-03	C R	7.84E-01	C Ing	8.75E-02	C Ing
FLUORANTHENE	206440	1.46E+03	N R	8.17E+04	N Ing	3.13E+03	N Ing
FLUORENE	86737	2.43E+02	N R	8.17E+04	N Ing	3.13E+03	N Ing
INDENO[1,2,3-C,D]PYRENE	193395	9.17E-02	C R	7.84E+00	C Ing	8.75E-01	C Ing
2-METHYLNAPHTHALENE	91576	1.22E+02	N	4.09E+04	N Ing	1.56E+03	N Ing
NAPHTHALENE	91203	6.20E+00	N R	2.47E+02	N Inh	1 1.94E+02	N Inh 1
PHENANTHRENE	85018	1.10E+03	N	6.13E+04	N Ing	2.35E+03	N Ing
PYRENE	129000	1.83E+02	N R	6.13E+04	N Ing	2.35E+03	N Ing
POTASSIUM CYANIDE	151508	1.83E+03	N	1.02E+04	N Ing	3.91E+03	N Ing
POTASSIUM SILVER CYANIDE	506616	7.30E+03	N	4.08E+04	N Ing	1.56E+04	N Ing
PROMETON	1610180	5.48E+02	N	3.07E+04	N Ing	1.17E+03	N Ing
PROMETRYN	7287196	1.46E+02	N	8.18E+03	N Ing	3.13E+02	N Ing
PROPACHLOR	1918167	4.75E+02	N	2.65E+04	N Ing	1.02E+03	N Ing
PROPANIL	709988	1.83E+02	N	1.02E+04	N Ing	3.91E+02	N Ing
PROPARGITE	2312358	7.30E+02	N	4.09E+04	N Ing	1.56E+03	N Ing
N-PROPYLBENZENE	103651	2.43E+02	N R	4.90E+02	Csat	4.90E+02	Csat
PROPYLENE GLYCOL	57556	7.30E+05	N	6.13E+06	N Ing	1.56E+06	N Ing
PROPYLENE GLYCOL, MONOETHYL ETHER	52125538	2.56E+04	N	1.43E+06	N Ing	5.48E+04	N Ing
PROPYLENE GLYCOL, MONOMETHYL ETHER	107982	2.56E+04	N	1.43E+06	N Ing	5.48E+04	N Ing
PURSUIT	81335775	9.13E+03	N	5.11E+05	N Ing	1.96E+04	N Ing
PYRENE	129000	1.83E+02	N R	6.13E+04	N Ing	2.35E+03	N Ing
PYRIDINE	110861	3.65E+01	N	2.04E+03	N Ing	7.82E+01	N Ing
QUINOLINE	91225	5.58E-03	C	4.77E-01	C Ing	5.32E-02	C Ing
RDX (CYCLONITE)	121824	6.09E-01	C	5.20E+01	C Ing	5.81E+00	C Ing
RESMETHRIN	10453868	1.10E+03	N	6.13E+04	N Ing	2.35E+03	N Ing
RONNEL	299843	1.83E+03	N	1.02E+04	N Ing	3.91E+03	N Ing
ROTONONE	83794	1.46E+02	N	8.18E+03	N Ing	3.13E+02	N Ing
SELENIOUS ACID	7783008	1.83E+02	N	1.02E+03	N Ing	3.91E+02	N Ing
SELENIUM	7782492	5.00E+01	MCL	1.02E+03	N Ing	3.91E+02	N Ing
SILVER	7440224	1.83E+02	N MCL	1.02E+03	N Ing	3.91E+02	N Ing
SILVER CYANIDE	506649	3.65E+03	N	2.04E+04	N Ing	7.62E+03	N Ing
SIMAZINE	122349	4.00E+00	MCL	4.77E+01	C Ing	5.32E+00	C Ing
SODIUM AZIDE	26628228	1.46E+02	N	8.18E+03	N Ing	3.13E+02	N Ing
SODIUM DIETHYLDITHIOCARBAMATE	148185	2.48E-01	C	2.12E+01	C Ing	2.37E+00	C Ing
SODIUM CYANIDE	143339	1.46E+03	N	8.17E+03	N Ing	3.13E+03	N Ing
STRONTIUM, STABLE	7440246	2.19E+04	N	1.23E+05	N Ing	4.69E+04	N Ing
STRYCHNINE	57249	1.10E+01	N	6.13E+02	N Ing	2.35E+01	N Ing
STYRENE	100425	1.00E+02	MCL	3.84E+02	N Inh	1 3.84E+02	N Inh 1
2,3,7,8-TETRACHLORODIBENZOFURAN (TCDF)	51207319	4.46E-06	C	3.82E-04	C Ing	4.26E-05	C Ing
2,3,7,8-TETRACHLORODIBENZO-P-DIOXIN (TCDD)	1746016	3.00E-05	MCL	3.82E-05	C Ing	4.26E-06	C Ing
1,2,4,5-TETRACHLOROBENZENE	95943	1.10E+01	N	6.13E+02	N Ing	2.35E+01	N Ing
1,1,1,2-TETRACHLOROETHANE	630206	4.06E-01	C	2.20E+02	C Ing	2.46E+01	C Ing
1,1,2,2-TETRACHLOROETHANE	79345	5.27E-02	C R	1.00E+00	C Inh	1 6.56E-01	C Inh 1
TETRACHLOROETHENE (PERCHLOROETHENE) (PCE)	127184	5.00E+00	MCL	1.82E+01	C Inh	1 1.19E+01	C Inh 1
2,3,4,6-TETRACHLOROPHENOL	58902	1.10E+03	N	6.13E+04	N Ing	2.35E+03	N Ing
P,A,A-TETRACHLOROTOLUENE	5216251	2.18E-03	C	2.86E-01	C Ing	3.19E-02	C Ing
TETRAETHYL LEAD	78002	3.65E-03	N	2.04E-01	N Ing	7.82E-03	N Ing
1,1,1,2-TETRAFLUOROETHANE	811972	1.67E+05	N				
TETRYL	479458	3.65E+02	N	2.04E+04	N Ing	7.82E+02	N Ing
THALLIC OXIDE	1314325	2.56E+00	N	1.43E+02	N Ing	5.48E+00	N Ing
THALLIUM	7440280	2.00E+00	MCL	1.43E+02	N Ing	5.48E+00	N Ing
THALLIUM ACETATE	563688	2.00E+00	MCL	1.84E+02	N Ing	7.04E+00	N Ing
THALLIUM CARBONATE	8533739	2.00E+00	MCL	1.63E+02	N Ing	6.26E+00	N Ing
THALLIUM CHLORIDE	7791120	2.00E+00	MCL	1.63E+02	N Ing	6.26E+00	N Ing
THALLIUM NITRATE	10102451	2.00E+00	MCL	1.84E+02	N Ing	7.04E+00	N Ing
THALLIUM SULFATE (2:1)	7446186	2.00E+00	MCL	1.63E+02	N Ing	6.26E+00	N Ing
THIOBENCARB	28249776	3.65E+02	N	2.04E+04	N Ing	7.82E+02	N Ing
THIOCYANATE		1.83E+03	N	1.02E+05	N Ing	3.91E+03	N Ing
TIN	7440315	2.19E+04	N	1.23E+05	N Ing	4.69E+04	N Ing
TITANIUM	7440326	1.46E+05	N	8.18E+06	N Ing	3.13E+05	N Ing

**MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY  
TIER 1 TRG TABLE**

CHEMICAL	CAS No.	Groundwater		Soil			
				Restricted		Unrestricted	
		ug/l	Notes	mg/kg	Notes	mg/kg	Notes
TITANIUM DIOXIDE	13463677	1.46E+05	N	8.18E+06	N	3.13E+05	N
TOLUENE	108883	1.00E+03	MCL	3.80E+01	N	3.80E+01	N
TOLUENE-2,4-DIAMINE	95807	2.09E-02	C	1.79E+00	C	2.00E-01	C
TOLUENE-2,5-DIAMINE	95705	2.19E+04	N	1.23E+05	N	4.69E+04	N
TOLUENE-2,6-DIAMINE	823405	7.30E+03	N	4.08E+04	N	1.56E+04	N
P-TOLUIDINE	106490	3.52E-01	C	3.01E+01	C	3.36E+00	C
TOTAL PETROLEUM HYDROCARBONS-GASOLINE RANGE ORGANICS (TPH-GRO)		3.50E+02	N R	3.00E+02	N	2.00E+02	N
TOTAL PETROLEUM HYDROCARBONS-DIESEL RANGE ORGANICS (TPH-DRO)		6.50E+02	N R	3.50E+02	Csat	3.00E+02	N
TOXAPHENE	8001352	3.00E+00	MCL	5.20E+00	C	5.81E-01	C
1,2,4-TRIBROMOBENZENE	615543	1.83E+02	N	1.02E+04	N	3.91E+02	N
TRIBUTYL TIN OXIDE	56359	1.10E+01	N	6.13E+02	N	2.35E+01	N
2,4,6-TRICHLOROANILINE	634935	1.97E+00	C	1.68E+02	C	1.88E+01	C
1,2,4-TRICHLOROBENZENE	120821	7.00E+01	MCL	8.24E+02	N	7.82E+02	N
1,1,1-TRICHLOROETHANE	71556	2.00E+02	MCL	1.19E+03	Csat	1.19E+03	Csat
1,1,2-TRICHLOROETHANE	79005	5.00E+00	MCL	1.67E+00	C	1.09E+00	C
TRICHLOROETHENE (TCE)	79016	5.00E+00	MCL	7.92E+00	C	5.17E+00	C
TRICHLOROFLUOROMETHANE	75694	1.29E+03	N	1.43E+05	N	2.35E+04	N
2,4,5-TRICHLOROPHENOL	95954	3.65E+03	N R	2.04E+05	N	7.82E+03	N
2,4,6-TRICHLOROPHENOL	88062	6.09E+00	C R	3.14E+02	C	5.81E+01	C
2,4,5-TRICHLOROPHOXYACETIC ACID (2,4,5-T)	93765	3.65E+02	N	2.04E+04	N	7.82E+02	N
2-(2,4,5-TRICHLOROPHOENOXY)PROPIONIC ACID (2,4,5-T SILVEX)	93721	5.00E+01	MCL	1.63E+03	N	6.26E+02	N
1,1,2-TRICHLOROPROPANE	598776	3.04E+01	N	1.02E+04	N	3.91E+02	N
1,2,3-TRICHLOROPROPANE	96184	6.23E-03	C	8.18E-01	C	9.12E-02	C
1,2,3-TRICHLOROPROPENE	96195	3.04E+01	N	1.02E+03	N	3.91E+02	N
1,1,2-TRICHLORO-1,2,2-TRIFLUOROETHANE	76131	5.94E+04	N	6.13E+05	N	6.13E+05	N
1,2,4-TRIMETHYLBENZENE	95636	1.23E+01	N	1.02E+05	N	3.91E+03	N
1,3,5-TRIMETHYLBENZENE	108678	1.23E+01	N R	4.36E+02	Csat	4.36E+02	Csat
TRIMETHYL PHOSPHATE							
1,3,5-TRINITROBENZENE	512561	1.81E+00	C	1.55E+02	C	1.73E+01	C
2,4,6-TRINITROTOLUENE	99354	1.10E+03	N	1.02E+02	N	1.02E+02	N
URANIUM (SOLUBLE SALTS)	118967	2.23E+00	C	1.02E+02	N	2.13E+01	C
VANADIUM							
VANADIUM PENTOXIDE	7440622	2.56E+02	N	1.43E+03	N	5.48E+02	N
VANADIUM SULFATE	1314621	3.29E+02	N	1.84E+03	N	7.04E+02	N
VINCLOZOLIN	16785812	7.30E+02	N	4.08E+03	N	1.56E+03	N
VINYL ACETATE	50471448	9.13E+02	N	5.11E+04	N	1.96E+03	N
VINYL BROMIDE (BROMOETHENE)	108054	4.12E+02	N R	9.13E+00	N	9.13E+00	N
VINYL CHLORIDE (CHLOROETHENE)	593602	1.12E-01	C R	1.26E-01	N	1.26E-01	N
WARFARIN	75014	2.00E+00	MCL	9.39E-01	C	4.26E-01	C
M-XYLENE	91812	1.10E+01	N	6.13E+01	N	2.35E+01	N
O-XYLENE	108383	1.22E+04	N R	4.18E+02	Csat	4.18E+02	Csat
P-XYLENE	95476	1.22E+04	N R	4.13E+02	Csat	4.13E+02	Csat
XYLEMES	106423	1.22E+04	N R	4.61E+02	Csat	4.61E+02	Csat
ZINC	1330207	1.00E+04	MCL	3.18E+02	Csat	3.18E+02	Csat
ZINC CYANIDE	7440686	1.10E+04	N	6.13E+04	N	2.35E+04	N
ZINC PHOSPHIDE	557211	1.83E+03	N	1.02E+04	N	3.91E+03	N
ZINEB	1314847	1.10E+01	N	6.13E+02	N	2.35E+01	N
	12122677	1.83E+03	N	1.02E+04	N	3.91E+03	N

## NOTES:

C = Carcinogenic effects as to the identification of appropriate TRG

N = Noncarcinogenic effects as to the identification of appropriate TRG

H = EPA Health Advisory

Csat = Soil Saturation Concentration

Csol = Aqueous Solubility Concentration - For mixtures of chemicals (e.g., gasoline, diesel, etc.) the EFFECTIVE Solubility should be used.

MCL = Maximum Contaminant Level from Safe Drinking Water Act

R = Risk-based value utilizing equations developed by EPA Region III for its RBC Table.

1 = Inhalation values apply to ambient air volatilization only. Enclosed space accumulation is not addressed in the Inhalation TRGs. For such scenarios, a site-specific evaluation is required.

2 = Inhalation values apply to ambient fugitive particulates only.

3 = If both the 2,4- and 2,6- isomers of 2,4-Dinitrotoluene are detected at a site, then the TRG for Dinitrotoluene Mixture must be met. If only one or the other isomer is detected, then the isomer specific value can be applied.

4 = According to "Revised Interim Soil Lead Guidance for CERCLA Sites and RCRA Corrective Action Facilities," OSWER Directive #9355.4-12, July 14, 1994, Laws EP.

5 = The reference dose is for the total oral intake of manganese. As discussed in the Principal and Supporting Studies and Uncertainty and Modifying Factors Sections of IRIS, it is recommended that a modifying factor of 3 be applied.

6 = The inhalation exposure is from nickel refinery dust.

7 = For Pentachlorophenol, the Ingestion value has been divided in half to account for increased exposure via the dermal route.

8 = According to EPA's Federal Register June 29, 1998, "Mega Rule," PCBs (total) must not exceed 1 ppm. If PCB concentrations are reported as individual Aroclors, the sum of the individual Aroclors must not exceed 1 ppm.

9 = According to EPA's Federal Register June 29, 1998, "Mega Rule," PCBs (total) must not exceed 10 ppm provided BOTH institutional and engineering controls are in place for a high occupancy site. Concentrations above the restricted level require a Tier 2 Risk Evaluation and the use of low occupancy criteria must be approved by MDEQ. All institutional and engineering controls must be consistent with the EPA "Mega Rule." If PCB concentrations are reported as individual Aroclors, the sum of the individual Aroclors must not exceed 10 ppm.

## ATTACHMENT 10

Bid Specifications  
V.A. Gulfcoast Veterans Health Care System,  
200 East Beach Boulevard  
Gulfport, Mississippi



5118 N 56<sup>th</sup> Street, Tampa, Florida 33610

Tel: (813) 626-8156 Fax: (813) 623-6702

Website: [www.ohcnet.com](http://www.ohcnet.com)

January 9, 2009

**Re: Bid Specifications for excavation, transport and disposal of selected excavated material, and backfill for areas in the Vicinity of B-45/B-117, B-6, B-61, B-32, and a former Electrical Vault in the vicinity of B-6, V.A. Gulfcoast Veterans Health Care System, 200 East Beach Boulevard, Gulfport, Mississippi**

## **1.0 Project Background**

OHC has performed several phases of environmental investigations since September 2007 at the V.A. Gulfcoast Veterans Health Care System located at 200 East Beach Boulevard, Gulfport, Mississippi (**Figure 1**). During the course of these investigations, soil analytical data indicated concentrations of polycyclic aromatic hydrocarbons (PAHs) in excess of Mississippi Department of Environmental Quality (MDEQ) defined limits in the areas of B-45/B-117, B-6, B-61, B-32, and a former Electrical Vault in the vicinity of B-6 in the southern portion of the facility.

**Figures 19 through 22, and Figure 26** show the extents and dimensions of the impacted areas. Based on these figures and the information provided, the total estimated volumes of the impacted areas are as follows:

- |              |                 |
|--------------|-----------------|
| • B-45/B-117 | 628 cyds        |
| • B-32       | 157 cyds        |
| • B-6        | 279 cyds        |
| • B-61       | 436 cyds        |
| • EV (B-6)   | <u>157 cyds</u> |

Total            **1,657 cyds**

## 2.0 Scope of Work

It is the V.A.'s intent to excavate this material (approximately 1,657 cyds), transport the material to a licensed facility (e.g., landfill, or burn facility), confirm that all contaminated material has been removed and properly disposed, and then backfill all of the excavated areas. The Contractor shall provide all necessary supervision, equipment and personnel to perform the scope of work described within this document in a target period of 10 business days or alternate proposed agreed upon schedule. Local Ordinance specifies that work can only be conducted between the hours of 7:00 AM to 9:00 PM for all seven days of the week. All equipment shall be supplied in good working order, properly maintained throughout the course of this project, and will be sufficient in size and capability to perform the Scope of Work within the specified or negotiated duration of work schedule.

### 2.1 Site Emergency Plan

The contractor shall provide a Site Emergency Plan (SEP) detailing what actions to be taken to secure the site, secure or demobilize equipment materials, and personnel in the event of a Hurricane, Tropical Storm Warning, or any specific natural or man made disaster that might possibly impact the project. Contractor will also prepare and maintain a Site Specific Health and Safety Plan and will be responsible for the safety of its own employees and subcontractors in the performance of work at this facility.

### 2.2 Site Preparation

Contractor shall provide all public and all emergency public services notification as required by local ordinances.

The contractor will prepare a Controlled work site including temporary fencing, 24 hr security (with lighting and security personnel during night time hours). Entry and exiting the site shall be controlled through man-way gates in the fencing that are monitored during work shifts and remain locked during non-working hours.

Contractor shall install erosion control and surface drainage control surrounding the work area (e.g., silt fence that will prevent runoff to adjacent street areas and booms across nearby drainage structures). In addition, contractor shall implement dust control (e.g., spraying the surface utilizing water trucks).

Contractor shall limit noise to 85 decibels or less at the property line, and limit detectable and noticeable vibration beyond the property line.

#### 2.3 Traffic Control

Gulfport Police Department Traffic Division has no specific requirements for traffic control. However, the Police Department has requested that truck traffic obey local speed limits.

#### 2.4 Dewatering

The depth to groundwater was observed at approximately 6 ft during previous investigations. Seasonal variations, tidal influences, local topography, and rainfall events may also influence the depth to water in these areas. Therefore, dewatering if deemed necessary, will be performed in accordance with all applicable permitting (e.g. Local, State, NPDES, etc.) and sampling requirements to monitor discharged water will be the responsibility of the contractor.

#### 2.5 Excavation

Contractor shall excavate the impacted areas under technical supervision of OHC personnel. OHC will direct the extent of excavations based on field observations, including environmental screening and confirmation sampling activities. Backfilling will be conducted following receipt of confirmation sampling results which confirm that all impacted soil has been removed. Else, additional excavation and confirmation sampling may be conducted until it is verified that all contaminated soil has been removed, then the area will be backfilled.

#### 2.6 Stockpiling

Contractor shall prepare bermed areas lined with double layer 6 mil visquene capable of containing the volume of excavated material stockpiled upon it. Material will be stockpiled within the bermed areas. All stock piling activity shall be in accordance to local and state regulations, including but not limited to area and height, noise, dust control, etc. Materials left overnight or during rainfall events shall be covered with a secured single layer of 6 ml visquene material.

#### 2.7 Sampling Process

OHC shall observe soil in the excavation and collect screening soil samples during the course of excavation at various depths and locations to

determine whether additional excavation is necessary in either vertical or horizontal directions. Confirmation samples will be collected to verify the observation and/or screening results. Confirmation soil samples will be submitted to the laboratory on a 48 hr turn around time (24 hrs for shipping to the laboratory and 24 hrs for laboratory analysis). Contractor shall allow OHC personnel uncontrolled access to the excavation to collect these samples and may be asked to collect material using excavation equipment from which OHC will collect samples.

#### 2.8 Disposal

OHC will provide all chemical profile information to the excavation contractor's designated disposal facility and will collect pre-burn samples prior to excavation if necessary. Contactor shall provide transportation and disposal of excavated material by licensed waste haulers to licensed facilities, respectively. Contactor shall sign all manifests and provide copies of the final manifests (i.e., with signature from the receiving facility) and weight tickets to OHC within 48 hours following receipt.

#### 2.9 Backfill and Compaction

Upon verification that a particular area has been sufficiently excavated; OHC shall give final clearance to the contractor in writing to begin backfilling that specific area. No backfilling shall be performed without written clearance forms signed by the OHC project manager at site. Contactor shall backfill the excavated area with sufficient clean backfill fill to restore excavated areas to grade. Clean backfill will be standard Number 5 B-Borrow. Backfilled material shall be placed in 18" lifts and compacted. Compaction of the lifts should be at minimum 90%. It is also understood that the intended future purpose of this area is not currently known. It will be the responsibility of the builder at the time of design to perform geotechnical testing and prepare the soils in the area accordingly. The surface shall be covered with like material as existed before excavation. It is noted that some shrinkage and settling may occur over time.

#### 2.10 Demobilization and Customer Release

Following excavation and backfilling operations, contractor shall remove all materials, trash, equipment, etc. to restore the site as much as practicable to pre-excavation conditions or better. The work will not be considered complete until this is verified and released in writing by the owner/customer.

## 2.11 Force Majeure

No Party shall be liable for any failure to perform its obligations where such failure is as a result of Acts of Nature (including fire, flood, earthquake, storm, hurricane or other natural disaster), war, invasion, act of foreign enemies, hostilities (whether war is declared or not), civil war, rebellion, revolution, insurrection, military or usurped power or confiscation, terrorist activities, nationalization, government sanction, blockage, embargo, labor dispute, strike, lockout or interruption or failure of electricity [or telephone service], and no other Party will have a right to terminate this Agreement in such circumstances."

Work shall commence following approval of the Department of Veterans Affairs, Mississippi Department of Environmental Quality, and mutually agreed schedules of the Excavation Contractor and OHC. If the contractor believes that the scope of services will take more than two weeks to accomplish, then adjustment of the duration specification will be considered and adjusted accordingly.

### Additional Requirements

Contractor must be experienced in performing excavation, licensed, and insured to perform the above scope of work.

Contractor must demonstrate that all personnel involved in field operations have the appropriate OSHA HAZWOPPER training and is current in all annual refresher requirements per Title 29 CFR 1910.120.


If there are any further questions, comments or concerns, feel free to contact me at (813) 626-8156 or mcross@ohcnet.com.


Sincerely,  
**OHC Environmental Engineering**




Michael Cross, P.G.  
Project Manager

## FIGURES







● Proposed location  
of Monitor Well  
following excavation.

Scale 1 inch = 50 feet

Figure 20. Benzo (a) Pyrene Concentrations in the Groundwater at Former B-45/B-117,  
VA Medical Center  
200 East Beach Boulevard  
Gulfport, Mississippi  
OHC Project No. 070103-EA4



October 2007 - April 2008




Figure 21. Chrysene and Benzo(a)pyrene Concentrations in the Soil at Former B-32  
VA Medical Center  
200 East Beach Boulevard  
Gulfport, Mississippi  
OHC Project No. 070103-EA4



B-6


$$V = \pi r^2 h$$

$$r = 20'$$

$$h = 6'$$

$$V = \pi (20)^2 6 = 7,536 \text{ ft}^3 / 27$$

$$= \underline{\underline{279 \text{ yd}^3}}$$

B61


$$V = \pi r^2 h$$

$$r = 25'$$

$$h = 6'$$

$$V = \pi (25)^2 6 = 11,775 \text{ ft}^3 / 27$$

$$= \underline{\underline{436 \text{ yd}^3}}$$

KEY:

- Direct Push Soil Sample Location

1.49 Benzo (b) Flouanthene  
concentration in mg/Kg

0.42 mg/Kg Benzo (b) Flouanthene  
isocon dashed where inferred

NS Not Sampled for this Analyte

Scale 1 inch = 33 feet






Figure 26. Background Arsenic Sample Locations & Location of Electrical Vault  
VA Medical Center  
200 East Beach Boulevard  
Gulfport, Mississippi  
OHC Project No. 070103-EA4

October 2007 - April 2008



